

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Huey P Stockstill, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$16,903,030.85					\$17,410,491.16	\$18,453,054.42	\$19,757,785.83
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS	18,700.00	21,594.40	18,000.00
0020	201-B001	Clearing and Grubbing	1.000	ACRE	15,600.00	11,114.00	18,000.00
0030	202-B006	Removal of Asphalt Paved Shoulders, All Depths	2,149.000	SY	19.75	19.00	19.00
0040	202-B007	Removal of Asphalt Pavement, All Depths	4,720.000	SY	23.75	22.17	13.50
0050	202-B052	Removal of Concrete Driveways, All Depths	1,160.000	SY	29.50	33.25	13.50
0060	202-B059	Removal of Concrete Median & Island Pavement, All Depths	157.000	SY	57.00	42.36	13.50
0070	202-B063	Removal of Concrete Paved Ditch	328.000	SY	62.00	20.28	13.50
0080	202-B073	Removal of Concrete Pavement, All Depths	9,030.000	SY	27.25	20.46	19.00
0090	202-B089	Removal of Curb &/or Curb and Gutter, All Types	1,769.000	LF	22.25	22.17	19.00
0100	202-B090	Removal of Curb Inlet	1.000	EA	2,640.00	890.88	7,000.00
0110	202-B092	Removal of Curb, All Types	1,410.000	LF	22.25	22.17	25.00
0120	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	619.000	LF	10.50	10.06	10.00
0130	202-B170	Removal of Junction Box	2.000	EA	340.00	224.25	240.00
0140	202-B178	Removal of Low Mast Lighting Assembly and Foundation	2.000	EA	2,810.00	592.25	600.00
0150	202-B191	Removal of Pipe, 8" And Above	6.000	LF	20.75	17.00	125.00
0160	202-B240	Removal of Traffic Stripe	19,670.000	LF	3.55	3.45	3.50
0170	202-B251	Removal of Underground Electric Wire	1,680.000	LF	1.35	1.32	1.25
0180	203-A001	Unclassified Excavation, FM, AH	4,965.000	CY	28.00	20.46	35.00
0190	203-EX017	Borrow Excavation, AH, FME, Class B7	29,847.000	CY	28.25	27.77	38.00
0200	206-A001	Structure Excavation	575.000	CY	28.25	22.22	63.00
0210	209-A005	Geotextile Stabilization, Type V, Non-Woven	15,744.000	SY	4.00	4.70	5.40
0220	211-B001	Topsoil for Slope Treatment, Contractor Furnished	3,411.000	CY	0.01	15.99	44.00
0230	213-C001	Superphosphate	7.000	TON	1,420.00	1,380.00	1,400.00
0240	216-A001	Solid Sodding	3,360.000	SY	6.60	6.15	12.00
0250	217-A001	Ditch Liner	847.000	SY	3.05	2.93	3.00
0260	219-A001	Watering	78.000	KGAL	20.00	20.00	20.00

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Huey P Stockstill, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$16,903,030.85					\$17,410,491.16	\$18,453,054.42	\$19,757,785.83
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	220-A001	Insect Pest Control	14.000	ACRE	30.00	30.00	30.00
0280	221-A001	Concrete Paved Ditch	234.000	CY	1,130.00	1,150.00	1,000.00
0290	223-A001	Mowing	14.000	ACRE	50.00	50.00	50.00
0300	225-A001	Grassing	14.000	ACRE	987.00	920.00	1,000.00
0310	225-B001	Agricultural Limestone	6.000	TON	812.00	805.00	800.00
0320	225-C001	Mulch, Vegetative Mulch	25.000	TON	848.00	833.75	800.00
0330	226-A001	Temporary Grassing	14.000	ACRE	1,670.00	1,610.00	1,600.00
0340	237-A002	Wattles, 20"	13,900.000	LF	10.75	6.04	6.00
0350	239-A001	Temporary Slope Drains	732.000	LF	11.50	5.18	5.50
0360	246-B001	Rockbags	2,213.000	EA	5.35	4.89	5.00
0370	249-A001	Riprap for Erosion Control	80.000	TON	107.00	111.55	116.00
0380	403-A002	12.5-mm, MT, Asphalt Pavement	2,614.000	TON	199.00	192.63	160.00
0390	403-A003	12.5-mm, ST, Asphalt Pavement	501.000	TON	205.00	198.38	165.00
0400	403-A005	19-mm, MT, Asphalt Pavement	3,098.000	TON	211.00	204.13	170.00
0410	403-A006	19-mm, ST, Asphalt Pavement	4,236.000	TON	191.00	184.58	150.00
0420	403-A014	9.5-mm, MT, Asphalt Pavement	2,470.000	TON	192.00	185.73	150.00
0430	403-A015	9.5-mm, ST, Asphalt Pavement	376.000	TON	218.00	211.03	175.00
0440	403-B002	12.5-mm, MT, Asphalt Pavement, Leveling	679.000	TON	196.00	188.03	156.00
0450	406-D001	Fine Milling of Bituminous Pavement, All Depths	2,199.000	SY	13.00	12.65	10.00
0460	407-A001	Asphalt for Tack Coat	6,035.000	GAL	6.45	6.32	5.00
0470	423-A001	Rumble Strips, Ground In	1.000	MI	340.00	18,687.50	4,500.00
0480	503-C010	Saw Cut, Full Depth	1,670.000	LF	23.50	8.05	11.00
0490	601-B001	Class "B" Structural Concrete, Minor Structures	110.000	CY	2,920.00	3,081.88	2,500.00
0500	602-A001	Reinforcing Steel	9,498.000	LBS	3.50	5.18	3.00
0510	603-CA012	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	648.000	LF	104.00	106.98	103.00
0520	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	296.000	LF	119.00	128.50	130.00

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Huey P Stockstill, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$16,903,030.85					\$17,410,491.16	\$18,453,054.42	\$19,757,785.83
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0530	603-CA041	30" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	80.000	LF	157.00	185.49	160.00
0540	603-CA056	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	96.000	LF	208.00	239.24	180.00
0550	603-CB003	18" Reinforced Concrete End Section	3.000	EA	1,500.00	1,606.71	2,000.00
0560	603-CB004	24" Reinforced Concrete End Section	5.000	EA	1,580.00	2,309.55	2,500.00
0570	603-CB005	30" Reinforced Concrete End Section	3.000	EA	3,680.00	2,769.09	3,000.00
0580	603-CB006	36" Reinforced Concrete End Section	2.000	EA	2,530.00	3,636.41	4,000.00
0590	603-CE003	22" x 13" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	24.000	LF	119.00	271.58	167.00
0600	603-CE009	29" x 18" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	424.000	LF	138.00	218.05	230.00
0610	604-A001	Castings	1,817.000	LBS	5.20	5.10	13.00
0620	604-B001	Gratings	300.000	LBS	5.20	7.93	44.00
0630	606-B001	Guard Rail, Class A, Type 1	113.000	LF	59.50	57.50	58.00
0640	606-D022	Guard Rail, Bridge End Section, Type 1	3.000	EA	5,580.00	5,405.00	5,400.00
0650	606-E007	Guard Rail, Terminal End Section, Non-Flared	3.000	EA	5,460.00	5,290.00	5,300.00
0660	608-A001	Concrete Sidewalk, Without Reinforcement	2,085.000	SY	79.25	77.05	80.00
0670	609-B003	Concrete Curb, Special Design	1,157.000	LF	41.50	40.25	40.00
0680	609-C001	Concrete Integral Curb, Type 1	811.000	LF	41.50	40.25	40.00
0690	609-D003	Combination Concrete Curb and Gutter Type 2	190.000	LF	41.25	40.25	40.00
0700	609-D009	Combination Concrete Curb and Gutter Type 3A Mod1	8,511.000	LF	38.00	36.80	35.00
0710	614-A001	Concrete Driveway, Without Reinforcement	1,378.000	SY	142.00	138.00	144.00
0720	616-A001	Concrete Median and/or Island Pavement, 10-inch	308.000	SY	140.00	138.00	144.00
0730	616-A004	Concrete Median and/or Island Pavement, 4-inch	2,054.000	SY	78.75	77.05	80.00
0740	617-A001	Right-of-Way Marker	10.000	EA	416.00	517.50	350.00
0750	618-A001	Maintenance of Traffic	1.000	LS	1,137,000.00	1,198,130.81	1,700,000.00
0760	619-A1001	Temporary Traffic Stripe, Continuous White	6.000	MI	2,380.00	2,300.00	2,400.00
0770	619-A1005	Temporary Traffic Stripe, Continuous White, Type 1 Tape	2,196.000	LF	2.40	2.30	2.25
0780	619-A2001	Temporary Traffic Stripe, Continuous Yellow	6.000	MI	2,380.00	2,300.00	2,400.00

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Huey P Stockstill, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$16,903,030.85					\$17,410,491.16	\$18,453,054.42	\$19,757,785.83
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0790	619-A2006	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	2,196.000	LF	2.40	2.30	2.38
0800	619-A3002	Temporary Traffic Stripe, Skip White	2,318.000	LF	1.20	1.15	1.19
0810	619-A5001	Temporary Traffic Stripe, Detail	14,552.000	LF	0.45	0.40	0.50
0820	619-A6001	Temporary Traffic Stripe, Legend	2,303.000	SF	2.40	2.30	2.38
0830	619-A6002	Temporary Traffic Stripe, Legend	184.000	LF	3.40	3.45	3.57
0840	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	209.000	SF	20.25	19.55	10.00
0850	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,006.000	SF	20.25	19.55	10.00
0860	619-E1001	Flashing Arrow Panel, Type C	1.000	EA	4,160.00	4,025.00	1,450.00
0870	619-F1001	Concrete Median Barrier, Precast	2,620.000	LF	117.00	103.01	150.00
0880	619-F2001	Remove and Reset Concrete Median Barrier, Precast	4,360.000	LF	48.25	39.25	33.00
0890	619-G4005	Barricades, Type III, Single Faced	372.000	LF	41.50	84.24	40.00
0900	619-G5001	Free Standing Plastic Drums	210.000	EA	77.25	140.31	100.00
0910	619-G7001	Warning Lights, Type "B"	9.000	EA	178.00	221.83	120.00
0920	619-J1001	Impact Attenuator, 40 MPH	4.000	EA	13,700.00	13,225.00	12,000.00
0930	619-J2001	Impact Attenuator, 40 MPH, Replacement Package	8.000	EA	8,630.00	8,366.25	8,000.00
0940	620-A001	Mobilization	1.000	LS	1,700,000.00	1,467,036.82	1,900,000.00
0950	626-A002	6" Thermoplastic Double Drop Traffic Stripe, Skip White	1,833.000	LF	2.40	2.30	2.38
0960	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3,804.000	LF	2.40	2.30	2.38
0970	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	2,542.000	LF	2.40	2.30	2.38
0980	626-F002	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	1,039.000	LF	2.40	2.30	2.38
0990	626-G004	Thermoplastic Double Drop Detail Stripe, White	8,332.000	LF	4.75	4.60	4.76
1000	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	5,815.000	LF	4.75	4.60	4.76
1010	626-H001	Thermoplastic Double Drop Legend, White	2,303.000	SF	14.25	13.80	14.00
1020	627-K001	Red-Clear Reflective High Performance Raised Markers	114.000	EA	12.00	11.50	12.00
1030	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	32.000	EA	11.50	11.50	12.00
1040	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	200.000	SF	35.75	34.50	34.00

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Huey P Stockstill, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$16,903,030.85					\$17,410,491.16	\$18,453,054.42	\$19,757,785.83
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1050	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	106.000	SF	38.00	36.80	37.00
1060	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	111.000	SF	37.00	35.65	36.00
1070	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	161.000	SF	44.00	42.55	42.00
1080	630-C003	Steel U-Section Posts, 3.0 lb/ft	637.000	LF	23.75	23.00	23.00
1090	630-D008	Structural Steel Beams, W6 x 9	195.000	LF	108.00	104.65	105.00
1100	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	227.000	LBS	5.35	5.18	5.25
1110	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	106.000	LBS	4.00	4.03	4.00
1120	630-F006	Delineators, Guard Rail, White	9.000	EA	34.00	34.50	35.00
1130	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	2.000	EA	176.00	178.25	180.00
1140	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	2.000	EA	176.00	178.25	180.00
1150	630-K001	Welded & Seamless Steel Pipe Posts, 3 1/2"	166.000	LF	86.75	83.95	85.00
1160	630-K003	Welded & Seamless Steel Pipe Posts, 4"	18.000	LF	91.50	88.55	90.00
1170	682-A028	Underground Branch Circuit, AWG 4, 3 Conductor	490.000	LF	15.00	13.80	15.00
1180	682-A038	Underground Branch Circuit, AWG 8, 2 Conductor	160.000	LF	9.20	8.11	9.00
1190	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	4,360.000	LF	9.40	9.14	10.00
1200	682-A041	Underground Branch Circuit, AWG 8, 5 Conductor	230.000	LF	14.25	13.11	14.00
1210	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	310.000	LF	22.25	19.44	20.00
1220	682-E003	Underground Junction Box With Concrete Pad	28.000	EA	2,420.00	2,346.00	2,500.00
1230	683-B001	Lighting Assembly, Low Mast, LED, Type 15-1-0-90	28.000	EA	4,710.00	4,617.25	4,800.00
1240	684-A003	Pole Foundation, 24" Diameter	30.000	CY	1,840.00	1,782.50	1,900.00
1250	699-A001	Roadway Construction Stakes	1.000	LS	250,700.00	340,963.73	360,000.00
1260	815-A007	Loose Riprap, Size 300	80.000	TON	110.00	108.67	190.00
1270	815-E001	Geotextile under Riprap	107.000	SY	3.75	12.85	50.00
1280	907-234-A001	Temporary Silt Fence	13,400.000	LF	4.20	4.03	5.00
1290	907-234-C001	Super Silt Fence	400.000	LF	13.25	12.65	13.00
1300	907-234-D001	Inlet Siltation Guard	2.000	EA	603.00	557.75	500.00

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Huey P Stockstill, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$16,903,030.85					\$17,410,491.16	\$18,453,054.42	\$19,757,785.83
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1310	907-234-E001	Reset Inlet Siltation Guard	2.000	EA	279.00	247.25	250.00
1320	907-604-PP001	Modify Existing Inlet, Per Plans	1.000	EA	2,790.00	2,282.66	18,000.00
1330	907-608-C001	Detectable Warning Panels	126.000	SF	115.00	115.00	120.00
1340	907-609-F002	Prefabricated Curb	815.000	LF	75.25	60.00	59.00
1350	907-616-C002	Colored and Imprinted Concrete Median and Island Pavement, 12-inch Thickness	7,911.000	SF	44.75	43.70	43.00
1360	907-619-E3001	Changeable Message Sign	8.000	EA	11,900.00	11,500.00	14,500.00
1370	907-682-A1007	Branch Circuit Wire, AWG #10, 1 Conductor	310.000	LF	0.70	0.69	0.75
1380	907-682-A1018	Branch Circuit Wire, AWG #4, 1 Conductor	1,060.000	LF	2.05	1.96	2.00
1390	907-906001	Trainees	720.000	HRS	5.00	5.00	5.00
1400	304-F001	3/4" and Down Crushed Stone Base	16,650.000	TON			
1410	304-F002	Size 610 Crushed Stone Base	16,650.000	TON	83.00	86.50	90.00
1420	304-F003	Size 825B Crushed Stone Base	16,650.000	TON			
1430	907-624-A002	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White	366.000	LF			
1440	907-624-B002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White	732.000	LF			
1450	907-624-D002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow	732.000	LF			
1460	628-G001	6" High Performance Cold Plastic Traffic Stripe, Skip White	366.000	LF	9.50	9.20	9.00
1470	628-H001	6" High Performance Cold Plastic Traffic Stripe, Continuous White	732.000	LF	9.50	9.20	9.00
1480	628-J001	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow	732.000	LF	9.50	9.20	9.00
1490	202-B027	Removal of Bridge Deck, Curb and Railing	201.000	SY	1,770.00	1,725.00	1,800.00
1500	202-B275	Removal of Part of End Bent Cap, Curb, and Wingwall	54.000	SY	628.00	862.50	900.00
1510	202-B277	Removal of Part of Int. Bent Cap	24.000	SY	628.00	862.50	900.00
1520	503-C001	Saw Cut, 1-inch	1,684.000	LF	13.75	12.65	13.00
1530	608-B001	Concrete Sidewalk, With Reinforcement	564.000	SY	229.00	256.45	265.00
1540	803-D005	HP 14 x 117 Steel Piling	580.000	LF	195.00	207.00	215.00
1550	803-P001	24" Steel Pipe Piling, Wall Thickness 0.500"	1,390.000	LF	226.00	277.15	300.00
1560	804-C209	115' Prestressed Concrete Beam, Type FIB-45	1,370.000	LF	544.00	699.20	728.00

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Huey P Stockstill, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$16,903,030.85					\$17,410,491.16	\$18,453,054.42	\$19,757,785.83
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1570	804-C269	68' Prestressed Concrete Beam, Type FIB-45	808.000	LF	516.00	699.20	728.00
1580	805-A001	Reinforcement	132,840.000	LBS	2.80	2.42	3.00
1590	805-C001	Reinforcement, Corrosion Resistant	3,570.000	LBS	4.90	3.68	4.00
1600	813-A004	Concrete Railing, 36"	366.000	LF	120.00	112.70	117.00
1610	813-E007	Modified Railing	366.000	LF	814.00	972.90	1,000.00
1620	815-D001	Concrete Slope Paving	18.000	CY	2,050.00	6,325.00	7,000.00
1630	907-803-B001	Conventional Static Pile Load Test	1.000	EA	5,000.00	5,000.00	5,000.00
1640	907-803-I003	PDA Test Pile, HP Steel Pile	1.000	EA	87,600.00	57,500.00	60,000.00
1650	907-803-I004	PDA Test Pile, Steel Pipe Pile	1.000	EA	99,700.00	66,700.00	70,000.00
1660	907-803-J001	Pile Restrike	2.000	EA	2,610.00	1,150.00	1,200.00
1670	907-804-A001	Bridge Concrete, Class BDX	398.000	CY	2,080.00	3,680.00	3,800.00
1680	907-804-A002	Bridge Concrete, Class AA	141.000	CY	2,420.00	4,025.00	4,200.00
1690	907-808-A002	Joint Repair	66.000	LF	29.75	230.00	240.00
1700	907-823-A002	Preformed Joint Seal, Type II	105.000	LF	35.75	115.00	120.00