



**MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
TABLE OF CONTENTS**

**PROJECT: STBG-0054-01(061)/109246301 - Lawrence  
CRP-0054-01(063)/109274301 - Lawrence**

Section 901 - Advertisement

Section 904 - Notice to Bidders

#1	Governing Specification, w/ Supplement
#2	Status of ROW, w/ Attachments
#3	Final Cleanup
#113	Tack Coat
#296	Reduced Speed Limit Signs
#445	Mississippi Agent or Qualified Nonresident Agent
#516	Errata and Modifications to the 2017 Standard Specifications
#757	Additional Erosion Control Requirements
#1225	Early Notice to Proceed
#1226	Material Storage Under Bridges
#1241	Fuel and Material Adjustments
#1434	Erosion Control Plan
#1878	Storm Water Discharge Associated with Construction Activities ( $\geq 1$ and $< 5$ Acres)
#1963	Guardrail Pads
#2172	App for Storm Water Reports
#2206	MASH Compliant Devices
#2273	Mississippi Special Fuel Tax Law
#2782	DBE Pre-Bid Meeting
#2954	Reflective Sheeting for Signs
#3676	Asphalt Gyrotory Compactor Internal Angle Calibration
#4113	Unique Entity ID Requirement For Federal Funded Projects
#4702	App for Traffic Control Report
#5086	Detail of Square Tube Sign Posts
#5551	Federal Bridge Formula
#5587	Contract Time
#5588	Specialty Items
#5589	Scope of Work
#5590	Project Number Change
#5591	Pay Item Corrections and Additional Construction Requirements
#5605	Disadvantaged Business Enterprise In Federal-Aid Highway Construction, w/ Supplement
906	Required Federal Contract Provisions -- FHWA 1273, w/Supplements

Section 907 - Special Provisions

907-101-1	Definitions and Terms
907-102-2	Bidding Requirements and Conditions
907-105-2	Control of Work
907-106-1	Control of Materials
907-107-2	Contractor's Erosion Control Plan
907-108-4	Subletting of Contract

**PROJECT: STBG-0054-01(061)/109246301 - Lawrence  
CRP-0054-01(063)/109274301 - Lawrence**

907-109-4	Measurement and Payment
907-234-1	Silt Fence
907-619-5	Traffic Control for Construction Zones
907-619-6	Temporary Portable Rumble Strips
907-700-1	Materials and Tests
907-701-3	Hydraulic Cement
907-702-4	Bituminous Materials
907-703-2	Gradation
907-705-1	Stone Riprap
907-707-3	Joint Materials
907-711-2	Plain Steel Wire
907-712-1	Fence and Guardrail
907-714-3	Miscellaneous Materials
907-718-1	Timber and Dimension Lumber
907-720-2	Acceptance Procedure for Glass Beads
907-721-4	Materials for Signing

Section 905 - Proposal, Proposal Bid Items, Combination Bid Proposal  
Certification of Performance - Prior Federal-Aid Contracts  
Certification Regarding Non-Collusion, Debarment and Suspension  
SAM.GOV Registration and Unique Entity ID  
Section 902 - Contract Form  
Section 903 - Contract Bond Forms  
Form -- OCR-485

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET  
OF SECTION 905 AS ADDENDA)

02/22/2024 05:14 PM

# MISSISSIPPI DEPARTMENT OF TRANSPORTATION

**SECTION 904 - NOTICE TO BIDDERS NO. 5591**

**CODE: (SP)**

**DATE: 02/22/2024**

**SUBJECT: Pay Item Corrections and Additional Construction Requirements**

**PROJECT: STBG-0054-01(061) / 109246301 & CRP-0054-01(063) / 109274301 –  
Lawrence County**

Bidders are hereby advised that the Summary of Quantities sheets in the Plans for Project Number CRP-0054-01(063) / 109274301 do not include pay item no. 907-619-E3001, Changeable Message Sign. This is in error. A quantity of **4 EA** for this pay item has been added to the bid items. This item will be used in accordance with the Traffic Control Sheets in the Contract Plans unless otherwise directed by the Engineer.

Bidders are further advised that the quantities for the pay items shown in the table below have been revised from what is shown on the Summary of Quantities sheets in the Plans for Project Number CRP-0054-01(063) / 109274301. Pay Item No. 682-A039 will be used in lieu of Pay Item Nos. 682-A018 and 682-A028. Pay Item No. 682-B037 will be used in lieu of Pay Item Nos. 682-B016 and 682-B025. The bid sheets are correct.

<b>Pay Item No.</b>	<b>Description</b>	<b>Plan Quantity</b>	<b>Revised Quantity</b>
682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	0 LF	2,468 LF
682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	1,420 LF	0 LF
682-A028	Underground Branch Circuit, AWG 4, 3 Conductor	1,048 LF	0 LF
682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	0 LF	325 LF
682-B016	Underground Branch Circuit, Jacked or Bored, AWG 2, 3 Conductor	240 LF	0 LF
682-B025	Underground Branch Circuit, Jacked or Bored, AWG 4, 3 Conductor	85 LF	0 LF

The Bidder's attention is also called to Sheet No. 4006 (Working No. LD-2). Vertical rebar in the Pole Foundations shall be #6 Bars. A quantity of 8 bars will be needed in each 30" Pole Foundation. All costs are to be absorbed in the price of Pay Item No. 684-A004, Pole Foundation, 30" Diameter.

Overlay approximately 8 miles of SR 27 from Dewey Ballard Road to just north of US 84, known as Federal Aid Project No. STBG-0054-01(061) / 109246301 & Roundabout Construction on SR 27 at West Thomas E Jolly Drive, known as Federal Aid Project No. CRP-0054-01(063) / 109274301 in Lawrence County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
<b>Roadway Items</b>					
0010	202-B006		830	Square Yard	Removal of Asphalt Paved Shoulders, All Depths
0020	202-B007		5,814	Square Yard	Removal of Asphalt Pavement, All Depths
0030	202-B059		518	Square Yard	Removal of Concrete Median & Island Pavement, All Depths
0040	202-B088		1,473	Linear Feet	Removal of Curb & Gutter, All Types
0050	202-B150		1,553	Linear Feet	Removal of Guard Rail Including Post, Blockouts & Hardware
0060	202-B172		154	Square Feet	Removal of Legend, All Types
0070	202-B240		11,010	Linear Feet	Removal of Traffic Stripe
0080	203-A002	(E)	1,097	Cubic Yard	Unclassified Excavation, LVM, AH
0090	203-EX040	(E)	275	Cubic Yard	Borrow Excavation, AH, LVM, Class B9
0100	203-G002	(E)	2,727	Cubic Yard	Excess Excavation, LVM, AH
0110	209-A005		5,761	Square Yard	Geotextile Stabilization, Type V, Non-Woven
0120	211-B001	(E)	269	Cubic Yard	Topsoil for Slope Treatment, Contractor Furnished
0130	213-C001		1	Ton	Superphosphate
0140	216-A001		172	Square Yard	Solid Sodding
0150	219-A001		4	Thousand Gallon	Watering [\$20.00]
0160	220-A001		1	Acre	Insect Pest Control [\$30.00]
0170	221-A001	(S)	49	Cubic Yard	Concrete Paved Ditch
0180	223-A001		5	Acre	Mowing [\$50.00]
0190	225-A001		1	Acre	Grassing
0200	225-B001		1	Ton	Agricultural Limestone
0210	225-C001		2	Ton	Mulch, Vegetative Mulch
0220	226-A001		1	Acre	Temporary Grassing
0230	237-A002		200	Linear Feet	Wattles, 20"
0240	245-A001		100	Linear Feet	Silt Dike
0250	246-A002		75	Each	Sandbags
0260	249-A001		29	Ton	Riprap for Erosion Control
0270	249-B001		18	Cubic Yard	Remove and Reset Riprap
0280	304-A008	(GY)	1,816	Cubic Yard	Granular Material, LVM, Class 6, Group D
0290	403-A003	(BA1)	773	Ton	12.5-mm, ST, Asphalt Pavement
0300	403-A006	(BA1)	141	Ton	19-mm, ST, Asphalt Pavement
0310	403-A015	(BA1)	15,073	Ton	9.5-mm, ST, Asphalt Pavement
0320	403-B012	(BA1)	811	Ton	9.5-mm, ST, Asphalt Pavement, Leveling

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	406-D001		52,194	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0340	407-A001	(A2)	19,083	Gallon	Asphalt for Tack Coat
0350	412-A001		1,584	Square Feet	Pre-Grinding [\$3.25]
0360	423-A001		15	Mile	Rumble Strips, Ground In
0370	503-C010		6,811	Linear Feet	Saw Cut, Full Depth
0380	601-B001	(S)	1	Cubic Yard	Class "B" Structural Concrete, Minor Structures
0390	606-B002		619	Linear Feet	Guard Rail, Class A, Type 1, 'W' Beam
0400	606-D019		8	Each	Guard Rail, Bridge End Section, Type H
0410	606-E005		10	Each	Guard Rail, Terminal End Section, Flared
0420	609-B003	(S)	530	Linear Feet	Concrete Curb, Special Design
0430	609-C001	(S)	290	Linear Feet	Concrete Integral Curb, Type 1
0440	609-D009	(S)	3,930	Linear Feet	Combination Concrete Curb and Gutter Type 3A Mod1
0450	616-A001	(S)	54	Square Yard	Concrete Median and/or Island Pavement, 10-inch
0460	616-A003	(S)	384	Square Yard	Concrete Median and/or Island Pavement, 12-inch
0470	616-A004	(S)	837	Square Yard	Concrete Median and/or Island Pavement, 4-inch
0480	618-A001		1	Lump Sum	Maintenance of Traffic
0490	618-B001		1	Square Feet	Additional Construction Signs [\$10.00]
0500	619-A1001		15	Mile	Temporary Traffic Stripe, Continuous White
0510	619-A1002		5,721	Linear Feet	Temporary Traffic Stripe, Continuous White
0520	619-A2001		10	Mile	Temporary Traffic Stripe, Continuous Yellow
0530	619-A2002		4,981	Linear Feet	Temporary Traffic Stripe, Continuous Yellow
0540	619-A4002		6	Mile	Temporary Traffic Stripe, Skip Yellow
0550	619-A5001		34,039	Linear Feet	Temporary Traffic Stripe, Detail
0560	619-A6001		561	Square Feet	Temporary Traffic Stripe, Legend
0570	619-A6002		5,400	Linear Feet	Temporary Traffic Stripe, Legend
0580	619-D1001		246	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0590	619-D2001		630	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0600	619-F1001		791	Linear Feet	Concrete Median Barrier, Precast
0610	619-G4005		36	Linear Feet	Barricades, Type III, Single Faced
0620	619-G5001		139	Each	Free Standing Plastic Drums
0630	619-G7001		78	Each	Warning Lights, Type "B"
0640	620-A001		1	Lump Sum	Mobilization
0650	626-C001		2,597	Linear Feet	6" Thermoplastic Double Drop Edge Stripe, Continuous White
0660	626-C002		15	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous White

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0670	626-D001		6	Mile	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow
0680	626-D002		271	Linear Feet	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow
0690	626-E001		9	Mile	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow
0700	626-E002		279	Linear Feet	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow
0710	626-F002		1,886	Linear Feet	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow
0720	626-G002		21,695	Linear Feet	Thermoplastic Detail Stripe, White
0730	626-G003		12,275	Linear Feet	Thermoplastic Detail Stripe, Yellow
0740	626-G004		156	Linear Feet	Thermoplastic Double Drop Detail Stripe, White
0750	626-G005		2,277	Linear Feet	Thermoplastic Double Drop Detail Stripe, Yellow
0760	626-H001		505	Square Feet	Thermoplastic Double Drop Legend, White
0770	626-H004		502	Square Feet	Thermoplastic Legend, White
0780	626-H005		4,752	Linear Feet	Thermoplastic Legend, White
0790	627-J001		1,013	Each	Two-Way Clear Reflective High Performance Raised Markers
0800	627-K001		24	Each	Red-Clear Reflective High Performance Raised Markers
0810	627-L001		1,518	Each	Two-Way Yellow Reflective High Performance Raised Markers
0820	630-A001		90	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness
0830	630-A003		72	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness
0840	630-C001		142	Linear Feet	Square Tube Posts, 4.0 lb/ft
0850	630-C005		200	Linear Feet	Square Tube Posts, 2.0 lb/ft
0860	630-F006		44	Each	Delineators, Guard Rail, White
0882	682-A039		2,468	Linear Feet	Underground Branch Circuit, AWG 8, 3 Conductor
0902	682-B037		325	Linear Feet	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor
0910	682-E003		16	Each	Underground Junction Box With Concrete Pad
0920	682-F001		1	Each	Secondary Power Controller
0930	683-B200		16	Each	Lighting Assembly, Low Mast, LED, Type 30-1-10-17
0940	684-A004		21	Cubic Yard	Pole Foundation, 30" Diameter
0950	699-A001		1	Lump Sum	Roadway Construction Stakes
0960	907-234-A001		2,000	Linear Feet	Temporary Silt Fence
0970	907-619-B001		132	Linear Feet	Temporary Portable Rumble Strips
0972	907-619-E3001		4	Each	Changeable Message Sign
<b>ALTERNATE GROUP AA NUMBER 1</b>					
0980	304-F001	(GT)	3,839	Ton	3/4" and Down Crushed Stone Base
<b>ALTERNATE GROUP AA NUMBER 2</b>					
0990	304-F002	(GT)	3,839	Ton	Size 610 Crushed Stone Base

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
			<b>ALTERNATE GROUP AA NUMBER 3</b>		
1000	304-F003	(GT)	3,839	Ton	Size 825B Crushed Stone Base