

Call 08 Mill & Overlay approximately 7 miles of SR 21 from Steele to Sebastopol, known as State Project No. SP-0045-01(020) / 109449301 in Scott County.

Q1. Regarding pay item 304-D002 Granular Material, Crushed Stone; how many tons are set up for shoulder stone and how many tons are set up for the guard rail locations?

A1. Approximately 361 tons for the guardrail locations and approximately 1400 tons for the shoulder material.

Q2. In Section 618.01.2 Traffic Control Management of the Red Book under section “G” of the TCS duties it states that the TCS will “Perform daily daytime inspections and weekly nighttime inspections on projects with predominantly daytime work and perform daily nighttime inspections and weekly daytime inspections on project with predominantly nighttime work.”. Will the prime contractor be held to this specification from the beginning of contract time until the official maintenance release regardless of whether the prime contractor is actively working on the job or not?

A2. ~~Yes.~~ **Revised Answer:** Weekly inspections will be allowed for periods outside of active construction. ~~When any lane closures are present, inspections will be performed daily whether work is being performed or not.~~ When lane closures are present or any non-fixed signs or traffic handling devices such as cones or barrels are in place, inspections shall be performed daily whether work is being performed or not. A Class IV Supplemental Agreement will be forthcoming to address this requirement.