

**Call 11 Mill & Overlay approximately 12 miles of SR 7 from 2 miles south of Morgan City to Itta Bena, known as State Project No. MP-2007-42(010) / 308294301 in Leflore County.**

Q1. Can the intent of pay item 201-B001 Clearing and Grubbing be provided, it is not discussed in the scope of work?

A1. See addendum.

Q2. Is density required on the 9.5MM ST Leveling pay item, 403-A015?

A2. The leveling lift will be rolled to refusal.

Q3. What smoothness tolerance will be required of this job?

A3. Category C.

Q4. In Section 618.01.2 Traffic Control Management of the Red Book under section "G" of the TCS duties it states that the TCS will "Perform daily daytime inspections and weekly nighttime inspections on projects with predominantly daytime work and perform daily nighttime inspections and weekly daytime inspections on project with predominantly nighttime work." It is Our interpretation that this requirement is only while there is work being performed on the project. Can MDOT please advise?

A4. **Revised Answer:** Weekly inspections will be allowed for periods outside of active construction. ~~When any lane closures are present, inspections will be performed daily whether work is being performed or not.~~ When lane closures are present or any non-fixed signs or traffic handling devices such as cones or barrels are in place, inspections shall be performed daily whether work is being performed or not. A Class IV Supplemental Agreement will be forthcoming to address this requirement.