

Call 15 Construction work in Renovating Building "A" Shop & Building "B" Enclosed Bay Shed & Building "C" Open Equipment Shed & Building "D" Chemical Storage, known as State Project Nos. BWO-3067-63(004) / 503758301, BWO-3125-63(002) / 503758302, BWO-3160-63(002) / 503758303 & BWO-3045-63(002) / 503758304 in Sharkey County.

- Q1. Division 13 34 19, Page 3 section 2.03 states "Large Tapered.....24 gage, Galvalume. Roof shall have a Kynar 500 (70 percent PVDF) color coating finish." Are the roofs and or walls to be: 24 gage? Colored or Galvalume? section 2.04 Calls for 4" insulation. Is this to be run Over the purlin? D. Retainer Strips Are these required? spacing?
- A1. Roof and Wall Panels – Large Tapered-Rib Profile, exposed fastener metal roof panels: equal to PBR Metal Roofing Panel, 1 ¼ inches high with 36 inches wide coverage, 24 gauge. Roof panel finish – Galvalume. Wall panel finish – Kynar 500 (70 percent PVDF) color coating finish. Standard colors from the manufacturer's full range of colors to be selected by the Project Engineer/MDOT Architect. Trim, downspouts, and gutter finish - Kynar 500 (70 percent PVDF) color coating finish. Standard colors from the manufacturer's full range of colors to be selected by the Project Engineer/MDOT Architect. 4- inch insulation to be run over purlins. Retainer strips are not required. See addendum.