

SUMMARY OF QUANTITIES				
Pay Item No.	Pay Item	Unit	Preliminary	Final
201-A001	Clearing and Grubbing	LS	100%	
907-225-A001	Grassing	Acre	1	
907-237-A002	Wattles, 12"	LF	150	
907-304-C005	Granular Material, AEA, Class 9, Group C	CY	1550	
907-603-ALT	18" Type A Alternate Pipe	LF	4036	
625-F001	Legend	SF	166	
815-A001	Loose Riprap, Size 100	SY	150	
	<b>Crushed Stone Alternate</b>			
907-304-H002	3/4" And Down Crushed Stone Base, LVM	CY	5510	
	<b>OR</b>			
907-304-H003	Size 610 Crushed Stone Base, LVM	CY	5510	
	<b>OR</b>			
907-304-H004	Size 825B Crushed Stone Base, LVM	CY	5510	
907-403-A017	9.5-mm, ST, Asphalt Pavement	TON	1500	
907-403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	TON	200	

①

① Type A Alternate:  
Approved alternate pipe options can be listed here for clarification.

****ADD OPTION 1 - Parking Lot****				
907-403-A017	9.5-mm, ST, Asphalt Pavement	TON	100	
907-625-C001	Traffic Stripe, Continuous White, 4" width	LF	1820	

****ADD OPTION 2 - Sidewalk****				
203-EX017	Borrow Excavation, AH, FME, Class B9	CY	200	
608-B001	Concrete Sidewalk, With Reinforcement	SY	500	

Add Option portion of the Summary of Quantity sheet required to be separate section and not necessarily separate sheet. Plan profile sheets if necessary for add options should be on separate sheets.