

CHICKASAW (9)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	FALCON CONTRACTING COMPANY, INC.	BONDS COMPANY, INC.	APAC-MISSISSIPPI, INC.
Construction necessary for the overlay of MS 245 from 0.3 miles north of US 45A to MS 41, known as Federal Aid Project No. STP-2841-00(010) / 104858301, in the County of Chickasaw, State of Mississippi.					879,638.50	821,326.00	860,701.00	986,655.06
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	202-B033	Removal of Concrete Pavement w/ Variable Depth Overlay	750.000	SY		12.00	12.00	15.00
0020	202-B102	Removal of Guard Rail	250.000	LF		3.50	3.50	3.62
0030	203-G001	Excess Excavation, FM	250.000	CY		10.00	12.00	13.50
0040	304-A014	Granular Material, LVM, Class 3, Group D	3,000.000	CY		17.00	24.00	21.80
0050	406-A001	Cold Milling of Bituminous Pavement, All Depths	2,200.000	SY		6.00	6.00	6.00
0060	423-A001	Rumble Strips, Ground In	9.000	MI		700.00	800.00	736.00
0070	606-E002	Guard Rail, Terminal End Section, Flared	4.000	EA		2,250.00	2,250.00	2,328.75
0080	618-A001	Maintenance of Traffic	1.000	LS		30,000.00	65,000.00	37,500.00
0090	618-B001	Additional Construction Signs	1.000	SF		10.00	10.00	10.00
0100	619-A1002	Temporary Traffic Stripe, Continuous White	10.000	MI		1,000.00	1,000.00	1,035.00
0110	619-A2002	Temporary Traffic Stripe, Continuous Yellow	6.000	MI		1,200.00	1,200.00	1,242.00
0120	619-A4006	Temporary Traffic Stripe, Skip Yellow	8.000	MI		1,200.00	1,200.00	1,242.00
0130	619-A5001	Temporary Traffic Stripe, Detail	600.000	LF		0.50	0.50	0.52
0140	619-A6001	Temporary Traffic Stripe, Legend	600.000	LF		1.00	1.00	1.04
0150	619-F3004	Delineators, Guard Rail, White	12.000	EA		18.00	18.00	18.63
0160	619-G5001	Free Standing Plastic Drums	25.000	EA		50.00	75.00	62.00
0170	626-C002	6" Thermoplastic Edge Stripe, Continuous White	10.000	MI		1,800.00	1,800.00	1,863.00
0180	626-D002	6" Thermoplastic Traffic Stripe, Skip Yellow	5.000	MI		1,000.00	1,000.00	1,035.00
0190	626-E002	6" Thermoplastic Traffic Stripe, Continuous Yellow	3.000	MI		2,500.00	2,500.00	2,587.50
0200	626-G001	Thermoplastic Detail Stripe, White	1,500.000	LF		1.25	1.25	1.29
0210	626-G002	Thermoplastic Detail Stripe, Yellow	600.000	LF		1.25	1.25	1.29
0220	626-H001	Thermoplastic Legend, White	700.000	SF		6.00	6.00	6.21
0230	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	500.000	EA		6.00	6.00	6.21
0240	907-403-A010	Hot Mix Asphalt, MT, 9.5-mm mixture	8,400.000	TON		62.00	60.00	75.00
0250	907-403-C003	Hot Mix Asphalt, MT, 19-mm mixture, Trench Widening	1,850.000	TON		59.00	58.00	74.00