

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0110	203-EX017	Borrow Excavation, AH, FME, Class B7	446,250.000	CY	7.27	6.50	8.30
0050	202-B088	Removal of Curb & Gutter, All Types	120.000	LF	6.15	15.00	8.60
0010	201-A001	Clearing and Grubbing	1.000	LS	575,000.00	2,500,000.00	875,000.00
0750	604-B001	Gratings	500.000	LBS	5.35	2.25	2.90
0760	605-AA001	Geotextile for Subsurface Drainage, Type III	67.000	SY	4.00	9.20	1.90
0770	605-T001	4" Perforated Pipe for Underdrains	120.000	LF	25.00	15.00	6.10
0780	605-U001	4" Non-perforated Pipe for Underdrains	5.000	LF	25.00	45.00	28.50
0790	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	5.000	CY	183.00	85.00	75.50
1770	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	88.000	CY		77.00	
1780	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	88.000	CY	29.00		22.00
0810	606-C003	Guard Rail, Cable Anchor, Type 1	3.000	EA	910.00	850.00	895.00
0820	606-D001	Guard Rail, Bridge End Section	2.000	EA	2,515.00	2,350.00	2,500.00
1080	619-G8001	Warning Lights, Type "C"	51.000	EA	160.00	135.00	142.00
1090	620-A001	Mobilization	1.000	LS	1,050,000.00	1,000,000.00	1,000,000.00
1100	626-A001	6" Thermoplastic Double Drop Traffic Stripe, Skip White	2.000	MI	2,140.00	2,000.00	2,100.00
1110	626-B001	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	374.000	LF	1.10	1.00	1.10
1120	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	10.000	MI	3,745.00	3,500.00	3,700.00
1130	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	7.000	MI	3,745.00	3,500.00	3,700.00
1140	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	4.000	MI	3,745.00	3,500.00	3,700.00
1150	626-G004	Thermoplastic Double Drop Detail Stripe, White	18,174.000	LF	1.10	1.00	1.10
1160	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	11,263.000	LF	1.10	1.00	1.10
1170	626-H001	Thermoplastic Double Drop Legend, White	883.000	SF	6.40	6.00	6.30
1180	626-H002	Thermoplastic Double Drop Legend, White	1,021.000	LF	1.60	1.50	1.60
1190	627-B001	Two-Way Clear Reflective Raised Markers	162.000	EA	6.00	5.00	5.30
1700	907-641-C001	ITS Radar Detection Sensor	2.000	EA	7,950.00	6,500.00	6,800.00
1480	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS	7,835.00	11,550.00	12,000.00

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1710	907-650-A002	On Street Video Equipment, Fixed Type	14.000	EA	5,022.00	2,640.00	2,800.00
1720	907-650-A003	On Street Video Equipment, PTZ Type	8.000	EA	8,422.00	5,500.00	5,700.00
0060	202-B136	Removal of Guard Rail	827.000	LF	6.40	6.00	6.35
0070	202-B191	Removal of Pipe, 8" And Above	287.000	LF	30.00	20.00	12.75
0080	202-B215	Removal of Sign Including Post & Footing	173.000	EA	374.50	350.00	370.00
0090	202-B240	Removal of Traffic Stripe	3,700.000	LF	2.15	2.00	2.10
0100	203-A001	Unclassified Excavation, FM, AH	65,950.000	CY	5.30	5.75	5.00
0120	203-EX018	Borrow Excavation, AH, FME, Class B7-6	1,000.000	CY	13.40	13.00	10.50
0130	203-G001	Excess Excavation, FM, AH	16,250.000	CY	7.80	6.00	3.75
0140	206-A001	Structure Excavation	923.000	CY	9.00	18.00	14.50
0150	206-B001	Select Material for Undercuts, Contractor Furnished, FM	565.000	CY	69.00	60.00	81.00
0160	209-A005	Geotextile Stabilization, Type V, Non-Woven	170,295.000	SY	2.30	2.35	1.60
0170	211-B001	Topsoil for Slope Treatment, Contractor Furnished	500.000	CY	24.00	10.00	12.00
0180	213-C001	Superphosphate	24.000	TON	535.00	665.00	1,000.00
0190	216-A001	Solid Sodding	3,343.000	SY	5.15	4.00	5.30
0200	217-A001	Ditch Liner	450.000	SY	3.10	3.00	1.80
0210	219-A001	Watering	26.000	KGAL	20.00	20.00	20.00
0320	236-A008	Silt Basin, Type D	29.000	EA	1,900.00	3,600.00	775.00
0330	237-A002	Wattles, 20"	3,000.000	LF	8.60	8.00	5.50
1490	907-240-A001	Interlocking Flexible Block Erosion Control System	1,484.000	SY	78.00	70.00	49.25
0340	246-B002	Rockbags	50.000	LF	21.40	70.00	61.00
0350	249-A001	Riprap for Erosion Control	500.000	TON	88.20	90.00	68.00
1500	907-253-A001	Coir Fiber Baffle	4,350.000	LF	5.35	9.00	4.25
0550	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	272.000	LF	71.00	49.00	52.00
0560	603-CA041	30" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	568.000	LF	86.00	62.50	66.00
0570	603-CA056	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	320.000	LF	103.00	73.00	78.25

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0580	603-CA067	42" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	80.000	LF	120.00	90.00	91.75
0590	603-CA077	48" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	96.000	LF	140.00	116.00	110.00
0600	603-CB003	18" Reinforced Concrete End Section	10.000	EA	667.00	770.00	708.00
0610	603-CB004	24" Reinforced Concrete End Section	6.000	EA	820.00	890.00	782.00
0620	603-CB005	30" Reinforced Concrete End Section	13.000	EA	1,012.00	960.00	860.00
0630	603-CB006	36" Reinforced Concrete End Section	5.000	EA	1,280.00	1,255.00	1,200.00
0640	603-CB007	42" Reinforced Concrete End Section	2.000	EA	1,870.00	1,675.00	1,500.00
1716	907-661-B002	Fiber Optic Drop Cable, 12 SM	1,375.000	LF	3.10	3.50	3.60
0860	607-P1008	Line Post, 7' x 1 1/2" Galvanized Steel	900.000	EA	31.00	35.00	28.00
0870	607-P2004	Brace Post, 7 1/2' x 2" Galvanized Steel	900.000	EA	106.00	95.00	98.00
0880	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	4,501.000	LF	21.40	20.00	21.00
0890	614-B001	Concrete Driveway, With Reinforcement	175.000	SY	100.00	80.00	98.50
0900	615-A002	Concrete Bridge End Barrier, 33.5"	40.000	LF	51.00	50.00	54.50
0910	616-A001	Concrete Median and/or Island Pavement, 10-inch	158.000	SY	114.00	115.00	112.00
0920	616-A004	Concrete Median and/or Island Pavement, 4-inch	2,673.000	SY	32.20	35.00	31.75
0930	617-A001	Right-of-Way Marker	90.000	EA	196.00	200.00	250.00
0940	618-A001	Maintenance of Traffic	1.000	LS	306,000.00	400,000.00	475,000.00
0950	619-A1001	Temporary Traffic Stripe, Continuous White	11.000	MI	803.00	750.00	789.00
0960	619-A2001	Temporary Traffic Stripe, Continuous Yellow	10.000	MI	803.00	750.00	789.00
0970	619-A3001	Temporary Traffic Stripe, Skip White	2.000	MI	803.00	750.00	789.00
1200	627-K001	Red-Clear Reflective High Performance Raised Markers	250.000	EA	5.40	5.00	5.30
1210	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	775.000	EA	5.40	5.00	5.30
1220	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	362.000	SF	24.60	23.00	24.25
1230	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	1,622.000	SF	26.00	24.00	25.25
1240	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	3,128.000	SF	28.00	26.00	27.25
1250	630-B003	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Overhead Mounted	190.000	SF	30.00	28.00	29.50

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1260	630-C002	Steel U-Section Posts, 2.0 lb/ft	186.000	LF	10.00	9.00	9.50
1270	630-C003	Steel U-Section Posts, 3.0 lb/ft	2,234.000	LF	12.00	11.00	11.50
1280	630-D003	Structural Steel Beams, W10 x 22	347.000	LF	118.00	110.00	116.00
1290	630-D006	Structural Steel Beams, W6 x 12	38.000	LF	64.00	60.00	63.25
1300	630-D007	Structural Steel Beams, W6 x 15	398.000	LF	70.00	65.00	68.50
1310	630-D008	Structural Steel Beams, W6 x 9	381.000	LF	59.00	55.00	58.00
1320	630-D010	Structural Steel Beams, W8 x 21	62.000	LF	86.00	80.00	84.25
1400	630-F012	Delineators, Post Mounted, Single White	66.000	EA	41.00	38.00	40.00
1410	630-F013	Delineators, Post Mounted, Single Yellow	40.000	EA	41.00	38.00	40.00
1420	630-G004	Type 3 Object Markers, OM-3R or OM-3L	14.000	EA	80.00	75.00	79.00
1430	630-I003	Metal Overhead Sign Supports, Assembly No. 1, Contractor Designed	1.000	LS	36,400.00	34,000.00	36,000.00
1440	630-K001	Welded & Seamless Steel Pipe Posts, 3 1/2"	120.000	LF	53.50	50.00	52.75
1450	630-K002	Welded & Seamless Steel Pipe Posts, 3"	289.000	LF	48.00	45.00	47.25
1460	630-K003	Welded & Seamless Steel Pipe Posts, 4"	411.000	LF	59.00	55.00	61.75
1470	630-K004	Welded & Seamless Steel Pipe Posts, 5"	38.000	LF	69.55	65.00	73.00
1520	907-630-L001	Pedestal Sign Support, Assembly No 1, Contractor Designed	1.000	LS	70,196.00	66,500.00	70,000.00
1530	907-630-L002	Pedestal Sign Support, Assembly No 2, Contractor Designed	1.000	LS	70,196.00	66,500.00	70,000.00
1540	907-630-M001	Post Sign Support, Assembly No 1, Contractor Designed	1.000	LS	21,972.00	22,000.00	22,000.00
1550	907-630-M002	Post Sign Support, Assembly No 2, Contractor Designed	1.000	LS	21,972.00	22,000.00	22,000.00
1560	907-632-J001	Power Service Pedestal	1.000	EA	3,007.00	5,100.00	5,400.00
1570	907-634-E001	Camera Pole with Foundation, 50' Pole	5.000	EA	12,154.00	6,250.00	6,600.00
1580	907-636-B043	Electric Cable, Underground in Conduit, THHN, AWG #2, 4 Conductor	85.000	LF	7.75	7.00	7.40
1590	907-636-B051	Electric Cable, Underground in Conduit, THHN, AWG #4, 4 Conductor	925.000	LF	5.25	5.00	5.10
1600	907-636-B053	Electric Cable, Underground in Conduit, THHN, AWG #6, 3 Conductor	2,915.000	LF	3.30	3.00	2.80
1610	907-637-A002	Pullbox Enclosure, Type 2	20.000	EA	604.00	1,000.00	984.00
1620	907-637-A004	Pullbox Enclosure, Type 4	28.000	EA	1,102.00	1,100.00	1,200.00

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1630	907-637-A005	Pullbox Enclosure, Type 5	26.000	EA	1,305.00	1,360.00	1,400.00
1640	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	160.000	LF	8.00	5.50	5.80
1650	907-637-H001	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2 @ 2"	365.000	LF	11.00	10.00	10.25
1660	907-637-H002	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2"	2,495.000	LF	7.00	9.00	9.30
1670	907-637-I001	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2 @ 2"	36,915.000	LF	10.00	10.00	10.25
1680	907-637-I002	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2"	2,330.000	LF	8.70	9.00	9.30
1718	907-663-A001	Network Switch, Type A	7.000	EA	3,131.00	1,860.00	2,000.00
1719	907-663-A002	Network Switch, Type B	4.000	EA	4,424.00	2,250.00	2,400.00
1464	682-A005	Underground Branch Circuit, AWG 1/0, 3 Conductor	2,550.000	LF	12.30	11.85	12.50
1465	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	8,940.000	LF	10.00	9.05	9.50
1466	682-A025	Underground Branch Circuit, AWG 3/0, 3 Conductor	210.000	LF	15.70	13.00	13.75
1467	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	7,355.000	LF	6.50	5.40	5.70
1468	682-B005	Underground Branch Circuit, Jacked or Bored, AWG 1/0, 3 Conductor	65.000	LF	21.50	20.25	21.25
1469	682-B016	Underground Branch Circuit, Jacked or Bored, AWG 2, 3 Conductor	683.000	LF	19.40	17.50	18.50
1471	682-B022	Underground Branch Circuit, Jacked or Bored, AWG 3/0, 3 Conductor	76.000	LF	25.25	17.20	18.00
0030	202-B007	Removal of Asphalt Pavement, All Depths	34,044.000	SY	3.00	3.50	3.40
0800	606-B001	Guard Rail, Class A, Type 1	650.000	LF	24.60	23.00	24.25
0690	603-CE018	44" x 27" Concrete Arch Pipe, Class A III	168.000	LF	103.00	75.00	86.50
0700	603-CF002	22" x 13" Concrete Arch Pipe End Section	16.000	EA	730.00	820.00	708.00
0710	603-CF003	29" x 18" Concrete Arch Pipe End Section	4.000	EA	884.00	940.00	768.00
0720	603-CF004	36" x 23" Concrete Arch Pipe End Section	4.000	EA	1,129.00	1,215.00	861.00
0730	603-CF005	44" x 27" Concrete Arch Pipe End Section	4.000	EA	1,451.00	1,425.00	1,200.00
0740	603-SB012	18" Branch Connections, Stub into Box Culvert	1.000	EA	1,605.00	1,225.00	1,200.00
0830	606-E005	Guard Rail, Terminal End Section, Flared	5.000	EA	2,782.00	2,600.00	2,700.00
0840	606-E007	Guard Rail, Terminal End Section, Non-Flared	2.000	EA	3,050.00	2,850.00	3,000.00
0850	607-B020	60" Type II Chain Link Fence, Class II	18,550.000	LF	6.15	5.50	5.60

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0040	202-B052	Removal of Concrete Driveways, All Depths	410.000	SY	8.70	15.00	10.75
0650	603-CB008	48" Reinforced Concrete End Section	2.000	EA	1,993.00	1,770.00	1,600.00
0660	603-CE002	22" x 13" Concrete Arch Pipe, Class A III	744.000	LF	66.75	45.00	47.25
0670	603-CE008	29" x 18" Concrete Arch Pipe, Class A III	128.000	LF	77.00	54.00	59.75
0680	603-CE013	36" x 23" Concrete Arch Pipe, Class A III	128.000	LF	85.00	60.00	64.25
1690	907-637-K001	Traffic Signal Conduit Bank, Aerial Supported, Type 1, 2 @ 2"	1,985.000	LF	41.25	35.00	35.50
1479	683-A129	Lighting Assembly, High Mast, LED, Type 130-8-S	4.000	EA	37,791.00	36,500.00	38,000.00
1481	683-B197	Lighting Assembly, Low Mast, LED, Type 40-1-15-268	34.000	EA	5,077.00	3,925.00	4,100.00
1482	683-D001	Portable Electric Power Units	1.000	EA	4,125.00	2,810.00	3,000.00
1483	684-A004	Pole Foundation, 30" Diameter	56.000	CY	847.00	980.00	1,000.00
1484	684-A007	Pole Foundation, 48" Diameter	110.000	CY	795.00	720.00	758.00
1485	684-B004	Slip Casing, 30" Diameter	9.000	LF	72.00	30.00	31.50
1486	684-B007	Slip Casing, 48" Diameter	21.000	LF	78.00	61.00	64.25
1487	699-A001	Roadway Construction Stakes	1.000	LS	245,000.00	150,000.00	250,000.00
1488	815-A007	Loose Riprap, Size 300	5,500.000	TON	87.00	70.00	69.50
1489	815-F002	Sediment Control Stone	971.000	TON	55.00	55.00	54.00
1730	907-906001	Trainees	1,040.000	HRS	5.00	5.00	5.00
1790	221-A001	Concrete Paved Ditch	28.000	CY	802.00	665.00	445.00
1800	501-K001	Transverse Grooving	1,716.000	SY	2.35	2.20	2.50
1810	803-I004	PDA Test Pile, Steel Pipe Pile	3.000	EA	48,150.00	18,000.00	19,000.00
1820	803-J001	Pile Restrike	2.000	EA	2,140.00	600.00	1,000.00
1830	803-P001	24" Steel Pipe Piling, Wall Thickness 0.500"	3,775.000	LF	134.00	100.00	108.00
1880	907-804-A002	Bridge Concrete, Class AA	266.000	CY	1,016.00	1,000.00	750.00
1890	907-804-A004	Bridge Concrete, Class BD	485.000	CY	1,284.00	1,000.00	850.00
1840	804-C167	99' Prestressed Concrete Beam, Type BT-54	2,360.000	LF	214.00	150.00	175.00
1850	805-A001	Reinforcement	162,682.000	LBS	1.10	1.00	1.00

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1860	809-A001	Retaining Wall System	8,525.000	SF	169.00	160.00	167.00
1870	813-A002	Concrete Railing, 32"	598.000	LF	51.00	50.00	58.25
1472	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	397.000	LF	12.40	13.80	14.50
1459	656-A002	Dynamic Message Sign, Type 2	2.000	EA	120,767.00	100,000.00	105,000.00
1461	656-A003	Dynamic Message Sign, Type 3	2.000	EA	47,260.00	35,000.00	36,000.00
1712	907-659-A001	Traffic Management Center Modifications	1.000	LS	142,000.00	72,000.00	75,000.00
1462	660-A003	Equipment Cabinet, Type B	4.000	EA	5,177.00	4,850.00	5,100.00
1463	660-A004	Equipment Cabinet, Type C	2.000	EA	9,611.00	8,840.00	9,300.00
1714	907-661-A004	Fiber Optic Cable, 72 SM	39,975.000	LF	2.40	2.50	2.60
1473	682-D003	Underground Pull Box	27.000	EA	1,312.00	1,685.00	1,800.00
1474	682-E003	Underground Junction Box With Concrete Pad	34.000	EA	1,329.00	1,315.00	1,400.00
1475	682-F002	Secondary Power Controllers	1.000	EA	15,410.00	14,600.00	15,000.00
1476	683-A126	Lighting Assembly, High Mast, LED, Type 110-8-S	1.000	EA	37,426.00	36,500.00	38,000.00
1477	683-A127	Lighting Assembly, High Mast, LED, Type 110-6-S	5.000	EA	35,256.00	33,250.00	35,000.00
1478	683-A128	Lighting Assembly, High Mast, LED, Type 110-6-A	2.000	EA	35,246.00	33,250.00	35,000.00
1740	304-F001	3/4" and Down Crushed Stone Base	62,600.000	TON			
1750	304-F002	Size 610 Crushed Stone Base	62,600.000	TON			46.25
1760	304-F003	Size 825B Crushed Stone Base	62,600.000	TON	43.80	45.00	
0360	403-A001	12.5-mm, HT, Asphalt Pavement	9,629.000	TON	83.00	80.00	87.50
0370	403-A002	12.5-mm, MT, Asphalt Pavement	4,858.000	TON	83.40	80.00	88.00
0380	403-A003	12.5-mm, ST, Asphalt Pavement	1,114.000	TON	88.25	85.00	93.00
0390	403-A004	19-mm, HT, Asphalt Pavement	10,592.000	TON	79.00	76.00	83.25
0400	403-A005	19-mm, MT, Asphalt Pavement	7,894.000	TON	79.00	76.00	83.50
0410	403-A006	19-mm, ST, Asphalt Pavement	12,220.000	TON	76.00	74.00	80.25
0420	403-A013	9.5-mm, HT, Asphalt Pavement	5,718.000	TON	100.00	96.00	106.00
0220	220-A001	Insect Pest Control	24.000	ACRE	30.00	30.00	30.00

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0230	221-A001	Concrete Paved Ditch	81.000	CY	535.00	665.00	680.00
0240	223-A001	Mowing	94.000	ACRE	50.00	50.00	50.00
0250	225-A001	Grassing	47.000	ACRE	1,370.00	900.00	1,300.00
0260	225-B001	Agricultural Limestone	24.000	TON	94.00	100.00	300.00
0270	225-C001	Mulch, Vegetative Mulch	94.000	TON	214.00	200.00	495.00
1032	619-F1001	Concrete Median Barrier, Precast	1,000.000	LF	40.00	25.00	38.75
1082	619-J1005	Impact Attenuator, 70 MPH	2.000	EA	9,095.00	8,500.00	8,900.00
1084	619-J2005	Impact Attenuator, 70 MPH, Replacement Package	2.000	EA	4,815.00	4,500.00	4,700.00
0280	226-A001	Temporary Grassing	47.000	ACRE	1,552.00	825.00	1,000.00
0290	227-A001	Hydroseeding	47.000	ACRE	1,369.00	2,750.00	3,000.00
0300	234-A001	Temporary Silt Fence	72,500.000	LF	3.00	3.00	2.50
0310	234-D001	Inlet Siltation Guard	2.000	EA	728.00	675.00	500.00
0430	403-A014	9.5-mm, MT, Asphalt Pavement	3,643.000	TON	98.25	94.00	103.00
0440	403-A015	9.5-mm, ST, Asphalt Pavement	821.000	TON	106.00	101.00	111.00
0450	406-A002	Cold Milling of Bituminous Pavement, All Depths	2,000.000	SY	6.60	6.50	7.40
0460	407-A001	Asphalt for Tack Coat	15,809.000	GAL	3.65	3.50	3.90
0470	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	118.000	LF	28.00	10.00	10.50
0480	423-A001	Rumble Strips, Ground In	13.000	MI	428.00	260.00	275.00
0490	502-A001	Reinforced Cement Concrete Bridge End Pavement	258.000	SY	209.00	200.00	240.00
0500	601-A001	Class "B" Structural Concrete	478.000	CY	599.00	700.00	675.00
0510	601-B001	Class "B" Structural Concrete, Minor Structures	55.000	CY	1,575.00	1,600.00	1,200.00
0520	602-A001	Reinforcing Steel	74,216.000	LBS	1.00	1.15	1.20
0530	603-ALT003	18" Type A Alternate Pipe	316.000	LF	59.00	31.00	36.00
0540	603-CA012	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	408.000	LF	60.00	40.50	40.25
0980	619-A5001	Temporary Traffic Stripe, Detail	21,261.000	LF	0.10	0.10	0.10
0990	619-A6001	Temporary Traffic Stripe, Legend	87.000	SF	2.15	2.00	2.10

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$24,196,880.20	\$24,489,870.90	\$24,050,044.25
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1000	619-A6002	Temporary Traffic Stripe, Legend	1,115.000	LF	0.55	0.50	0.55
1010	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	472.000	SF	16.00	5.00	5.30
1020	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,279.000	SF	16.00	5.00	5.30
1030	619-E1001	Flashing Arrow Panel, Type C	2.000	EA	2,140.00	1,850.00	1,900.00
1510	907-619-E3001	Changeable Message Sign	6.000	EA	16,050.00	10,000.00	9,000.00
1040	619-G4001	Barricades, Type III, Double Faced	288.000	LF	32.00	14.00	14.75
1050	619-G4005	Barricades, Type III, Single Faced	72.000	LF	30.00	12.00	12.75
1060	619-G5001	Free Standing Plastic Drums	207.000	EA	59.00	45.00	47.25
1070	619-G7001	Warning Lights, Type "B"	15.000	EA	160.00	185.00	195.00
1330	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	456.000	LBS	4.00	3.50	3.70
1340	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	477.000	LBS	4.00	3.50	3.70
1350	630-E003	Structural Steel Angles & Bars, 4" x 4" x 5/16" Angles	591.000	LBS	4.00	3.50	3.70
1360	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	1,281.000	LBS	2.70	2.50	2.60
1370	630-F006	Delineators, Guard Rail, White	32.000	EA	19.00	18.00	19.00
1380	630-F010	Delineators, Post Mounted, Double White	126.000	EA	51.00	48.00	50.50
1390	630-F011	Delineators, Post Mounted, Double Yellow	77.000	EA	51.00	48.00	50.50
0020	202-A001	Removal of Obstructions	1.000	LS	252,000.00	210,000.00	88,000.00

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$25,999,999.64		
Ref#	Item	Item Description	Item Qty	Units			
					4		
0110	203-EX017	Borrow Excavation, AH, FME, Class B7	446,250.000	CY		10.25	
0050	202-B088	Removal of Curb & Gutter, All Types	120.000	LF		8.00	
0010	201-A001	Clearing and Grubbing	1.000	LS		250,000.00	
0750	604-B001	Gratings	500.000	LBS		1.90	
0760	605-AA001	Geotextile for Subsurface Drainage, Type III	67.000	SY		12.00	
0770	605-T001	4" Perforated Pipe for Underdrains	120.000	LF		29.75	
0780	605-U001	4" Non-perforated Pipe for Underdrains	5.000	LF		31.00	
0790	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	5.000	CY		174.00	
1770	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	88.000	CY		51.50	
1780	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	88.000	CY			
0810	606-C003	Guard Rail, Cable Anchor, Type 1	3.000	EA		909.50	
0820	606-D001	Guard Rail, Bridge End Section	2.000	EA		2,515.00	
1080	619-G8001	Warning Lights, Type "C"	51.000	EA		144.50	
1090	620-A001	Mobilization	1.000	LS		1,250,000.00	
1100	626-A001	6" Thermoplastic Double Drop Traffic Stripe, Skip White	2.000	MI		2,141.00	
1110	626-B001	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	374.000	LF		1.10	
1120	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	10.000	MI		3,746.00	
1130	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	7.000	MI		3,746.00	
1140	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	4.000	MI		3,746.00	
1150	626-G004	Thermoplastic Double Drop Detail Stripe, White	18,174.000	LF		1.10	
1160	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	11,263.000	LF		1.10	
1170	626-H001	Thermoplastic Double Drop Legend, White	883.000	SF		6.40	
1180	626-H002	Thermoplastic Double Drop Legend, White	1,021.000	LF		1.60	
1190	627-B001	Two-Way Clear Reflective Raised Markers	162.000	EA		5.40	
1700	907-641-C001	ITS Radar Detection Sensor	2.000	EA		6,930.00	
1480	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS		12,360.00	

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29						\$25,999,999.64	
Ref#	Item	Item Description	Item Qty	Units		4	
1710	907-650-A002	On Street Video Equipment, Fixed Type	14.000	EA		2,826.00	
1720	907-650-A003	On Street Video Equipment, PTZ Type	8.000	EA		5,747.00	
0060	202-B136	Removal of Guard Rail	827.000	LF		6.40	
0070	202-B191	Removal of Pipe, 8" And Above	287.000	LF		18.00	
0080	202-B215	Removal of Sign Including Post & Footing	173.000	EA		374.50	
0090	202-B240	Removal of Traffic Stripe	3,700.000	LF		2.10	
0100	203-A001	Unclassified Excavation, FM, AH	65,950.000	CY		11.25	
0120	203-EX018	Borrow Excavation, AH, FME, Class B7-6	1,000.000	CY		14.00	
0130	203-G001	Excess Excavation, FM, AH	16,250.000	CY		6.70	
0140	206-A001	Structure Excavation	923.000	CY		9.00	
0150	206-B001	Select Material for Undercuts, Contractor Furnished, FM	565.000	CY		53.25	
0160	209-A005	Geotextile Stabilization, Type V, Non-Woven	170,295.000	SY		1.40	
0170	211-B001	Topsoil for Slope Treatment, Contractor Furnished	500.000	CY		6.00	
0180	213-C001	Superphosphate	24.000	TON		711.50	
0190	216-A001	Solid Sodding	3,343.000	SY		4.30	
0200	217-A001	Ditch Liner	450.000	SY		3.20	
0210	219-A001	Watering	26.000	KGAL		20.00	
0320	236-A008	Silt Basin, Type D	29.000	EA		5,943.00	
0330	237-A002	Wattles, 20"	3,000.000	LF		4.80	
1490	907-240-A001	Interlocking Flexible Block Erosion Control System	1,484.000	SY		62.75	
0340	246-B002	Rockbags	50.000	LF		16.00	
0350	249-A001	Riprap for Erosion Control	500.000	TON		78.00	
1500	907-253-A001	Coir Fiber Baffle	4,350.000	LF		6.40	
0550	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	272.000	LF		51.00	
0560	603-CA041	30" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	568.000	LF		63.00	
0570	603-CA056	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	320.000	LF		86.75	

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29						\$25,999,999.64	
Ref#	Item	Item Description	Item Qty	Units		4	
0580	603-CA067	42" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	80.000	LF		99.50	
0590	603-CA077	48" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	96.000	LF		116.50	
0600	603-CB003	18" Reinforced Concrete End Section	10.000	EA		1,225.00	
0610	603-CB004	24" Reinforced Concrete End Section	6.000	EA		1,365.00	
0620	603-CB005	30" Reinforced Concrete End Section	13.000	EA		1,540.00	
0630	603-CB006	36" Reinforced Concrete End Section	5.000	EA		1,404.00	
0640	603-CB007	42" Reinforced Concrete End Section	2.000	EA		2,392.00	
1716	907-661-B002	Fiber Optic Drop Cable, 12 SM	1,375.000	LF		3.60	
0860	607-P1008	Line Post, 7' x 1 1/2" Galvanized Steel	900.000	EA		30.75	
0870	607-P2004	Brace Post, 7 1/2' x 2" Galvanized Steel	900.000	EA		105.50	
0880	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	4,501.000	LF		21.50	
0890	614-B001	Concrete Driveway, With Reinforcement	175.000	SY		100.00	
0900	615-A002	Concrete Bridge End Barrier, 33.5"	40.000	LF		54.01	
0910	616-A001	Concrete Median and/or Island Pavement, 10-inch	158.000	SY		114.00	
0920	616-A004	Concrete Median and/or Island Pavement, 4-inch	2,673.000	SY		32.25	
0930	617-A001	Right-of-Way Marker	90.000	EA		291.50	
0940	618-A001	Maintenance of Traffic	1.000	LS		699,138.26	
0950	619-A1001	Temporary Traffic Stripe, Continuous White	11.000	MI		802.50	
0960	619-A2001	Temporary Traffic Stripe, Continuous Yellow	10.000	MI		802.50	
0970	619-A3001	Temporary Traffic Stripe, Skip White	2.000	MI		802.50	
1200	627-K001	Red-Clear Reflective High Performance Raised Markers	250.000	EA		5.40	
1210	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	775.000	EA		5.40	
1220	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	362.000	SF		24.50	
1230	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	1,622.000	SF		25.75	
1240	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	3,128.000	SF		27.75	
1250	630-B003	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Overhead Mounted	190.000	SF		30.00	

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29						\$25,999,999.64	
Ref#	Item	Item Description	Item Qty	Units		4	
1260	630-C002	Steel U-Section Posts, 2.0 lb/ft	186.000	LF		9.60	
1270	630-C003	Steel U-Section Posts, 3.0 lb/ft	2,234.000	LF		11.75	
1280	630-D003	Structural Steel Beams, W10 x 22	347.000	LF		117.50	
1290	630-D006	Structural Steel Beams, W6 x 12	38.000	LF		64.25	
1300	630-D007	Structural Steel Beams, W6 x 15	398.000	LF		69.50	
1310	630-D008	Structural Steel Beams, W6 x 9	381.000	LF		58.75	
1320	630-D010	Structural Steel Beams, W8 x 21	62.000	LF		85.50	
1400	630-F012	Delineators, Post Mounted, Single White	66.000	EA		40.75	
1410	630-F013	Delineators, Post Mounted, Single Yellow	40.000	EA		40.75	
1420	630-G004	Type 3 Object Markers, OM-3R or OM-3L	14.000	EA		80.25	
1430	630-I003	Metal Overhead Sign Supports, Assembly No. 1, Contractor Designed	1.000	LS		36,390.00	
1440	630-K001	Welded & Seamless Steel Pipe Posts, 3 1/2"	120.000	LF		53.50	
1450	630-K002	Welded & Seamless Steel Pipe Posts, 3"	289.000	LF		48.25	
1460	630-K003	Welded & Seamless Steel Pipe Posts, 4"	411.000	LF		58.75	
1470	630-K004	Welded & Seamless Steel Pipe Posts, 5"	38.000	LF		69.50	
1520	907-630-L001	Pedestal Sign Support, Assembly No 1, Contractor Designed	1.000	LS		71,170.00	
1530	907-630-L002	Pedestal Sign Support, Assembly No 2, Contractor Designed	1.000	LS		71,170.00	
1540	907-630-M001	Post Sign Support, Assembly No 1, Contractor Designed	1.000	LS		22,520.00	
1550	907-630-M002	Post Sign Support, Assembly No 2, Contractor Designed	1.000	LS		22,520.00	
1560	907-632-J001	Power Service Pedestal	1.000	EA		5,448.00	
1570	907-634-E001	Camera Pole with Foundation, 50' Pole	5.000	EA		6,689.00	
1580	907-636-B043	Electric Cable, Underground in Conduit, THHN, AWG #2, 4 Conductor	85.000	LF		7.50	
1590	907-636-B051	Electric Cable, Underground in Conduit, THHN, AWG #4, 4 Conductor	925.000	LF		5.20	
1600	907-636-B053	Electric Cable, Underground in Conduit, THHN, AWG #6, 3 Conductor	2,915.000	LF		2.90	
1610	907-637-A002	Pullbox Enclosure, Type 2	20.000	EA		1,001.00	
1620	907-637-A004	Pullbox Enclosure, Type 4	28.000	EA		1,172.00	

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29					\$25,999,999.64		
Ref#	Item	Item Description	Item Qty	Units	4		
1630	907-637-A005	Pullbox Enclosure, Type 5	26.000	EA	1,456.00		
1640	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	160.000	LF	5.90		
1650	907-637-H001	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2 @ 2"	365.000	LF	10.50		
1660	907-637-H002	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2"	2,495.000	LF	9.50		
1670	907-637-I001	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2 @ 2"	36,915.000	LF	10.25		
1680	907-637-I002	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2"	2,330.000	LF	9.50		
1718	907-663-A001	Network Switch, Type A	7.000	EA	1,991.00		
1719	907-663-A002	Network Switch, Type B	4.000	EA	2,397.00		
1464	682-A005	Underground Branch Circuit, AWG 1/0, 3 Conductor	2,550.000	LF	12.75		
1465	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	8,940.000	LF	9.70		
1466	682-A025	Underground Branch Circuit, AWG 3/0, 3 Conductor	210.000	LF	14.00		
1467	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	7,355.000	LF	5.80		
1468	682-B005	Underground Branch Circuit, Jacked or Bored, AWG 1/0, 3 Conductor	65.000	LF	21.75		
1469	682-B016	Underground Branch Circuit, Jacked or Bored, AWG 2, 3 Conductor	683.000	LF	18.75		
1471	682-B022	Underground Branch Circuit, Jacked or Bored, AWG 3/0, 3 Conductor	76.000	LF	18.50		
0030	202-B007	Removal of Asphalt Pavement, All Depths	34,044.000	SY	3.30		
0800	606-B001	Guard Rail, Class A, Type 1	650.000	LF	24.50		
0690	603-CE018	44" x 27" Concrete Arch Pipe, Class A III	168.000	LF	102.00		
0700	603-CF002	22" x 13" Concrete Arch Pipe End Section	16.000	EA	1,283.00		
0710	603-CF003	29" x 18" Concrete Arch Pipe End Section	4.000	EA	1,423.00		
0720	603-CF004	36" x 23" Concrete Arch Pipe End Section	4.000	EA	1,860.00		
0730	603-CF005	44" x 27" Concrete Arch Pipe End Section	4.000	EA	2,105.00		
0740	603-SB012	18" Branch Connections, Stub into Box Culvert	1.000	EA	806.50		
0830	606-E005	Guard Rail, Terminal End Section, Flared	5.000	EA	2,783.00		
0840	606-E007	Guard Rail, Terminal End Section, Non-Flared	2.000	EA	3,050.00		
0850	607-B020	60" Type II Chain Link Fence, Class II	18,550.000	LF	6.10		

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29						\$25,999,999.64	
Ref#	Item	Item Description	Item Qty	Units	4		
0040	202-B052	Removal of Concrete Driveways, All Depths	410.000	SY		7.60	
0650	603-CB008	48" Reinforced Concrete End Section	2.000	EA		2,504.00	
0660	603-CE002	22" x 13" Concrete Arch Pipe, Class A III	744.000	LF		52.00	
0670	603-CE008	29" x 18" Concrete Arch Pipe, Class A III	128.000	LF		61.50	
0680	603-CE013	36" x 23" Concrete Arch Pipe, Class A III	128.000	LF		87.25	
1690	907-637-K001	Traffic Signal Conduit Bank, Aerial Supported, Type 1, 2 @ 2"	1,985.000	LF		36.00	
1479	683-A129	Lighting Assembly, High Mast, LED, Type 130-8-S	4.000	EA		38,880.00	
1481	683-B197	Lighting Assembly, Low Mast, LED, Type 40-1-15-268	34.000	EA		4,201.00	
1482	683-D001	Portable Electric Power Units	1.000	EA		3,007.00	
1483	684-A004	Pole Foundation, 30" Diameter	56.000	CY		1,049.00	
1484	684-A007	Pole Foundation, 48" Diameter	110.000	CY		770.50	
1485	684-B004	Slip Casing, 30" Diameter	9.000	LF		32.00	
1486	684-B007	Slip Casing, 48" Diameter	21.000	LF		65.25	
1487	699-A001	Roadway Construction Stakes	1.000	LS		217,340.00	
1488	815-A007	Loose Riprap, Size 300	5,500.000	TON		75.25	
1489	815-F002	Sediment Control Stone	971.000	TON		56.25	
1730	907-906001	Trainees	1,040.000	HRS		5.00	
1790	221-A001	Concrete Paved Ditch	28.000	CY		699.00	
1800	501-K001	Transverse Grooving	1,716.000	SY		2.40	
1810	803-I004	PDA Test Pile, Steel Pipe Pile	3.000	EA		22,120.00	
1820	803-J001	Pile Restrike	2.000	EA		3,444.00	
1830	803-P001	24" Steel Pipe Piling, Wall Thickness 0.500"	3,775.000	LF		128.00	
1880	907-804-A002	Bridge Concrete, Class AA	266.000	CY		1,116.00	
1890	907-804-A004	Bridge Concrete, Class BD	485.000	CY		919.00	
1840	804-C167	99' Prestressed Concrete Beam, Type BT-54	2,360.000	LF		278.00	
1850	805-A001	Reinforcement	162,682.000	LBS		1.30	

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29						\$25,999,999.64	
Ref#	Item	Item Description	Item Qty	Units		4	
1860	809-A001	Retaining Wall System	8,525.000	SF		172.00	
1870	813-A002	Concrete Railing, 32"	598.000	LF		69.50	
1472	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	397.000	LF		14.75	
1459	656-A002	Dynamic Message Sign, Type 2	2.000	EA		106,390.00	
1461	656-A003	Dynamic Message Sign, Type 3	2.000	EA		37,110.00	
1712	907-659-A001	Traffic Management Center Modifications	1.000	LS		76,480.00	
1462	660-A003	Equipment Cabinet, Type B	4.000	EA		5,191.00	
1463	660-A004	Equipment Cabinet, Type C	2.000	EA		9,461.00	
1714	907-661-A004	Fiber Optic Cable, 72 SM	39,975.000	LF		2.70	
1473	682-D003	Underground Pull Box	27.000	EA		1,803.00	
1474	682-E003	Underground Junction Box With Concrete Pad	34.000	EA		1,407.00	
1475	682-F002	Secondary Power Controllers	1.000	EA		15,630.00	
1476	683-A126	Lighting Assembly, High Mast, LED, Type 110-8-S	1.000	EA		38,780.00	
1477	683-A127	Lighting Assembly, High Mast, LED, Type 110-6-S	5.000	EA		35,540.00	
1478	683-A128	Lighting Assembly, High Mast, LED, Type 110-6-A	2.000	EA		35,540.00	
1740	304-F001	3/4" and Down Crushed Stone Base	62,600.000	TON			
1750	304-F002	Size 610 Crushed Stone Base	62,600.000	TON		40.00	
1760	304-F003	Size 825B Crushed Stone Base	62,600.000	TON			
0360	403-A001	12.5-mm, HT, Asphalt Pavement	9,629.000	TON		88.00	
0370	403-A002	12.5-mm, MT, Asphalt Pavement	4,858.000	TON		88.00	
0380	403-A003	12.5-mm, ST, Asphalt Pavement	1,114.000	TON		92.00	
0390	403-A004	19-mm, HT, Asphalt Pavement	10,592.000	TON		84.00	
0400	403-A005	19-mm, MT, Asphalt Pavement	7,894.000	TON		85.00	
0410	403-A006	19-mm, ST, Asphalt Pavement	12,220.000	TON		80.00	
0420	403-A013	9.5-mm, HT, Asphalt Pavement	5,718.000	TON		106.00	
0220	220-A001	Insect Pest Control	24.000	ACRE		30.00	

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29						\$25,999,999.64	
Ref#	Item	Item Description	Item Qty	Units		4	
0230	221-A001	Concrete Paved Ditch	81.000	CY		699.00	
0240	223-A001	Mowing	94.000	ACRE		50.00	
0250	225-A001	Grassing	47.000	ACRE		963.00	
0260	225-B001	Agricultural Limestone	24.000	TON		107.00	
0270	225-C001	Mulch, Vegetative Mulch	94.000	TON		214.00	
1032	619-F1001	Concrete Median Barrier, Precast	1,000.000	LF		23.00	
1082	619-J1005	Impact Attenuator, 70 MPH	2.000	EA		9,097.00	
1084	619-J2005	Impact Attenuator, 70 MPH, Replacement Package	2.000	EA		4,816.00	
0280	226-A001	Temporary Grassing	47.000	ACRE		883.00	
0290	227-A001	Hydroseeding	47.000	ACRE		2,943.00	
0300	234-A001	Temporary Silt Fence	72,500.000	LF		2.10	
0310	234-D001	Inlet Siltation Guard	2.000	EA		508.50	
0430	403-A014	9.5-mm, MT, Asphalt Pavement	3,643.000	TON		105.50	
0440	403-A015	9.5-mm, ST, Asphalt Pavement	821.000	TON		113.00	
0450	406-A002	Cold Milling of Bituminous Pavement, All Depths	2,000.000	SY		7.10	
0460	407-A001	Asphalt for Tack Coat	15,809.000	GAL		3.90	
0470	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	118.000	LF		11.00	
0480	423-A001	Rumble Strips, Ground In	13.000	MI		538.00	
0490	502-A001	Reinforced Cement Concrete Bridge End Pavement	258.000	SY		296.50	
0500	601-A001	Class "B" Structural Concrete	478.000	CY		966.00	
0510	601-B001	Class "B" Structural Concrete, Minor Structures	55.000	CY		1,178.00	
0520	602-A001	Reinforcing Steel	74,216.000	LBS		1.10	
0530	603-ALT003	18" Type A Alternate Pipe	316.000	LF		37.75	
0540	603-CA012	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	408.000	LF		42.36	
0980	619-A5001	Temporary Traffic Stripe, Detail	21,261.000	LF		0.10	
0990	619-A6001	Temporary Traffic Stripe, Legend	87.000	SF		2.10	

Interchange construction on I-59 at SR 42, known as Federal Aid Project No. NH-0059-01(075) / 102334301 in Forrest County.					Eutaw Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$26,713,938.29						\$25,999,999.64	
Ref#	Item	Item Description	Item Qty	Units		4	
1000	619-A6002	Temporary Traffic Stripe, Legend	1,115.000	LF		0.55	
1010	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	472.000	SF		5.40	
1020	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,279.000	SF		5.40	
1030	619-E1001	Flashing Arrow Panel, Type C	2.000	EA		1,980.00	
1510	907-619-E3001	Changeable Message Sign	6.000	EA		9,174.00	
1040	619-G4001	Barricades, Type III, Double Faced	288.000	LF		15.00	
1050	619-G4005	Barricades, Type III, Single Faced	72.000	LF		12.75	
1060	619-G5001	Free Standing Plastic Drums	207.000	EA		48.25	
1070	619-G7001	Warning Lights, Type "B"	15.000	EA		198.04	
1330	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	456.000	LBS		3.80	
1340	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	477.000	LBS		3.80	
1350	630-E003	Structural Steel Angles & Bars, 4" x 4" x 5/16" Angles	591.000	LBS		3.80	
1360	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	1,281.000	LBS		2.70	
1370	630-F006	Delineators, Guard Rail, White	32.000	EA		19.25	
1380	630-F010	Delineators, Post Mounted, Double White	126.000	EA		51.25	
1390	630-F011	Delineators, Post Mounted, Double Yellow	77.000	EA		51.25	
0020	202-A001	Removal of Obstructions	1.000	LS		350,000.00	