

Mill & Overlay approximately 1 mile of SR 878 through the Town of Walnut Grove, and 2 miles of SR 492 through the Town of Walnut Grove, known as State Project Nos. MP-5878-40(001) / 306660301 & MP-5492-40(003) / 306660302 in Leake County.					Dickerson & Bowen, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,196,682.50					\$1,345,188.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	1,123.000	SY	14.50		
0020	202-B009	Removal of Asphalt Pavement, Failed Areas	456.000	SY	54.00		
0030	202-B080	Removal of Concrete Sidewalk	52.000	SY	34.00		
0040	202-B138	Removal of Guard Rail Bridge End Section	8.000	EA	275.00		
0050	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	960.000	LF	6.00		
0060	202-B165	Removal of Inlets, All Sizes	1.000	EA	3,600.00		
0070	202-B191	Removal of Pipe, 8" And Above	273.000	LF	31.00		
0080	202-B240	Removal of Traffic Stripe	1,576.000	LF	2.00		
0090	203-G001	Excess Excavation, FM, AH	200.000	CY	31.00		
0100	206-A001	Structure Excavation	128.000	CY	38.00		
0110	206-B001	Select Material for Undercuts, Contractor Furnished, FM	113.000	CY	42.00		
0120	216-A001	Solid Sodding	44.000	SY	24.00		
0130	304-A004	Granular Material, LVM, Class 5, Group C	371.000	CY	60.00		
0140	403-A003	12.5-mm, ST, Asphalt Pavement	275.000	TON	185.00		
0150	403-A015	9.5-mm, ST, Asphalt Pavement	4,850.000	TON	106.00		
0160	403-B003	12.5-mm, ST, Asphalt Pavement, Leveling	163.000	TON	159.00		
0170	406-D001	Fine Milling of Bituminous Pavement, All Depths	40,660.000	SY	2.20		
0180	407-A001	Asphalt for Tack Coat	4,090.000	GAL	3.00		
0190	503-C010	Saw Cut, Full Depth	871.000	LF	11.00		
0200	601-B001	Class "B" Structural Concrete, Minor Structures	1.000	CY	5,500.00		
0210	602-A001	Reinforcing Steel	70.000	LBS	1.50		
0220	603-ALT001	12" Type A Alternate Pipe	15.000	LF	63.00		
0230	603-ALT003	18" Type A Alternate Pipe	118.000	LF	84.00		
0240	603-ALT006	24" Type A Alternate Pipe	22.000	LF	105.00		
0250	603-CE002	22" x 13" Concrete Arch Pipe, Class A III	31.000	LF	75.00		
0260	603-CE015	36" x 23" Concrete Arch Pipe, Class A IV	87.000	LF	120.00		

Mill & Overlay approximately 1 mile of SR 878 through the Town of Walnut Grove, and 2 miles of SR 492 through the Town of Walnut Grove, known as State Project Nos. MP-5878-40(001) / 306660301 & MP-5492-40(003) / 306660302 in Leake County.					Dickerson & Bowen, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,196,682.50					\$1,345,188.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	604-B001	Gratings	180.000	LBS	8.00		
0280	606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	560.000	LF	22.00		
0290	606-D020	Guard Rail, Bridge End Section, Type H, Metal Post	8.000	EA	1,850.00		
0300	606-E005	Guard Rail, Terminal End Section, Flared	8.000	EA	2,750.00		
0310	608-B001	Concrete Sidewalk, With Reinforcement	9.000	SY	350.00		
0320	618-A001	Maintenance of Traffic	1.000	LS	110,000.00		
0330	619-A1001	Temporary Traffic Stripe, Continuous White	12.000	MI	800.00		
0340	619-A2001	Temporary Traffic Stripe, Continuous Yellow	12.000	MI	900.00		
0350	619-A4002	Temporary Traffic Stripe, Skip Yellow	6.000	MI	900.00		
0360	619-A5001	Temporary Traffic Stripe, Detail	12,216.000	LF	0.25		
0370	619-A6001	Temporary Traffic Stripe, Legend	1,510.000	SF	1.00		
0380	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	214.000	SF	9.00		
0390	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	502.000	SF	9.00		
0400	619-G4001	Barricades, Type III, Double Faced	36.000	LF	15.00		
0410	619-G4005	Barricades, Type III, Single Faced	48.000	LF	15.00		
0420	620-A001	Mobilization	1.000	LS	160,000.00		
0430	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	6.000	MI	3,300.00		
0440	626-D001	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	2.000	MI	1,600.00		
0450	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	4.000	MI	3,100.00		
0460	626-G001	Thermoplastic Detail Stripe, Blue-ADA	575.000	LF	6.00		
0470	626-G004	Thermoplastic Double Drop Detail Stripe, White	4,441.000	LF	1.50		
0480	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	1,092.000	LF	1.50		
0490	626-H001	Thermoplastic Double Drop Legend, White	955.000	SF	8.00		
0500	627-J001	Two-Way Clear Reflective High Performance Raised Markers	660.000	EA	6.00		
0510	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	335.000	EA	6.00		
0520	630-F006	Delineators, Guard Rail, White	32.000	EA	18.00		

Mill & Overlay approximately 1 mile of SR 878 through the Town of Walnut Grove, and 2 miles of SR 492 through the Town of Walnut Grove, known as State Project Nos. MP-5878-40(001) / 306660301 & MP-5492-40(003) / 306660302 in Leake County.					Dickerson & Bowen, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,196,682.50					\$1,345,188.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0530	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	4.000	EA	75.00		
0540	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	4.000	EA	75.00		
0550	907-619-B001	Temporary Portable Rumble Strips	132.000	LF	200.00		
0560	907-619-E3001	Changeable Message Sign	3.000	EA	10,000.00		
0570	907-626-H001	Thermoplastic Legend, Blue-ADA Handicap Symbol	7.000	EA	500.00		
0580	304-G001	Size 3/4" and Down Crushed Stone Base, AEA	15.000	CY			
0590	304-G002	Size 610 Crushed Stone Base, AEA	15.000	CY	300.00		
0600	304-G003	Size 825B Crushed Stone Base, AEA	15.000	CY			
0610	907-808-A002	Joint Repair	828.000	LF	1.00		
0620	907-823-A001	Preformed Joint Seal, Type I	273.000	LF	25.00		
0630	907-823-A002	Preformed Joint Seal, Type II	141.000	LF	29.00		
0640	907-823-B001	Saw Cut, Type I	546.000	LF	8.00		
0650	907-823-B002	Saw Cut, Type II	282.000	LF	8.00		