

Construction of a Roundabout on SR 7 at Eddie L. Smith Drive, known as Federal Aid Project No. HSIP-0019-02(060) / 108069301 in Marshall County.					Gregory Construction Services, Inc.	Cook & Son, LLC	Phillips Contracting Co., Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,178,834.77					\$2,293,448.90	\$2,417,871.76	\$2,647,359.78
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS	87,000.00	5,000.00	100,000.00
0020	202-B007	Removal of Asphalt Pavement, All Depths	1,894.000	SY	11.50	14.00	20.00
0030	202-B052	Removal of Concrete Driveways, All Depths	1,018.000	SY	28.00	14.00	25.00
0040	202-B059	Removal of Concrete Median & Island Pavement, All Depths	560.000	SY	29.00	15.00	22.00
0050	202-B088	Removal of Curb & Gutter, All Types	667.000	LF	17.00	12.00	15.00
0060	202-B165	Removal of Inlets, All Sizes	1.000	EA	1,035.00	500.00	1,500.00
0070	202-B171	Removal of Legend, All Types	162.000	LF	3.80	25.00	5.00
0080	202-B172	Removal of Legend, All Types	164.000	SF	3.80	20.00	5.00
0090	202-B191	Removal of Pipe, 8" And Above	217.000	LF	25.00	20.00	29.00
0100	202-B240	Removal of Traffic Stripe	11,275.000	LF	3.80	3.00	3.60
0110	203-EX020	Borrow Excavation, AH, FME, Class B9	2,050.000	CY	34.00	15.00	27.50
0120	203-G002	Excess Excavation, LVM, AH	500.000	CY	17.00	16.00	25.00
0130	209-A005	Geotextile Stabilization, Type V, Non-Woven	5,598.000	SY	3.50	2.50	3.50
0140	211-B001	Topsoil for Slope Treatment, Contractor Furnished	1,075.000	CY	20.00	12.00	30.00
0150	213-C001	Superphosphate	1.000	TON	1,000.00	1,500.00	1,775.00
0160	216-A001	Solid Sodding	808.000	SY	8.90	10.00	12.00
0170	217-A001	Ditch Liner	975.000	SY	3.25	4.00	4.75
0180	219-A001	Watering	17.000	KGAL	20.00	20.00	20.00
0190	220-A001	Insect Pest Control	2.000	ACRE	30.00	30.00	30.00
0200	221-A001	Concrete Paved Ditch	87.000	CY	600.00	850.00	766.00
0210	223-A001	Mowing	2.000	ACRE	50.00	50.00	50.00
0220	225-A001	Grassing	2.000	ACRE	1,900.00	2,500.00	2,960.00
0230	225-B001	Agricultural Limestone	1.000	TON	370.00	500.00	592.00
0240	225-C001	Mulch, Vegetative Mulch	4.000	TON	440.00	250.00	296.00
0250	226-A001	Temporary Grassing	2.000	ACRE	1,900.00	1,750.00	2,100.00
0260	234-A001	Temporary Silt Fence	6,900.000	LF	5.00	4.50	5.35

Construction of a Roundabout on SR 7 at Eddie L. Smith Drive, known as Federal Aid Project No. HSIP-0019-02(060) / 108069301 in Marshall County.					Gregory Construction Services, Inc.	Cook & Son, LLC	Phillips Contracting Co., Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,178,834.77					\$2,293,448.90	\$2,417,871.76	\$2,647,359.78
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0270	237-A002	Wattles, 20"	300.000	LF	6.00	10.00	12.00
0280	239-A001	Temporary Slope Drains	50.000	LF	30.00	15.00	25.00
0290	246-A001	Sandbags	100.000	LF	17.00	10.00	12.00
0300	304-B002	Granular Material, Class 3, Group D	5,817.000	TON	33.00	50.00	47.00
0310	403-A003	12.5-mm, ST, Asphalt Pavement	20.000	TON	1,265.00	1,000.00	1,250.00
0320	403-A006	19-mm, ST, Asphalt Pavement	92.000	TON	500.00	400.00	500.00
0330	403-A015	9.5-mm, ST, Asphalt Pavement	1,213.000	TON	160.00	128.00	160.00
0340	403-B003	12.5-mm, ST, Asphalt Pavement, Leveling	137.000	TON	400.00	315.00	395.00
0350	406-D001	Fine Milling of Bituminous Pavement, All Depths	8,482.000	SY	2.75	5.00	2.91
0360	407-A001	Asphalt for Tack Coat	1,310.000	GAL	4.40	3.50	4.40
0370	503-C010	Saw Cut, Full Depth	7,457.000	LF	4.00	12.00	10.00
0380	601-B001	Class "B" Structural Concrete, Minor Structures	5.000	CY	1,800.00	1,050.00	1,500.00
0390	602-A001	Reinforcing Steel	274.000	LBS	8.00	5.00	10.00
0400	603-CA011	18" Reinforced Concrete Pipe, Class III	232.000	LF	57.00	41.18	51.50
0410	604-B001	Gratings	250.000	LBS	6.00	2.25	5.00
0420	609-B003	Concrete Curb, Special Design	937.000	LF	44.00	30.00	36.45
0430	609-C001	Concrete Integral Curb, Type 1	239.000	LF	28.00	37.50	19.80
0440	609-D008	Combination Concrete Curb and Gutter Type 3A	6,178.000	LF	23.00	30.00	30.75
0450	614-A001	Concrete Driveway, Without Reinforcement	877.000	SY	53.00	75.00	83.80
0460	614-B001	Concrete Driveway, With Reinforcement	789.000	SY	56.00	80.00	86.20
0470	616-A001	Concrete Median and/or Island Pavement, 10-inch	57.000	SY	130.00	100.00	100.00
0480	616-A003	Concrete Median and/or Island Pavement, 12-inch	585.000	SY	80.00	120.00	128.30
0490	616-A004	Concrete Median and/or Island Pavement, 4-inch	1,295.000	SY	36.01	70.00	73.37
0500	618-A001	Maintenance of Traffic	1.000	LS	80,000.00	35,000.00	100,000.00
0510	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	1,901.000	LF	1.90	1.50	1.76
0520	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	10,613.000	LF	1.90	1.50	1.76

Construction of a Roundabout on SR 7 at Eddie L. Smith Drive, known as Federal Aid Project No. HSIP-0019-02(060) / 108069301 in Marshall County.					Gregory Construction Services, Inc.	Cook & Son, LLC	Phillips Contracting Co., Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,178,834.77					\$2,293,448.90	\$2,417,871.76	\$2,647,359.78
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0530	619-A5002	Temporary Traffic Stripe, Detail, Paint	10,369.000	LF	1.90	1.50	1.76
0540	619-A6002	Temporary Traffic Stripe, Legend	144.000	LF	1.90	1.50	1.76
0550	619-A6003	Temporary Traffic Stripe, Legend, Paint	152.000	SF	5.00	4.00	4.75
0560	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	185.000	SF	8.80	7.00	8.25
0570	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	524.000	SF	8.80	7.00	8.25
0580	619-G4001	Barricades, Type III, Double Faced	180.000	LF	25.00	20.00	23.50
0590	619-G5001	Free Standing Plastic Drums	245.000	EA	63.00	50.00	60.00
0600	619-G7001	Warning Lights, Type "B"	9.000	EA	253.00	200.00	236.00
0610	620-A001	Mobilization	1.000	LS	115,000.00	346,536.80	200,000.00
0620	626-C003	6" Thermoplastic Edge Stripe, Continuous White	6,819.000	LF	2.50	2.00	2.35
0630	626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	4,211.000	LF	2.50	2.00	2.35
0640	626-F004	6" Thermoplastic Edge Stripe, Continuous Yellow	1,890.000	LF	2.50	2.00	2.35
0650	626-G002	Thermoplastic Detail Stripe, White	266.000	LF	3.80	3.00	3.53
0660	626-G003	Thermoplastic Detail Stripe, Yellow	2,337.000	LF	3.80	3.00	3.53
0670	626-H004	Thermoplastic Legend, White	605.000	SF	12.60	10.00	11.75
0680	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	146.000	EA	19.00	15.00	17.65
0690	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	134.000	SF	26.00	21.00	26.25
0700	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	72.000	SF	28.00	22.00	27.50
0710	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	459.000	SF	60.00	48.00	60.00
0720	630-C001	Square Tube Posts, 4.0 lb/ft	129.000	LF	32.00	25.00	31.25
0730	630-C005	Square Tube Posts, 2.0 lb/ft	276.000	LF	20.00	16.00	20.00
0740	630-D008	Structural Steel Beams, W6 x 9	146.000	LF	82.00	65.00	81.25
0750	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	110.000	LBS	6.00	5.00	6.25
0760	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	83.000	LBS	6.00	5.00	6.25
0770	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	50.000	LF	32.00	42.35	31.25
0780	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	2,500.000	LF	6.70	11.00	6.70

Construction of a Roundabout on SR 7 at Eddie L. Smith Drive, known as Federal Aid Project No. HSIP-0019-02(060) / 108069301 in Marshall County.					Gregory Construction Services, Inc.	Cook & Son, LLC	Phillips Contracting Co., Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,178,834.77					\$2,293,448.90	\$2,417,871.76	\$2,647,359.78
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0790	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	196.000	LF	21.50	27.20	21.25
0800	682-E003	Underground Junction Box With Concrete Pad	18.000	EA	2,530.00	1,740.00	3,125.00
0810	682-F001	Secondary Power Controller	1.000	EA	11,395.00	11,115.00	11,250.00
0820	683-B200	Lighting Assembly, Low Mast, LED, Type 30-1-10-17	18.000	EA	6,330.00	3,620.00	6,250.00
0830	684-A004	Pole Foundation, 30" Diameter	24.000	CY	1,050.00	1,640.00	1,040.00
0840	684-B004	Slip Casing, 30" Diameter	126.000	LF	1.30	1.00	1.25
0850	699-A001	Roadway Construction Stakes	1.000	LS	104,000.00	30,000.00	50,000.00
0860	907-619-E3001	Changeable Message Sign	3.000	EA	8,230.00	6,500.00	7,650.00
0870	304-F001	3/4" and Down Crushed Stone Base	2,385.000	TON		57.00	47.00
0880	304-F002	Size 610 Crushed Stone Base	2,385.000	TON	60.00		
0890	304-F003	Size 825B Crushed Stone Base	2,385.000	TON			

Construction of a Roundabout on SR 7 at Eddie L. Smith Drive, known as Federal Aid Project No. HSIP-0019-02(060) / 108069301 in Marshall County.					J. M. Duncan, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,178,834.77					\$2,750,083.30		
Ref#	Item	Item Description	Item Qnty	Units			
					4		
0010	201-A001	Clearing and Grubbing	1.000	LS	60,000.00		
0020	202-B007	Removal of Asphalt Pavement, All Depths	1,894.000	SY	20.00		
0030	202-B052	Removal of Concrete Driveways, All Depths	1,018.000	SY	20.00		
0040	202-B059	Removal of Concrete Median & Island Pavement, All Depths	560.000	SY	20.00		
0050	202-B088	Removal of Curb & Gutter, All Types	667.000	LF	20.00		
0060	202-B165	Removal of Inlets, All Sizes	1.000	EA	1,000.00		
0070	202-B171	Removal of Legend, All Types	162.000	LF	10.00		
0080	202-B172	Removal of Legend, All Types	164.000	SF	10.00		
0090	202-B191	Removal of Pipe, 8" And Above	217.000	LF	40.00		
0100	202-B240	Removal of Traffic Stripe	11,275.000	LF	3.60		
0110	203-EX020	Borrow Excavation, AH, FME, Class B9	2,050.000	CY	30.00		
0120	203-G002	Excess Excavation, LVM, AH	500.000	CY	25.00		
0130	209-A005	Geotextile Stabilization, Type V, Non-Woven	5,598.000	SY	3.50		
0140	211-B001	Topsoil for Slope Treatment, Contractor Furnished	1,075.000	CY	40.00		
0150	213-C001	Superphosphate	1.000	TON	1,785.00		
0160	216-A001	Solid Sodding	808.000	SY	12.00		
0170	217-A001	Ditch Liner	975.000	SY	5.00		
0180	219-A001	Watering	17.000	KGAL	20.00		
0190	220-A001	Insect Pest Control	2.000	ACRE	30.00		
0200	221-A001	Concrete Paved Ditch	87.000	CY	1,000.00		
0210	223-A001	Mowing	2.000	ACRE	50.00		
0220	225-A001	Grassing	2.000	ACRE	3,000.00		
0230	225-B001	Agricultural Limestone	1.000	TON	600.00		
0240	225-C001	Mulch, Vegetative Mulch	4.000	TON	300.00		
0250	226-A001	Temporary Grassing	2.000	ACRE	2,080.00		
0260	234-A001	Temporary Silt Fence	6,900.000	LF	5.35		

Construction of a Roundabout on SR 7 at Eddie L. Smith Drive, known as Federal Aid Project No. HSIP-0019-02(060) / 108069301 in Marshall County.					J. M. Duncan, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,178,834.77					\$2,750,083.30		
Ref#	Item	Item Description	Item Qnty	Units	4		
0270	237-A002	Wattles, 20"	300.000	LF	12.00		
0280	239-A001	Temporary Slope Drains	50.000	LF	20.00		
0290	246-A001	Sandbags	100.000	LF	12.00		
0300	304-B002	Granular Material, Class 3, Group D	5,817.000	TON	60.00		
0310	403-A003	12.5-mm, ST, Asphalt Pavement	20.000	TON	1,200.00		
0320	403-A006	19-mm, ST, Asphalt Pavement	92.000	TON	475.00		
0330	403-A015	9.5-mm, ST, Asphalt Pavement	1,213.000	TON	150.00		
0340	403-B003	12.5-mm, ST, Asphalt Pavement, Leveling	137.000	TON	375.00		
0350	406-D001	Fine Milling of Bituminous Pavement, All Depths	8,482.000	SY	6.00		
0360	407-A001	Asphalt for Tack Coat	1,310.000	GAL	5.00		
0370	503-C010	Saw Cut, Full Depth	7,457.000	LF	13.00		
0380	601-B001	Class "B" Structural Concrete, Minor Structures	5.000	CY	2,100.00		
0390	602-A001	Reinforcing Steel	274.000	LBS	6.00		
0400	603-CA011	18" Reinforced Concrete Pipe, Class III	232.000	LF	75.00		
0410	604-B001	Gratings	250.000	LBS	3.50		
0420	609-B003	Concrete Curb, Special Design	937.000	LF	45.00		
0430	609-C001	Concrete Integral Curb, Type 1	239.000	LF	45.00		
0440	609-D008	Combination Concrete Curb and Gutter Type 3A	6,178.000	LF	35.00		
0450	614-A001	Concrete Driveway, Without Reinforcement	877.000	SY	90.00		
0460	614-B001	Concrete Driveway, With Reinforcement	789.000	SY	95.00		
0470	616-A001	Concrete Median and/or Island Pavement, 10-inch	57.000	SY	160.00		
0480	616-A003	Concrete Median and/or Island Pavement, 12-inch	585.000	SY	130.00		
0490	616-A004	Concrete Median and/or Island Pavement, 4-inch	1,295.000	SY	85.00		
0500	618-A001	Maintenance of Traffic	1.000	LS	60,000.00		
0510	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	1,901.000	LF	1.80		
0520	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	10,613.000	LF	1.80		

Construction of a Roundabout on SR 7 at Eddie L. Smith Drive, known as Federal Aid Project No. HSIP-0019-02(060) / 108069301 in Marshall County.					J. M. Duncan, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,178,834.77					\$2,750,083.30		
Ref#	Item	Item Description	Item Qnty	Units	4		
0530	619-A5002	Temporary Traffic Stripe, Detail, Paint	10,369.000	LF	1.80		
0540	619-A6002	Temporary Traffic Stripe, Legend	144.000	LF	1.80		
0550	619-A6003	Temporary Traffic Stripe, Legend, Paint	152.000	SF	4.75		
0560	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	185.000	SF	8.35		
0570	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	524.000	SF	8.35		
0580	619-G4001	Barricades, Type III, Double Faced	180.000	LF	23.80		
0590	619-G5001	Free Standing Plastic Drums	245.000	EA	60.00		
0600	619-G7001	Warning Lights, Type "B"	9.000	EA	240.00		
0610	620-A001	Mobilization	1.000	LS	130,000.00		
0620	626-C003	6" Thermoplastic Edge Stripe, Continuous White	6,819.000	LF	2.40		
0630	626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	4,211.000	LF	2.40		
0640	626-F004	6" Thermoplastic Edge Stripe, Continuous Yellow	1,890.000	LF	2.40		
0650	626-G002	Thermoplastic Detail Stripe, White	266.000	LF	3.60		
0660	626-G003	Thermoplastic Detail Stripe, Yellow	2,337.000	LF	3.60		
0670	626-H004	Thermoplastic Legend, White	605.000	SF	12.00		
0680	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	146.000	EA	18.00		
0690	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	134.000	SF	25.00		
0700	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	72.000	SF	26.15		
0710	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	459.000	SF	57.00		
0720	630-C001	Square Tube Posts, 4.0 lb/ft	129.000	LF	29.75		
0730	630-C005	Square Tube Posts, 2.0 lb/ft	276.000	LF	19.00		
0740	630-D008	Structural Steel Beams, W6 x 9	146.000	LF	77.30		
0750	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	110.000	LBS	6.00		
0760	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	83.000	LBS	6.00		
0770	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	50.000	LF	30.00		
0780	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	2,500.000	LF	6.30		

Construction of a Roundabout on SR 7 at Eddie L. Smith Drive, known as Federal Aid Project No. HSIP-0019-02(060) / 108069301 in Marshall County.					J. M. Duncan, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,178,834.77					\$2,750,083.30		
Ref#	Item	Item Description	Item Qty	Units	4		
0790	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	196.000	LF	20.20		
0800	682-E003	Underground Junction Box With Concrete Pad	18.000	EA	2,380.00		
0810	682-F001	Secondary Power Controller	1.000	EA	10,700.00		
0820	683-B200	Lighting Assembly, Low Mast, LED, Type 30-1-10-17	18.000	EA	5,945.00		
0830	684-A004	Pole Foundation, 30" Diameter	24.000	CY	986.00		
0840	684-B004	Slip Casing, 30" Diameter	126.000	LF	1.20		
0850	699-A001	Roadway Construction Stakes	1.000	LS	60,000.00		
0860	907-619-E3001	Changeable Message Sign	3.000	EA	7,500.00		
0870	304-F001	3/4" and Down Crushed Stone Base	2,385.000	TON			
0880	304-F002	Size 610 Crushed Stone Base	2,385.000	TON	65.00		
0890	304-F003	Size 825B Crushed Stone Base	2,385.000	TON			