

Call 11 Mill & Overlay approximately 1.5 miles on SR 463 from the end of the 2-Lane section to east of Main Street, known as Federal Aid Project No. NHPP-6947-01(001) / 108244301 in Madison County.

Q1. 1.) Will milling and paving take place at the I 55 Ramps? If so what are the limits?
2.) Could you provide the table for the sidewalk and ADA repairs? The markups and the maps are very faint.

A1. 1.) No. 2.) See addendum.

Q2. In the last paragraph on page 116, the proposal states that payment for saw cuts will be made using the appropriate pay items. There is not a pay item for saw cut. Will the saw cuts be absorbed?

A2. See addendum.

Q3. 1.) The labeling on the Google Earth drawings for the replacement of sidewalks is not legible. Can a table be put out for the specific repairs? 2.) Some of the areas that you can read are labeled SS-2. There are some inlets that have damage, will these inlets be repaired under the sidewalk item or is this just to label the sidewalk around them? 3.) In some areas there are truncated domes and in other areas brick pavers are used to form the detectable warning. Will truncated domes be allowed in all areas while making the sidewalks ADA complaint?

A3. 1.) See addendum. 2.) The existing SS-2 inlets are shown as a reference point only. 3.) Truncated domes shall be used for the detectable warnings. The truncated domes shall be of the same coloring as existing detectable warnings in the area.

Q4. After seeing the schedule of areas to be repaired for sidewalk and being able to look at each area closer, a high percentage of the ramps that are to be made ADA complaint will need the curb and gutter removed and replaced in order to get the proper slope. There are no pay items for removal and replacement of curb and gutter. Will this be an absorbed item or will the contractor only be required to get the percentage that the curb and gutter will allow?

A4. If the existing curb and gutter needs to be removed and replaced in order to achieve the proper slope, then said work shall be absorbed into Pay Item No. 202-B: Removal of Concrete Sidewalk and Pay Item No. 608-B: Concrete Sidewalk with Reinforcement.