

**Call 05 Interchange Improvements & Placement of Stripe on I-20 from 0.6 miles east of US 61N to the Hinds County Line, known as Federal Aid Project No. IM-0020-01(261) / 108584301 in Warren County.**

Q1. Is there any information into how thick are the parking areas that are to be removed by Full Depth Milling at the Flowers Interchange?

A1. 7½" and variable.

Q2. Will rumble strips be required on any of the new pavement?

A2. No.

Q3. The following questions are concerning the Removal of Existing Stripe by High Pressure Water Blasting: **1.)** Will Temporary Stripe be required after removal due to the fact that Permanent Stripe cannot be placed until the pavement surface has dried? **2.)** Some of the Joint Sealant will likely be "Blown Out" during the Removal process. How will this be addressed?

A3. **1.)** No. **2.)** Should the Contractor elect to use water blasting for stripe removal, care shall be taken to ensure joint sealant is not damaged or removed during the stripe removal process. Any joint sealant damaged or removed during water blasting shall be replaced at no cost to the Department.