

Call 12 Placement of Stripe on various routes throughout the District, known as Federal Project No. HSIP-9999-02(394) / 109061301 in District 2.

- Q1. 1.) Will existing raised markers be removed and replaced or will just missing raised markers be replaced? 2.) Will there be any detail or legend thermoplastic? 3.) Will cold plastic on bridges be removed and replaced? 4.) There are numerous cracks with grass on the stripe, blading will not remove grass. Will each individual crack need to be cleaned?
- A1. 1.) Existing raised pavement markers will be removed and replaced. Removal of existing markers will be absorbed. 2.) No. 3.) Yes. The removal of existing cold plastic will be absorbed. 4.) No. The Contractor will only be required to perform a good surface cleaning.
- Q2. In the Scope of Work it states, "The Contractor shall be responsible for any damage caused by the Contractor's operations to the existing raised pavement markers (for example, painting over reflective surfaces)." If there is a RPM in the location of where a Center Line Audible Bar (907-626-A003 & 907-626-A004) goes, should the contractor skip that particular bar that is in conflict with the existing RPM or knock the RPM up and replace it with a new RPM that does not conflict with the Audible Bar?
- A2. The RPM will be removed prior to placement of the audible bar and replaced with a new RPM that does not conflict with the audible bar.