

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO.	<u>1</u>	DATED	<u>4/25/2022</u>	ADDENDUM NO.	_____	DATED	_____
ADDENDUM NO.	<u>2</u>	DATED	<u>4/29/2022</u>	ADDENDUM NO.	_____	DATED	_____
ADDENDUM NO.	_____	DATED	_____	ADDENDUM NO.	_____	DATED	_____

Number

Description

- 1 Postponed until May 4, 2022 Letting.
- 2 Revised Advertisement; Revised Table of Contents; Added Notice to Bidder No. 4244; Revised Bid Items; Amendment ESBx Download Required.

TOTAL ADDENDA: 2

(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____

Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

President

Address

Secretary

Address

Treasurer

Address

The following is my (our) itemized proposal.

STBG-0023-02(063) / 108677301

Scott County(ies)

Revised 01/26/2016

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 901 - ADVERTISEMENT

Electronic bids will be received by the Mississippi Transportation Commission at 10:00 o'clock A.M., Wednesday, May 04, 2022, from Bid Express Service and shortly thereafter publicly read in the Construction Division for:

Mill & Overlay approximately 8 miles on SR 35 from the Smith County Line to the pavement change south of I-20, known as Federal Aid Project No. STBG-0023-02(063) / 108677301 in Scott County.

In accordance with authority granted under Section 65-1-85 Mississippi Code of 1972, Annotated, the work to be accomplished under this contract has been declared by the Executive Director to be an emergency, and it is desired that you submit a bid for performing the needed and necessary work for alleviating the situation that exists at this site.

The attention of bidders is directed to the Contract Provisions governing selection and employment of labor. Minimum wage rates have been predetermined by the Secretary of Labor and are subject to Public Law 87-581, Work Hours Act of 1962, as set forth in the Contract Provisions.

The Mississippi Department of Transportation hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, sex, age, disability, religion or national origin in consideration for an award.

The award of this contract will be contingent upon the Contractor satisfying the DBE requirements.

Contractors may request permission to bid online at <http://shopmdot.ms.gov> at no cost. Upon approval, Contractors shall be eligible to submit a bid using Bid Express at <http://bidx.com>. Specimen proposals may be viewed and downloaded online at no cost at <http://mdot.ms.gov> or purchased online at <https://shopmdot.ms.gov>. Specimen proposals are available at a cost of Ten Dollars (\$10.00) per proposal plus a small convenience fee. Cash or checks will not be accepted as payment.

Bid bond, signed or countersigned by a Mississippi Agent or Qualified Nonresident Agent, with Power of Attorney attached, a Cashier's check or Certified Check for five (5%) percent of bid, payable to STATE OF MISSISSIPPI, must accompany each proposal.

The attention of bidders is directed to the provisions of Subsection 102.07 pertaining to irregular proposals and rejection of bids.

BRAD WHITE
EXECUTIVE DIRECTOR

**MISSISSIPPI DEPARTMENT OF TRANSPORTATION
TABLE OF CONTENTS**

PROJECT: STBG-0023-02(063)/108677301 - Scott

RE-ADVERTISEMENT NOTICE TO BIDDERS NO. 4136

Section 901 - Advertisement

Section 904 - Notice to Bidders

#1	Governing Specification, w/ Supplement
#2	Status of ROW, w/ Attachments
#3	Final Cleanup
#9	Federal Bridge Formula
#13	Safety Edge
#113	Tack Coat
#296	Reduced Speed Limit Signs
#445	Mississippi Agent or Qualified Nonresident Agent
#446	Traffic on Milled Surface in Urban Areas
#516	Errata and Modifications to the 2017 Standard Specifications
#1225	Early Notice to Proceed
#1226	Material Storage Under Bridges
#1241	Fuel and Material Adjustments
#1963	Guardrail Pads
#2206	MASH Compliant Devices
#2273	Mississippi Special Fuel Tax Law
#2611	Disadvantaged Business Enterprise In Federal-Aid Highway Construction, w/ Supplement
#2782	DBE Pre-Bid Meeting
#2954	Reflective Sheeting for Signs
#3599	Standard Drawings w/Supplement
#3676	Asphalt Gyratory Compactor Internal Angle Calibration
#3890	Contract Time
#3891	Specialty Items
#3892	Scope of Work
#3893	Temporary Construction Signs
#3894	Underground Utilities
#4113	Unique Entity ID Requirement For Federal Funded Projects
#4244	Pay Item Correction
906	Required Federal Contract Provisions -- FHWA 1273, w/Supplements

Section 907 - Special Provisions

907-102-2	Bidding Requirements and Conditions
907-105-1	Authority of the Engineer
907-108-4	Subletting of Contract
907-109-3	Measurement and Payment
907-204-1	Geogrid
907-619-6	Temporary Portable Rumble Strips

PROJECT: STBG-0023-02(063)/108677301 - Scott

907-701-3	Hydraulic Cement
907-702-4	Bituminous Materials
907-703-1	Gradation
907-705-1	Stone Riprap
907-707-3	Joint Materials
907-711-2	Plain Steel Wire
907-712-1	Fence and Guardrail
907-714-3	Miscellaneous Materials
907-718-1	Timber and Dimension Lumber
907-720-2	Acceptance Procedure for Glass Beads
907-721-2	Materials for Signs

Section 905 - Proposal, Proposal Bid Items, Combination Bid Proposal

Certification of Performance - Prior Federal-Aid Contracts

Certification Regarding Non-Collusion, Debarment and Suspension

SAM.GOV Registration and Unique Entity ID

Section 902 - Contract Form

Section 903 - Contract Bond Forms

Form -- OCR-485

Progress Schedule

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET
OF SECTION 905 AS ADDENDA)

04/29/2022 11:01 AM

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 -NOTICE TO BIDDERS NO. 4244

CODE: (SP)

DATE: 4/26/2022

SUBJECT: Pay Item Correction

PROJECT: STBG-0023-02(063) / 108677301 – Scott County

The Bidder's attention is called to Sheet Number 20 in the Notice to Bidders entitled "Scope of Work", Page No. 116 of the proposal.

The quantity shown for Crushed Stone Base in the table "Full Depth Failure Repair with Stone", and in the bid sheets, of 23,290 tons is in error. The correct quantity is 12,784 tons. The attached table shall govern.

The Bid Sheets are correct.

Full Depth Failure Repair with Stone.													
Location	STA	STA	Length (ft)	Width (ft)	Saw Cuts (ft)	Removal of Asphalt (All Depth) SY	Geotextile (SY)	GeoGrid (SY)	12.5mm MT. Leveling (TONS)	19mm MT Leveling (Tons)	Crushed Stone Base (Tons)	Estimated Excess	
RT & LT	92+75		275	28	331	855.556	1100.00	977.78	192.31	288.75	1577.81	733.33	
RT & LT	102+80		220	28	276	684.444	880.00	782.22	153.85	231.00	1262.25	586.67	
RT & LT	106+00		100	28	156	311.111	400.00	355.56	69.93	105.00	573.75	266.67	
LT	113+00		420	14	448	653.333	840.00	746.67	146.85	220.50	1275.75	560.00	
RT	115+50		170	14	198	264.444	340.00	302.22	59.44	89.25	516.38	226.67	
RT & LT	160+00		250	14	278	388.889	500.00	444.44	87.41	131.25	759.38	333.33	
RT & LT	175+00		150	28	206	466.667	600.00	533.33	104.90	157.50	860.63	400.00	
RT & LT	194+00		350	28	406	1088.889	1400.00	1244.44	244.76	367.50	2008.13	933.33	
RT	223+00		200	14	228	311.111	400.00	355.56	69.93	105.00	607.50	266.67	
RT	225+00		200	14	228	311.111	400.00	355.56	69.93	105.00	607.50	266.67	
LT	131+50		250	14	278	388.889	500.00	444.44	87.41	131.25	759.38	333.33	
	177+50		450	14	478	700.000	900.00	800.00	157.34	236.25	1366.88	600.00	
Asphalt Repair at Penn's			35	15	100	58.333				39.38		19.69	
			Totals				6482.778	8260.00	7342.22	1444.05	2207.625	12784.078	5526.354
QUANTITIES ARE ESTIMATED BASED ON FIELD CONDITIONS AND MAY BE MODIFIED AS DIRECTED BY THE ENGINEER.													

Section 905

STBG-0023-02(063)/108677301

Proposal (Sheet 2 - 1)

SCOTT

Mill & Overlay approximately 8 miles on SR 35 from the Smith County Line to the pavement change south of I-20, known as Federal Aid Project No. STBG-0023-02(063) / 108677301 in Scott County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	202-B007		6,483	Square Yard	Removal of Asphalt Pavement, All Depths
0020	202-B136		350	Linear Feet	Removal of Guard Rail
0030	203-G001	(E)	5,692	Cubic Yard	Excess Excavation, FM, AH
0040	209-A005		8,260	Square Yard	Geotextile Stabilization, Type V, Non-Woven
0050	304-D002	(GT)	3,955	Ton	Granular Material, Crushed Stone
0060	403-A002	(BA1)	15,295	Ton	12.5-mm, MT, Asphalt Pavement
0070	403-B002	(BA1)	2,515	Ton	12.5-mm, MT, Asphalt Pavement, Leveling
0080	403-B005	(BA1)	2,274	Ton	19-mm, MT, Asphalt Pavement, Leveling
0090	406-D001		131,720	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0100	407-A001	(A2)	13,172	Gallon	Asphalt for Tack Coat
0110	423-A001		15	Mile	Rumble Strips, Ground In
0120	503-C010		3,611	Linear Feet	Saw Cut, Full Depth
0130	606-B003		275	Linear Feet	Guard Rail, Class A, Type 1, "W" Beam, Metal Post
0140	606-E007		2	Each	Guard Rail, Terminal End Section, Non-Flared
0150	618-A001		1	Lump Sum	Maintenance of Traffic
0160	619-A1001		32	Mile	Temporary Traffic Stripe, Continuous White
0170	619-A2001		27	Mile	Temporary Traffic Stripe, Continuous Yellow
0180	619-A4002		18	Mile	Temporary Traffic Stripe, Skip Yellow
0190	619-A5001		4,700	Linear Feet	Temporary Traffic Stripe, Detail
0200	619-A6002		2,100	Linear Feet	Temporary Traffic Stripe, Legend
0210	619-D1001		620	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0220	619-D2001		196	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0230	619-G4001		24	Linear Feet	Barricades, Type III, Double Faced
0240	620-A001		1	Lump Sum	Mobilization
0250	626-B002		16	Mile	6" Thermoplastic Double Drop Traffic Stripe, Continuous White
0260	626-D001		6	Mile	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow
0270	626-E001		9	Mile	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow
0280	626-G004		1,600	Linear Feet	Thermoplastic Double Drop Detail Stripe, White
0290	626-G005		750	Linear Feet	Thermoplastic Double Drop Detail Stripe, Yellow
0300	626-H002		1,044	Linear Feet	Thermoplastic Double Drop Legend, White
0310	627-M001		1,800	Each	One-Way Clear Reflective High Performance Raised Markers
0320	627-J001		305	Each	Two-Way Clear Reflective High Performance Raised Markers

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	627-L001		900	Each	Two-Way Yellow Reflective High Performance Raised Markers
0340	630-A001		12	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness
0350	630-A003		179	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness
0360	630-C003		242	Linear Feet	Steel U-Section Posts, 3.0 lb/ft
0370	630-F006		20	Each	Delineators, Guard Rail, White
0380	630-G004		41	Each	Type 3 Object Markers, OM-3R or OM-3L
0390	907-204-A003		7,343	Square Yard	Geogrid, Type II, Biaxial
0400	907-619-B001		132	Linear Feet	Temporary Portable Rumble Strips
ALTERNATE GROUP AA NUMBER 1					
0410	304-F001	(GT)	12,784	Ton	3/4" and Down Crushed Stone Base
ALTERNATE GROUP AA NUMBER 2					
0420	304-F002	(GT)	12,784	Ton	Size 610 Crushed Stone Base
ALTERNATE GROUP AA NUMBER 3					
0430	304-F003	(GT)	12,784	Ton	Size 825B Crushed Stone Base