

**SECTION 905 -- PROPOSAL (CONTINUED)**

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. <u>  1  </u>	DATED <u>  5/19/2022  </u>	ADDENDUM NO. <u>          </u>	DATED <u>          </u>
ADDENDUM NO. <u>          </u>	DATED <u>          </u>	ADDENDUM NO. <u>          </u>	DATED <u>          </u>
ADDENDUM NO. <u>          </u>	DATED <u>          </u>	ADDENDUM NO. <u>          </u>	DATED <u>          </u>

Number	Description
1	Revised NTB No. 3738; Revised Bid Items; Revised or Added Plan Sheet Nos. 2 & 9; Amendment EBSx Download Required.

TOTAL ADDENDA:   1    
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE \_\_\_\_\_

\_\_\_\_\_  
 Contractor

BY \_\_\_\_\_  
 Signature

TITLE \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY, STATE, ZIP \_\_\_\_\_

PHONE \_\_\_\_\_

FAX \_\_\_\_\_

E-MAIL \_\_\_\_\_

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of \_\_\_\_\_ and the names, titles and business addresses of the executives are as follows:

_____	President	Address
_____	Secretary	Address
_____	Treasurer	Address

The following is my (our) itemized proposal.

BR-0063-03(011)/ 107008301000

Perry County(ies)

Revised 01/26/2016

# MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 3738

DATE: 05/19/2022

SUBJECT: Specialty Items

PROJECT: BR-0063-03(011)/107008301 - PERRY

Pursuant to the provisions of Section 108, the following work items are hereby designated as "Specialty Items" for this contract. Bidders are reminded that these items must be subcontracted in order to be considered as specialty items.

## CATEGORY: EROSION CONTROL

---

Line No	Pay Item	Description
0140	213-C001	Superphosphate
0150	216-A001	Solid Sodding
0160	217-A001	Ditch Liner
0170	219-A001	Watering
0180	220-A001	Insect Pest Control
0190	221-A001	Concrete Paved Ditch
0200	223-A001	Mowing
0210	225-A001	Grassing
0220	225-B001	Agricultural Limestone
0230	225-C001	Mulch, Vegetative Mulch
0240	226-A001	Temporary Grassing
0250	229-A001	Erosion Mat
0280	236-A008	Silt Basin, Type D
0290	237-A002	Wattles, 20"
0300	239-A001	Temporary Slope Drains
0310	246-B001	Rockbags
0320	249-A001	Riprap for Erosion Control
0832	907-234-A001	Temporary Silt Fence
0834	907-234-C001	Super Silt Fence
0840	907-253-A001	Coir Fiber Baffle

## CATEGORY: GUARDRAIL, GUIDERAIL

---

Line No	Pay Item	Description
0480	606-B001	Guard Rail, Class A, Type 1
0490	606-D022	Guard Rail, Bridge End Section, Type I
0500	606-E005	Guard Rail, Terminal End Section, Flared

## CATEGORY: MISCELLANEOUS/ SPECIALTY WORK ITEMS

---

Line No	Pay Item	Description
0400	423-A001	Rumble Strips, Ground In

CATEGORY: PAVEMENT STRIPING AND MARKING

---

Line No	Pay Item	Description
0670	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White
0680	626-D002	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow
0690	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow
0700	626-G004	Thermoplastic Double Drop Detail Stripe, White
0710	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow
0720	626-H005	Thermoplastic Legend, White
0732	627-J001	Two-Way Clear Reflective High Performance Raised Markers
0740	627-L001	Two-Way Yellow Reflective High Performance Raised Markers
0890	907-624-B002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White
0900	907-624-C001	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow
0910	907-624-D002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow
0920	628-H001	6" High Performance Cold Plastic Traffic Stripe, Continuous White
0930	628-I002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow
0940	628-J001	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow

CATEGORY: SURVEY AND STAKING

---

Line No	Pay Item	Description
0810	699-A001	Roadway Construction Stakes

CATEGORY: TRAFFIC CONTROL - PERMANENT

---

Line No	Pay Item	Description
0750	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness
0760	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness
0770	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness
0780	630-C002	Steel U-Section Posts, 2.0 lb/ft
0790	630-C003	Steel U-Section Posts, 3.0 lb/ft
0800	630-F006	Delineators, Guard Rail, White

CATEGORY: TRAFFIC CONTROL - TEMPORARY

---

Line No	Pay Item	Description
0540	619-A1004	Temporary Traffic Stripe, Continuous White, Paint
0550	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint
0560	619-A4003	Temporary Traffic Stripe, Skip Yellow, Paint
0570	619-A5002	Temporary Traffic Stripe, Detail, Paint
0580	619-A6004	Temporary Traffic Stripe, Legend, Paint
0590	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker
0600	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet
0610	619-D2002	Standard Roadside Construction Signs, 10 Square Feet or More, Permanent
0620	619-G4001	Barricades, Type III, Double Faced
0630	619-G4005	Barricades, Type III, Single Faced

CATEGORY: TRAFFIC CONTROL - TEMPORARY

---

Line No	Pay Item	Description
0640	619-G5001	Free Standing Plastic Drums
0650	619-G7001	Warning Lights, Type "B"

Bridge Replacement on SR 42 over Tallahalla Creek (Bridge No. 70.4), known as Federal Aid Project No. BR-0063-03(011) / 107008301 in Perry County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	201-B001		7	Acre	Clearing and Grubbing
0020	202-A001		1	Lump Sum	Removal of Obstructions
0030	202-B007		8,901	Square Yard	Removal of Asphalt Pavement, All Depths
0040	202-B052		330	Square Yard	Removal of Concrete Driveways, All Depths
0050	202-B150		298	Linear Feet	Removal of Guard Rail Including Post, Blockouts & Hardware
0060	202-B191		138	Linear Feet	Removal of Pipe, 8" And Above
0070	202-B213		15	Each	Removal of Sign
0080	202-B219		1	Each	Removal of Sign, Ground Mounted with Posts
0090	203-A001	(E)	4,093	Cubic Yard	Unclassified Excavation, FM, AH
0100	203-EX017	(E)	61,684	Cubic Yard	Borrow Excavation, AH, FME, Class B7
0110	203-G001	(E)	34,036	Cubic Yard	Excess Excavation, FM, AH
0120	209-A005		12,696	Square Yard	Geotextile Stabilization, Type V, Non-Woven
0130	211-B001	(E)	250	Cubic Yard	Topsoil for Slope Treatment, Contractor Furnished
0140	213-C001		10	Ton	Superphosphate
0150	216-A001		89	Square Yard	Solid Sodding
0160	217-A001		255	Square Yard	Ditch Liner
0170	219-A001		16	Thousand Gallon	Watering [\$20.00]
0180	220-A001		20	Acre	Insect Pest Control [\$30.00]
0190	221-A001	(S)	13	Cubic Yard	Concrete Paved Ditch
0200	223-A001		40	Acre	Mowing [\$50.00]
0210	225-A001		20	Acre	Grassing
0220	225-B001		10	Ton	Agricultural Limestone
0230	225-C001		39	Ton	Mulch, Vegetative Mulch
0240	226-A001		20	Acre	Temporary Grassing
0250	229-A001		801	Square Yard	Erosion Mat
0280	236-A008		1	Each	Silt Basin, Type D
0290	237-A002		2,000	Linear Feet	Wattles, 20"
0300	239-A001		2,400	Linear Feet	Temporary Slope Drains
0310	246-B001		100	Each	Rockbags
0320	249-A001		600	Ton	Riprap for Erosion Control
0330	403-A002	(BA1)	1,210	Ton	12.5-mm, MT, Asphalt Pavement
0340	403-A005	(BA1)	842	Ton	19-mm, MT, Asphalt Pavement
0350	403-A006	(BA1)	1,131	Ton	19-mm, ST, Asphalt Pavement

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0360	403-A014	(BA1)	1,015	Ton	9.5-mm, MT, Asphalt Pavement
0370	406-A002		2,942	Square Yard	Cold Milling of Bituminous Pavement, All Depths
0380	407-A001	(A2)	1,677	Gallon	Asphalt for Tack Coat
0390	413-E001		74	Linear Feet	Sawing and Sealing Transverse Joints in Asphalt Pavement
0400	423-A001		2	Mile	Rumble Strips, Ground In
0410	501-E001		74	Linear Feet	Expansion Joints, Without Dowels
0420	502-A001	(C)	159	Square Yard	Reinforced Cement Concrete Bridge End Pavement
0430	603-ALT003	(S)	456	Linear Feet	18" Type A Alternate Pipe
0440	605-AA001	(S)	44	Square Yard	Geotextile for Subsurface Drainage, Type III
0450	605-O002	(S)	80	Linear Feet	4" Perforated Sewer Pipe for Underdrains, SDR 23.5
0460	605-P002	(S)	5	Linear Feet	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5
0470	605-W001	(GY)	3	Cubic Yard	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM
0480	606-B001		150	Linear Feet	Guard Rail, Class A, Type 1
0490	606-D022		4	Each	Guard Rail, Bridge End Section, Type I
0500	606-E005		4	Each	Guard Rail, Terminal End Section, Flared
0510	615-A024	(S)	40	Linear Feet	Concrete Bridge End Barrier, 37.5"
0520	617-A001		14	Each	Right-of-Way Marker
0530	618-A001		1	Lump Sum	Maintenance of Traffic
0540	619-A1004		5	Mile	Temporary Traffic Stripe, Continuous White, Paint
0550	619-A2004		5	Mile	Temporary Traffic Stripe, Continuous Yellow, Paint
0560	619-A4003		2,915	Linear Feet	Temporary Traffic Stripe, Skip Yellow, Paint
0570	619-A5002		240	Linear Feet	Temporary Traffic Stripe, Detail, Paint
0580	619-A6004		31	Linear Feet	Temporary Traffic Stripe, Legend, Paint
0590	619-C7001		78	Each	Two-Way Yellow Reflective High Performance Raised Marker
0600	619-D1001		49	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0610	619-D2002		444	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More, Permanent
0620	619-G4001		24	Linear Feet	Barricades, Type III, Double Faced
0630	619-G4005		192	Linear Feet	Barricades, Type III, Single Faced
0640	619-G5001		111	Each	Free Standing Plastic Drums
0650	619-G7001		2	Each	Warning Lights, Type "B"
0660	620-A001		1	Lump Sum	Mobilization
0670	626-C001		6,558	Linear Feet	6" Thermoplastic Double Drop Edge Stripe, Continuous White
0680	626-D002		1,798	Linear Feet	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0690	626-E002		5,759	Linear Feet	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow
0700	626-G004		240	Linear Feet	Thermoplastic Double Drop Detail Stripe, White
0710	626-G005		87	Linear Feet	Thermoplastic Double Drop Detail Stripe, Yellow
0720	626-H005		31	Linear Feet	Thermoplastic Legend, White
0732	627-J001		26	Each	Two-Way Clear Reflective High Performance Raised Markers
0740	627-L001		117	Each	Two-Way Yellow Reflective High Performance Raised Markers
0750	630-A001		20	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness
0760	630-A003		36	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness
0770	630-A005		24	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness
0780	630-C002		22	Linear Feet	Steel U-Section Posts, 2.0 lb/ft
0790	630-C003		182	Linear Feet	Steel U-Section Posts, 3.0 lb/ft
0800	630-F006		14	Each	Delineators, Guard Rail, White
0810	699-A001		1	Lump Sum	Roadway Construction Stakes
0820	815-A007	(S)	216	Ton	Loose Riprap, Size 300
0830	815-F002	(S)	150	Ton	Sediment Control Stone
0832	907-234-A001		4,650	Linear Feet	Temporary Silt Fence
0834	907-234-C001		2,422	Linear Feet	Super Silt Fence
0840	907-253-A001		172	Linear Feet	Coir Fiber Baffle
0850	907-906001		1,040	Hours	Trainees [\$5.00]
ALTERNATE GROUP AA NUMBER 1					
0860	304-F001	(GT)	4,882	Ton	3/4" and Down Crushed Stone Base
ALTERNATE GROUP AA NUMBER 2					
0870	304-F002	(GT)	4,882	Ton	Size 610 Crushed Stone Base
ALTERNATE GROUP AA NUMBER 3					
0880	304-F003	(GT)	4,882	Ton	Size 825B Crushed Stone Base
ALTERNATE GROUP BB NUMBER 1					
0890	907-624-B002		2,604	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White
0900	907-624-C001		1,117	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow
0910	907-624-D002		1,485	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow
ALTERNATE GROUP BB NUMBER 2					
0920	628-H001		2,604	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous White
0930	628-I002		1,117	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow
0940	628-J001		1,485	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow
ALTERNATE GROUP CC NUMBER 1					

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0950	605-W002	(GY)	47	Cubic Yard	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM
ALTERNATE GROUP CC NUMBER 2					
0960	605-W003	(GY)	47	Cubic Yard	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM
Bridge Items					
0970	501-K001		4,630	Square Yard	Transverse Grooving
0980	803-K010	(S)	630	Linear Feet	Drilled Shaft, 72" Diameter
0990	803-L006	(S)	1	Each	Test Shaft, 72" Diameter
1000	803-M009	(S)	119	Linear Feet	Trial Shaft, 72" Diameter
1010	803-N001	(S)	100	Linear Feet	Exploration
1020	803-O023	(S)	60	Linear Feet	Temporary Casing, 72" Diameter
1030	803-P004	(S)	780	Linear Feet	30" Steel Pipe Piling, Wall Thickness 0.750"
1040	803-P011	(S)	4,320	Linear Feet	24" Steel Pipe Piling, Wall Thickness 1.000"
1050	804-C192	(S)	3,973	Linear Feet	100' Prestressed Concrete Beam, Type FIB-36
1060	805-A001	(S)	371,547	Pounds	Reinforcement
1070	805-C001	(S)	6,850	Pounds	Reinforcement, Corrosion Resistant
1080	813-A004	(S)	2,605	Linear Feet	Concrete Railing, 36"
1090	815-A007	(S)	8,283	Ton	Loose Riprap, Size 300
1100	815-E001	(S)	6,900	Square Yard	Geotextile under Riprap
1110	907-803-B001	(S)	1	Each	Conventional Static Pile Load Test [\$5,000.00]
1120	907-803-I004	(S)	7	Each	PDA Test Pile, Steel Pipe Pile
1130	907-803-J001	(S)	7	Each	Pile Restrike
1140	907-804-A001	(S)	1,534	Cubic Yard	Bridge Concrete, Class BDx
1150	907-804-A002	(S)	338	Cubic Yard	Bridge Concrete, Class AA
1160	907-804-A002	(S)	52	Cubic Yard	Bridge Concrete, Class AA - Closure Pour
1170	907-804-PP003	(S)	680	Linear Feet	68' Post-Tensioned Concrete Beam, Per Plans
1180	907-804-PP004	(S)	1	Lump Sum	Post Tensioning System
1190	907-804-PP008	(S)	1,139	Linear Feet	114' Post-Tensioned Concrete Beam, Per Plans
1200	907-804-PP009	(S)	640	Linear Feet	128' Post-Tensioned Concrete Beam, Per Plans
1210	907-822-B001		75	Linear Feet	2 1/2" Reinforced Elastomeric Molded Rubber Expansion Joint
1220	907-823-A001		73	Linear Feet	Preformed Joint Seal, Type I
1230	907-823-A002		37	Linear Feet	Preformed Joint Seal, Type II





**ADDENDUM**


STATE	PROJECT NO.
MISS	BR-0063-03(011)

**SUMMARY OF QUANTITIES (SHEET 1)**

PAY ITEM NO.	PAY ITEM	UNIT	PERRY : 107008-301000	
			Prelim	Final
201-B001	Clearing and Grubbing	ACRE	7	
202-A001	Removal of Obstructions	LS	1	
202-B007	Removal of Asphalt Pavement, All Depths	SY	8,901	
202-B052	Removal of Concrete Driveways, All Depths	SY	330	
202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	LF	298	
202-B191	Removal of Pipe, 8" And Above	LF	138	
202-B213	Removal of Sign	EA	15	
202-B219	Removal of Sign, Ground Mounted with Posts	EA	1	
203-A001	Unclassified Excavation, FM, AH	CY	4,093	
203-EX017	Borrow Excavation, AH, FME, Class B7	CY	61,684	
203-G001	Excess Excavation, FM, AH	CY	34,036	
209-A005	Geotextile Stabilization, Type V, Non-Woven	SY	12,696	
211-B001	Topsoil for Slope Treatment, Contractor Furnished	CY	250	
213-C001	Superphosphate	TON	10	
216-A001	Solid Sodding	SY	89	
217-A001	Ditch Liner	SY	255	
219-A001	Watering	KGAL	16	
220-A001	Insect Pest Control	ACRE	20	
221-A001	Concrete Paved Ditch	CY	13	
223-A001	Mowing	ACRE	40	
225-A001	Grassing	ACRE	20	
225-B001	Agricultural Limestone	TON	10	
225-C001	Mulch, Vegetative Mulch	TON	39	
226-A001	Temporary Grassing	ACRE	20	
229-A001	Erosion Mat	SY	801	
234-A001	Temporary Silt Fence	LF	4,650	
234-C001	Super Silt Fence	LF	2,422	
236-A008	Silt Basin, Type D	EA	1	
237-A002	Wattles, 20"	LF	2,000	
239-A001	Temporary Slope Drains	LF	2,400	
246-B001	Rockbags	EA	100	
249-A001	Riprap for Erosion Control	TON	600	
907-253-A001	Coir Fiber Baffle	LF	172	
304-F001	3/4" and Down Crushed Stone Base	TON	4,882	
304-F002	OR Size 610 Crushed Stone Base	TON	4,882	
304-H003	Size 825B Crushed Stone Base, LVM	CY	4,882	
403-A002	12.5-mm, MT, Asphalt Pavement	TON	1,210	
403-A005	19-mm, MT, Asphalt Pavement	TON	842	
403-A006	19-mm, ST, Asphalt Pavement	TON	1,131	

- ① FOR REMOVAL OF EXISTING BRIDGE #70.4 DECK IS CAST IN PLACE CONCRETE, PIERS CONCRETE AND STEEL, STEEL PARKER THROUGH TRUSS MAIN SPAN, BRIDGE TOTAL LENGTH 1,231.43 FT. SPAN ARRANGEMENT 26@30',1@60',1@50',1@60',6@30'. INCLUDES THE REMOVAL OF BRIDGE END SECTIONS, TERMINAL END SECTIONS,POSTS, BLOCKOUTS,HARDWARE, ETC.(AS MEASURED FROM BEGINNING OF BRIDGE END SECTION) AND OBJECT MARKERS.
- ② 12 C.Y. FOR TYPE "B" FLUMES AND 0.73 C.Y. FOR EDGE DRAIN OUTLET AT BRIDGE END PAVEMENT.
- ④ 1293 FT. FROM BRIDGE ECP, AND 1129 FT. AT WETLAND
- ⑤ FOR CONCRETE SLAB RIGHT OF STA.459+00.
- ⑥ 20% SHRINKAGE FACTOR IS USED FOR CRUSHED STONE TONS. INCLUDES 621 TONS FOR RAMPS.
- ⑦ 25% BALANCE FACTOR WAS USED.
- ⑧ INCLUDES 70.33 TONS AT PAVED SHOULDER AT BRIDGE ENDS AND 83.98 TONS AT PAVED APRONS.
- ⑨ THE TWO ADOPT-A-HIGHWAY SIGNS WILL NOT BE REPLACED.
- ⑩ FLEXAMAT, SHOREFLEX, OR AN APPROVED CONCRETE EQUAL IS REQUIRED FOR USE.



	
<b>MISSISSIPPI DEPARTMENT OF TRANSPORTATION</b> <b>SUMMARY OF QUANTITIES</b>	
REVISIONS AND REMOVED NOTES 05/19/2024	Revision 05/19/2024
PROJ NO: BR-0063-03(011) COUNTY: PERRY	
Working Number <b>SQ-1</b>	
Design Team <b>smith</b> Checked <b>smith</b> Date <b>7-7-2021</b>	
FILENAME: <b>sq5-107008/301000</b> Sheet Number Design Team <b>smith</b> Checked <b>smith</b> Date <b>7-7-2021</b> <b>9</b>	