

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO.	<u> 1 </u>	DATED	<u> 5/17/2022 </u>	ADDENDUM NO.	<u> </u>	DATED	<u> </u>
ADDENDUM NO.	<u> 2 </u>	DATED	<u> 5/19/2022 </u>	ADDENDUM NO.	<u> </u>	DATED	<u> </u>
ADDENDUM NO.	<u> </u>	DATED	<u> </u>	ADDENDUM NO.	<u> </u>	DATED	<u> </u>

- | Number | Description |
|--------|--|
| 1 | Revised Table of Contents; Added Notice To Bidders No. 2278; Revised Notice To Bidders No. 4075; Revised Form OCR-485; Amendment EBSx Download Required. |
| 2 | Revised Bid Items; Amendment EBSx Download Required. |

TOTAL ADDENDA: 2
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____
Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

President Address

Secretary Address

Treasurer Address

The following is my (our) itemized proposal.

SP-0024-02(035)/ 108997301000

Madison County(ies)

Revised 01/26/2016

Mill & Overlay approximately 3 miles of SR 22 from the Beginning of the 5-Lane Section to US 51, known as State Project No. SP-0024-02(035) / 108997301 in Madison County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	202-B009		500	Square Yard	Removal of Asphalt Pavement, Failed Areas
0020	202-B081		243	Square Yard	Removal of Concrete Sidewalks & Driveways, All Depths
0030	202-B089		561	Linear Feet	Removal of Curb &/or Curb and Gutter, All Types
0040	202-B158		470	Linear Feet	Removal of Guard Rail, Including Rails, Posts and Terminal Ends
0050	203-G001	(E)	50	Cubic Yard	Excess Excavation, FM, AH
0060	304-D002	(GT)	156	Ton	Granular Material, Crushed Stone
0070	310-B001	(GT)	10	Ton	Size I Stabilizer Aggregate, Coarse
0080	403-A014	(BA1)	10,770	Ton	9.5-mm, MT, Asphalt Pavement
0090	403-B002	(BA1)	50	Ton	12.5-mm, MT, Asphalt Pavement, Leveling
0100	406-D001		130,000	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0110	407-A001	(A2)	11,000	Gallon	Asphalt for Tack Coat
0120	503-C010		300	Linear Feet	Saw Cut, Full Depth
0130	606-B003		320	Linear Feet	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post
0140	606-D019		4	Each	Guard Rail, Bridge End Section, Type H
0150	606-E007		4	Each	Guard Rail, Terminal End Section, Non-Flared
0160	608-B001	(S)	243	Square Yard	Concrete Sidewalk, With Reinforcement
0170	609-D008	(S)	561	Linear Feet	Combination Concrete Curb and Gutter Type 3A
0180	618-A001		1	Lump Sum	Maintenance of Traffic
0190	619-A1001		13	Mile	Temporary Traffic Stripe, Continuous White
0200	619-A2001		12	Mile	Temporary Traffic Stripe, Continuous Yellow
0210	619-A3001		7	Mile	Temporary Traffic Stripe, Skip White
0220	619-A4002		12	Mile	Temporary Traffic Stripe, Skip Yellow
0230	619-A5001		122,091	Linear Feet	Temporary Traffic Stripe, Detail
0240	619-A6001		2,709	Square Feet	Temporary Traffic Stripe, Legend
0250	619-A6002		12,496	Linear Feet	Temporary Traffic Stripe, Legend
0260	619-D1001		26	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0270	619-D2001		612	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0280	619-G4001		48	Linear Feet	Barricades, Type III, Double Faced
0290	620-A001		1	Lump Sum	Mobilization
0300	626-A001		3	Mile	6" Thermoplastic Double Drop Traffic Stripe, Skip White
0310	626-B002		5	Mile	6" Thermoplastic Double Drop Traffic Stripe, Continuous White
0320	626-D001		4	Mile	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	626-E001		4	Mile	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow
0340	626-G001		95	Linear Feet	Thermoplastic Detail Stripe, Blue-ADA
0350	626-G004		25,967	Linear Feet	Thermoplastic Double Drop Detail Stripe, White
0360	626-G005		14,730	Linear Feet	Thermoplastic Double Drop Detail Stripe, Yellow
0370	626-H001		2,709	Square Feet	Thermoplastic Double Drop Legend, White
0380	626-H002		6,248	Linear Feet	Thermoplastic Double Drop Legend, White
0390	627-J001		652	Each	Two-Way Clear Reflective High Performance Raised Markers
0400	627-K001		500	Each	Red-Clear Reflective High Performance Raised Markers
0410	627-L001		1,481	Each	Two-Way Yellow Reflective High Performance Raised Markers
0420	630-F006		23	Each	Delineators, Guard Rail, White
0430	907-619-B001		66	Linear Feet	Temporary Portable Rumble Strips
0440	907-632-D001		4	Each	Solid State Traffic Actuated Controller, Type 1
0450	907-641-A002		18	Each	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2
0460	907-641-D001		2,315	Linear Feet	Radar Vehicle Detection Cable
0470	907-899-A001		1	Lump Sum	Railway-Highway Provisions