

**Call 17 Mill & Overlay approximately 3 miles of SR 22 from the Beginning of the 5-Lane Section to US 51, known as State Project No. SP-0024-02(035) / 108997301 in Madison County.**

Q1. Will manhole, water valve and grate risers be provided by the City of Canton, or will it be the responsibility of the contractor?

A1. It shall be the responsibility of the Contractor and shall be absorbed in other items bid.

Q2. **1.)** There is not a pay item for the truncated domes. Are the domes going to be absorbed? **2.)** There is only 243 square yards shown on the table on page 150. The planned quantities show 243 square yards to be removed but shows 2,243 square yards to be poured back. Is this correct?

A2. **1.)** The truncated domes shall be absorbed in Pay Item No. 608-B001 Concrete Sidewalk, With Reinforcement. **2.)** See addendum. The quantity of 2,243 SY shown on the SQ sheet in the Scope of Work is in error and is to be disregarded.

Q3. The scope of work says the Contractor will be responsible for milling the parking around the square. Is this all 4 sides or just the SR 22 side of the square?

A3. Only the SR 22 side of the square.