

| Overlay approximately 8 miles of SR 16 from the BOSM at Grace to the EOSM at Rolling Fork, known as State Project Nos. SP-1509-00 (006) / 109019301 & SP-0504-00(016) / 109019302 in Issaquena & Sharkey Counties. |           |  |           |       | APAC - Mississippi, Inc. |  |  |
|--|-----------|--|-----------|-------|--------------------------|--|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,470,451.50   |           |  |           |       | \$4,337,454.28           |  |  |
| Ref#   | Item      | Item Description   | Item Qty  | Units | 1                        |  |  |
| 0010   | 202-B007  | Removal of Asphalt Pavement, All Depths                        | 650.000   | SY    | 90.60                    |  |  |
| 0020   | 202-B240  | Removal of Traffic Stripe                                      | 1,650.000 | LF    | 4.80                     |  |  |
| 0030   | 203-G001  | Excess Excavation, FM, AH                                      | 100.000   | CY    | 6.00                     |  |  |
| 0040   | 304-D002  | Granular Material, Crushed Stone                               | 5,000.000 | TON   | 95.00                    |  |  |
| 0050   | 403-A015  | 9.5-mm, ST, Asphalt Pavement                                   | 8,700.000 | TON   | 165.00                   |  |  |
| 0060   | 403-B006  | 19-mm, ST, Asphalt Pavement, Leveling                          | 300.000   | TON   | 275.00                   |  |  |
| 0070   | 403-B012  | 9.5-mm, ST, Asphalt Pavement, Leveling                         | 4,600.000 | TON   | 195.00                   |  |  |
| 0072   | 406-D001  | Fine Milling of Bituminous Pavement, All Depths                | 3,850.000 | SY    | 8.48                     |  |  |
| 0090   | 407-A001  | Asphalt for Tack Coat  | 8,100.000 | GAL   | 2.95                     |  |  |
| 0100   | 503-C010  | Saw Cut, Full Depth  | 1,200.000 | LF    | 15.00                    |  |  |
| 0110   | 618-A001  | Maintenance of Traffic   | 1.000     | LS    | 450,000.00               |  |  |
| 0120   | 618-B001  | Additional Construction Signs                                  | 2.000     | SF    | 10.00                    |  |  |
| 0130   | 619-A1001 | Temporary Traffic Stripe, Continuous White                     | 16.000    | MI    | 1,920.00                 |  |  |
| 0140   | 619-A2001 | Temporary Traffic Stripe, Continuous Yellow                    | 4.000     | MI    | 2,160.00                 |  |  |
| 0150   | 619-A4002 | Temporary Traffic Stripe, Skip Yellow                          | 10.000    | MI    | 2,160.00                 |  |  |
| 0160   | 619-A5001 | Temporary Traffic Stripe, Detail                               | 700.000   | LF    | 0.08                     |  |  |
| 0170   | 619-A6002 | Temporary Traffic Stripe, Legend                               | 300.000   | LF    | 1.80                     |  |  |
| 0180   | 620-A001  | Mobilization   | 1.000     | LS    | 600,000.00               |  |  |
| 0190   | 626-B002  | 6" Thermoplastic Double Drop Traffic Stripe, Continuous White  | 16.000    | MI    | 6,960.00                 |  |  |
| 0200   | 626-D001  | 6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow       | 8.000     | MI    | 3,480.00                 |  |  |
| 0210   | 626-E001  | 6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow | 3.000     | MI    | 6,840.00                 |  |  |
| 0220   | 626-G004  | Thermoplastic Double Drop Detail Stripe, White                 | 1,100.000 | LF    | 3.00                     |  |  |
| 0230   | 626-G005  | Thermoplastic Double Drop Detail Stripe, Yellow                | 550.000   | LF    | 3.00                     |  |  |
| 0240   | 626-H002  | Thermoplastic Double Drop Legend, White                        | 475.000   | LF    | 4.80                     |  |  |
| 0250   | 627-J001  | Two-Way Clear Reflective High Performance Raised Markers       | 210.000   | EA    | 10.80                    |  |  |
| 0260   | 627-L001  | Two-Way Yellow Reflective High Performance Raised Markers      | 680.000   | EA    | 10.80                    |  |  |

| Overlay approximately 8 miles of SR 16 from the BOSM at Grace to the EOSM at Rolling Fork, known as State Project Nos. SP-1509-00 (006) / 109019301 & SP-0504-00(016) / 109019302 in Issaquena & Sharkey Counties. |              |  |          |       | APAC - Mississippi, Inc. |  |  |
|--|--------------|--|----------|-------|--------------------------|--|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,470,451.50   |              |  |          |       | \$4,337,454.28           |  |  |
| Ref#   | Item         | Item Description                           | Item Qty | Units | 1                        |  |  |
| 0270   | 630-F006     | Delineators, Guard Rail, White             | 31.000   | EA    | 78.00                    |  |  |
| 0280   | 630-G003     | Type 3 Object Markers, OM-3L, Post Mounted | 8.000    | EA    | 300.00                   |  |  |
| 0290   | 907-619-B001 | Temporary Portable Rumble Strips           | 66.000   | LF    | 190.08                   |  |  |

Letting Date: 5/24/2022

Call Number: 21

Page 2 of 2