

Call 14 Thin Lift Overlay approximately 4 miles of SR 145 from US 45 to US 45, known as State Project Nos. MP-6145-77(005) & MP-6145-12(005) / 307492301 & 302 in Wayne & Clarke Counties.

Q1. Clarify what work will be covered under pay item #0020, #0030 and #0120 in reference to **1.)** Curb & Gutter milling, **2.)** Failed areas on the main facility, **3.)** Reconstruction Area.

A1. **1.)** Pay Item #0020 is for punch outs and for the removal of asphalt on the re-construction area. **2.)** Pay Item #0030 will be used in the event that we encounter material other than asphalt. **3.)** Pay Item #0120 is for tie-ins at the BOP, EOP, and bridge ends as well as the curb and gutter section in Shubuta.

Q2. The bid documents do not include a Construction Signing Plan for advance construction signs. Should the Scope of Work include a Supplement to Special Provision 907-618-4?

A2. The construction signing plan was inadvertently omitted from the proposal and can be downloaded at the following link. The cost for these signs will be paid for under Pay Item 618-A, Maintenance of Traffic.

<https://file-exchange.mdot.state.ms.us/dl/?f=a4ba948bd807ae614bd4c718ba74ff8d32a06ba8>