

Call 10 Mill & Overlay approximately 15 miles of SR 5 from 1.4 miles south of Massengill Rd to 0.1 miles north of the old MDOT Maintenance Shop and approximately 1.3 miles of SR 370 from SR 5 to the east Ashland City Limits, known as State Project Nos. MP-2005-05(004) / 307511301 & MP-2370-05(001) / 307511302 in Benton County.

- Q1. Does the Excavation in the Failed Areas get paid for? No.1 in the Scope of Work says it is paid for as Excess Excavation. The Pay Item Quantity is significantly lower than the calculated quantity.
- A1. The failed areas were estimated at 1' depth to be paid under the asphalt removal item and backfilled with 1' of 19-mm asphalt. It is estimated at this time that 25% of the failed areas would require an additional 6" of excavation to be paid for as excess and backfilled with crushed stone. Bidders are advised to bid as per the plans and proposal.