

Call 05 Mill and Overlay approximately 1 mile on SR 24 from the west city limits of Liberty to just west of Velma Street, known as State Project No. SP-0163-00(008) / 108896301 in Amite County.

- Q1. 1.) The Proposal has Pay Item 406-D001, but the Plans has Pay Item 406-A002. Which is correct? 2.) On the Typical Sections, TS-1 and TS-2, under the Proposed build up there are two Fine Milling items, 1 & 10. Where will the 1.5" Fine Milling be required?
- A1. 1.) See addendum. 2.) The 1.5" milling will be required against the curb and gutter in various locations in order to tie the surface into the face of the curb. See detail "A" on TS-1 and TS-2. The new surface should be 1.5" higher than the existing.
- Q2. 1.) Detail "B" on Sheet 4 and Sheet 5 show a different depth of saw cut for sawing and sealing transverse joints. Which is correct? 2.) It appears the joint tape is going on all transverse joints after the milling takes place, prior to the overlay. Is this correct?
- A2. 1.) One inch (1") is correct. 2.) Yes.