

Bridge Replacements on SR 145 (Bridge Nos. 35.0 & 43.8), known as Federal Aid Project No. BR-0145-00(006) / 102485302 in Clarke County.					T. L. Wallace Construction, Inc.	Joe McGee Construction Company, Inc.	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,770,020.45					\$4,278,744.00	\$4,591,693.73	\$4,862,157.60
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0010	201-B001	Clearing and Grubbing	1.000	ACRE	7,700.00	8,600.00	13,250.00
0020	202-B007	Removal of Asphalt Pavement, All Depths	2,992.000	SY	12.40	10.20	12.50
0030	202-B023	Removal of Bridge	2.000	EA	24,300.00	46,250.00	57,000.00
0040	202-B080	Removal of Concrete Sidewalk	30.000	SY	26.50	17.40	60.00
0050	202-B088	Removal of Curb & Gutter, All Types	100.000	LF	15.30	18.30	12.75
0060	202-B136	Removal of Guard Rail	656.000	LF	10.15	11.00	10.00
0070	202-B191	Removal of Pipe, 8" And Above	16.000	LF	33.00	32.00	75.00
0080	202-B215	Removal of Sign Including Post & Footing	9.000	EA	282.00	300.00	285.00
0090	203-A001	Unclassified Excavation, FM, AH	2,432.000	CY	10.95	8.40	10.50
0100	203-EX017	Borrow Excavation, AH, FME, Class B7	11,271.000	CY	17.05	16.90	21.50
0110	206-A001	Structure Excavation	4.000	CY	22.15	100.00	335.00
0120	209-A005	Geotextile Stabilization, Type V, Non-Woven	5,660.000	SY	3.70	3.65	2.85
0130	211-B001	Topsoil for Slope Treatment, Contractor Furnished	1,500.000	CY	1.15	12.85	15.50
0140	213-C001	Superphosphate	3.000	TON	1,100.00	1,100.00	1,085.00
0150	216-A001	Solid Sodding	54.000	SY	22.55	23.30	22.50
0160	217-A001	Ditch Liner	134.000	SY	11.30	11.65	11.50
0170	219-A001	Watering	1.000	KGAL	20.00	20.00	20.00
0180	220-A001	Insect Pest Control	5.000	ACRE	30.00	30.00	30.00
0190	221-A001	Concrete Paved Ditch	6.000	CY	1,500.00	1,705.00	1,800.00
0200	223-A001	Mowing	9.000	ACRE	50.00	50.00	50.00
0210	225-A001	Grassing	5.000	ACRE	1,100.00	1,136.00	1,115.00
0220	225-B001	Agricultural Limestone	3.000	TON	102.00	105.00	105.00
0230	225-C001	Mulch, Vegetative Mulch	9.000	TON	237.00	245.00	250.00
0240	226-A001	Temporary Grassing	5.000	ACRE	1,100.00	1,050.00	1,050.00
0250	229-A001	Erosion Mat	134.000	SY	106.00	80.25	90.00
0260	236-A008	Silt Basin, Type D	1.000	EA	2,800.00	4,250.00	10,000.00

Bridge Replacements on SR 145 (Bridge Nos. 35.0 & 43.8), known as Federal Aid Project No. BR-0145-00(006) / 102485302 in Clarke County.					T. L. Wallace Construction, Inc.	Joe McGee Construction Company, Inc.	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,770,020.45					\$4,278,744.00	\$4,591,693.73	\$4,862,157.60
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0270	237-A002	Wattles, 20"	1,400.000	LF	7.65	8.00	7.50
0280	239-A001	Temporary Slope Drains	400.000	LF	7.70	17.00	30.00
0290	246-B001	Rockbags	128.000	EA	11.30	17.00	10.00
0300	249-A001	Riprap for Erosion Control	500.000	TON	87.80	91.65	95.00
0310	403-A002	12.5-mm, MT, Asphalt Pavement	517.000	TON	268.00	248.20	245.00
0320	403-A006	19-mm, ST, Asphalt Pavement	701.000	TON	226.00	211.90	210.00
0330	403-A014	9.5-mm, MT, Asphalt Pavement	559.000	TON	282.00	248.20	245.00
0340	406-D001	Fine Milling of Bituminous Pavement, All Depths	2,170.000	SY	22.55	11.70	8.50
0350	407-A001	Asphalt for Tack Coat	1,026.000	GAL	5.65	7.30	7.25
0360	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	144.000	LF	5.65	9.75	5.75
0370	423-A001	Rumble Strips, Ground In	1.000	MI	305.00	330.00	4,250.00
0380	501-E001	Expansion Joints, Without Dowels	144.000	LF	22.55	1.00	25.00
0390	501-K001	Transverse Grooving	48.000	SY	2.50	2.64	6.00
0400	502-A001	Reinforced Cement Concrete Bridge End Pavement	333.000	SY	293.00	334.00	375.00
0410	601-B001	Class "B" Structural Concrete, Minor Structures	1.000	CY	4,700.00	4,325.00	1,425.00
0420	603-ALT009	30" Type A Alternate Pipe	40.000	LF	61.45	76.15	165.00
0430	603-CA026	24" Reinforced Concrete Pipe, Class III	16.000	LF	83.90	110.00	97.50
0440	603-CB004	24" Reinforced Concrete End Section	1.000	EA	3,000.00	1,420.00	5,550.00
0450	605-AA001	Geotextile for Subsurface Drainage, Type III	92.000	SY	8.50	8.60	3.25
0460	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	158.000	LF	20.75	15.50	35.00
0470	605-P003	4" Non-perforated Sewer Pipe for Underdrains, SDR 35	120.000	LF	20.75	21.75	35.00
0480	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	20.000	CY	110.00	94.00	145.00
0490	606-B001	Guard Rail, Class A, Type 1	175.000	LF	36.10	39.00	35.00
0500	606-D022	Guard Rail, Bridge End Section, Type I	8.000	EA	3,800.00	4,000.00	3,850.00
0510	606-E005	Guard Rail, Terminal End Section, Flared	8.000	EA	4,000.00	4,200.00	4,000.00
0520	608-B001	Concrete Sidewalk, With Reinforcement	30.000	SY	84.60	87.50	85.00

Bridge Replacements on SR 145 (Bridge Nos. 35.0 & 43.8), known as Federal Aid Project No. BR-0145-00(006) / 102485302 in Clarke County.					T. L. Wallace Construction, Inc.	Joe McGee Construction Company, Inc.	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,770,020.45					\$4,278,744.00	\$4,591,693.73	\$4,862,157.60
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0530	609-D002	Combination Concrete Curb and Gutter Type 1 Modified	114.000	LF	56.40	58.30	55.00
0540	615-A024	Concrete Bridge End Barrier, 37.5"	80.000	LF	98.20	100.00	90.00
0550	617-A001	Right-of-Way Marker	11.000	EA	294.00	350.00	450.00
0560	618-A001	Maintenance of Traffic	1.000	LS	8,200.00	143,000.00	45,950.00
0570	619-A1002	Temporary Traffic Stripe, Continuous White	3,199.000	LF	1.15	3.60	3.45
0580	619-A2002	Temporary Traffic Stripe, Continuous Yellow	1,690.000	LF	1.15	3.60	3.45
0590	619-A4001	Temporary Traffic Stripe, Skip Yellow	623.000	LF	1.15	3.60	3.45
0600	619-A6002	Temporary Traffic Stripe, Legend	40.000	LF	3.25	6.10	5.75
0610	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	131.000	EA	11.30	18.30	17.25
0620	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	711.000	SF	11.30	12.20	12.00
0630	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	200.000	SF	11.30	12.20	12.00
0640	619-G4001	Barricades, Type III, Double Faced	30.000	LF	22.55	24.40	24.00
0650	619-G4005	Barricades, Type III, Single Faced	68.000	LF	20.30	22.00	21.50
0660	619-G5001	Free Standing Plastic Drums	50.000	EA	39.50	42.75	42.00
0670	619-G7001	Warning Lights, Type "B"	41.000	EA	141.00	152.50	150.00
0680	620-A001	Mobilization	1.000	LS	498,100.00	450,000.00	472,750.00
0690	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3,199.000	LF	2.25	8.50	8.00
0700	626-D002	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	623.000	LF	2.25	6.10	5.75
0710	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	1,690.000	LF	2.25	8.55	8.00
0720	626-G004	Thermoplastic Double Drop Detail Stripe, White	685.000	LF	4.55	8.55	8.00
0730	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	2,222.000	LF	4.55	8.55	8.00
0740	626-H002	Thermoplastic Double Drop Legend, White	328.000	LF	6.80	12.20	11.50
0750	627-J001	Two-Way Clear Reflective High Performance Raised Markers	27.000	EA	9.05	30.50	28.50
0760	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	131.000	EA	9.05	30.50	28.50
0770	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	55.000	SF	24.85	26.85	25.25
0780	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	44.000	SF	27.10	29.30	27.50

Bridge Replacements on SR 145 (Bridge Nos. 35.0 & 43.8), known as Federal Aid Project No. BR-0145-00(006) / 102485302 in Clarke County.					T. L. Wallace Construction, Inc.	Joe McGee Construction Company, Inc.	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,770,020.45					\$4,278,744.00	\$4,591,693.73	\$4,862,157.60
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0790	630-C002	Steel U-Section Posts, 2.0 lb/ft	66.000	LF	9.05	9.75	10.00
0800	630-C003	Steel U-Section Posts, 3.0 lb/ft	187.000	LF	13.55	14.65	13.75
0810	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	145.000	LBS	5.65	6.10	5.75
0820	630-F006	Delineators, Guard Rail, White	30.000	EA	24.85	26.00	25.25
0830	630-G005	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	8.000	EA	95.85	104.00	97.50
0840	630-K002	Welded & Seamless Steel Pipe Posts, 3"	42.000	LF	50.75	55.00	51.50
0850	699-A001	Roadway Construction Stakes	1.000	LS	56,400.00	59,500.00	27,500.00
0860	815-A003	Loose Riprap, Size 150	230.000	TON	87.80	97.00	90.25
0870	815-E001	Geotextile under Riprap	357.000	SY	4.90	4.15	3.05
0880	815-F002	Sediment Control Stone	100.000	TON	87.80	88.25	100.00
0890	907-234-A001	Temporary Silt Fence	4,000.000	LF	3.95	4.10	4.65
0900	907-234-C001	Super Silt Fence	1,581.000	LF	13.55	14.00	14.25
0910	907-234-D001	Inlet Siltation Guard	1.000	EA	450.00	1,100.00	850.00
0920	907-253-A001	Coir Fiber Baffle	96.000	LF	11.30	14.00	11.50
0930	907-608-C001	Detectable Warning Panels	20.000	SF	33.85	35.00	35.00
0940	907-619-E3001	Changeable Message Sign	10.000	EA	5,700.00	6,000.00	6,000.00
0950	907-630-PP002	Roadside Directional Signs, Sheet Aluminum, 0.125" Thickness, Ground Mounted	42.000	SF	29.35	31.75	29.50
0960	304-F001	3/4" and Down Crushed Stone Base	2,167.000	TON			
0970	304-F002	Size 610 Crushed Stone Base	2,167.000	TON	75.35	82.35	85.00
0980	304-F003	Size 825B Crushed Stone Base	2,167.000	TON			
0990	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	132.000	CY	110.00	79.00	
1000	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	132.000	CY			155.00
1010	907-624-B002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White	640.000	LF			
1020	907-624-D002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow	640.000	LF			
1030	628-H001	6" High Performance Cold Plastic Traffic Stripe, Continuous White	640.000	LF	10.15	18.30	17.25
1040	628-J001	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow	640.000	LF	10.15	18.30	17.25

Bridge Replacements on SR 145 (Bridge Nos. 35.0 & 43.8), known as Federal Aid Project No. BR-0145-00(006) / 102485302 in Clarke County.					T. L. Wallace Construction, Inc.	Joe McGee Construction Company, Inc.	Hemphill Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,770,020.45					\$4,278,744.00	\$4,591,693.73	\$4,862,157.60
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
1050	501-K001	Transverse Grooving	1,153.000	SY	2.60	2.80	5.00
1060	803-D006	HP 14 x 73 Steel Piling	4,435.000	LF	84.25	93.50	99.50
1070	804-C186	110' Prestressed Concrete Beam, Type FIB-45	547.000	LF	389.00	417.00	575.00
1080	804-C199	70' Prestressed Concrete Beam, Type FIB-36	1,043.000	LF	317.00	340.00	350.00
1090	805-A001	Reinforcement	102,641.000	LBS	1.60	1.78	1.85
1100	805-C001	Reinforcement, Corrosion Resistant	2,632.000	LBS	4.70	3.39	5.00
1110	813-A004	Concrete Railing, 36"	648.000	LF	98.00	99.00	90.00
1120	815-A007	Loose Riprap, Size 300	3,042.000	TON	96.25	98.50	90.25
1130	815-E001	Geotextile under Riprap	2,550.000	SY	4.90	4.25	3.05
1140	907-803-B001	Conventional Static Pile Load Test	2.000	EA	5,000.00	5,000.00	5,000.00
1150	907-803-I003	PDA Test Pile, HP Steel Pile	3.000	EA	11,600.00	11,500.00	14,500.00
1160	907-803-J001	Pile Restrike	3.000	EA	2,300.00	1,360.00	500.00
1170	907-804-A001	Bridge Concrete, Class BDX	362.000	CY	1,200.00	1,187.00	1,450.00
1180	907-804-A002	Bridge Concrete, Class AA	182.000	CY	1,100.00	1,245.00	1,485.00
1190	907-823-A001	Preformed Joint Seal, Type I	146.000	LF	33.85	31.75	35.00