

Slide Repairs on SR 13 Northbound approximately 500 feet north of SR 481 & on I-20 Eastbound approximately 1 mile east of SR 481 east of milepost 81, known as Federal Aid Project Nos. ER-0322-00(016) / 108486301 & ER-0020-02(099) / 108482301 in Scott County.					Joe McGee Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$652,026.60					\$982,432.35		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	203-EX008	Borrow Excavation, AH, FME, Class B15	2,873.000	CY	43.75		
0020	203-G001	Excess Excavation, FM, AH	3,373.000	CY	26.25		
0030	216-A001	Solid Sodding	8.000	SY	120.00		
0040	219-A001	Watering	1.000	KGAL	20.00		
0050	220-A001	Insect Pest Control	2.000	ACRE	30.00		
0060	223-A001	Mowing	2.000	ACRE	50.00		
0070	227-A001	Hydroseeding	2.000	ACRE	2,900.00		
0080	237-A002	Wattles, 20"	400.000	LF	8.50		
0090	304-F002	Size 610 Crushed Stone Base	864.000	TON	94.50		
0100	601-B002	Class "C" Structural Concrete, Minor Structures	2.000	CY	3,500.00		
0110	605-AA001	Geotextile for Subsurface Drainage, Type III	681.000	SY	4.60		
0120	605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	425.000	LF	21.15		
0130	605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	70.000	LF	25.00		
0140	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	30.000	CY	130.00		
0150	618-A001	Maintenance of Traffic	1.000	LS	68,000.00		
0160	619-A6008	Temporary Traffic Stripe, Legend, Type 1 or 2 Tape	50.000	LF	12.00		
0170	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	60.000	SF	24.00		
0180	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	280.000	SF	24.00		
0190	619-F1001	Concrete Median Barrier, Precast	300.000	LF	29.50		
0200	619-G4001	Barricades, Type III, Double Faced	24.000	LF	69.50		
0210	619-G4005	Barricades, Type III, Single Faced	48.000	LF	45.00		
0220	619-J1005	Impact Attenuator, 70 MPH	1.000	EA	14,000.00		
0230	619-J2005	Impact Attenuator, 70 MPH, Replacement Package	1.000	EA	3,600.00		
0240	620-A001	Mobilization	1.000	LS	87,000.00		
0250	699-A001	Roadway Construction Stakes	1.000	LS	10,000.00		
0260	802-C001	Temporary Steel Sheet Piling	6,000.000	SF	61.35		

Slide Repairs on SR 13 Northbound approximately 500 feet north of SR 481 & on I-20 Eastbound approximately 1 mile east of SR 481 east of milepost 81, known as Federal Aid Project Nos. ER-0322-00(016) / 108486301 & ER-0020-02(099) / 108482301 in Scott County.					Joe McGee Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$652,026.60					\$982,432.35		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	907-234-A001	Temporary Silt Fence	800.000	LF	4.50		
0280	907-619-H2001	Traffic Signal, Portable, Type 1	2.000	EA	37,850.00		