

Mill & Overlay approximately 5 miles of US 84 from US 61 to Dunbarton Road, known as State Project No. MP-7084-01(012) / 308316301 in Adams County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,510,178.60					\$4,949,740.84		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	304-A008	Granular Material, LVM, Class 6, Group D	5,647.000	CY	44.50		
0020	403-A005	19-mm, MT, Asphalt Pavement	401.000	TON	194.00		
0030	403-A014	9.5-mm, MT, Asphalt Pavement	18,571.000	TON	160.00		
0040	403-B011	9.5-mm, MT, Asphalt Pavement, Leveling	2,427.000	TON	177.60		
0050	406-A002	Cold Milling of Bituminous Pavement, All Depths	11,040.000	SY	5.00		
0060	406-D001	Fine Milling of Bituminous Pavement, All Depths	25,700.000	SY	5.50		
0070	407-A001	Asphalt for Tack Coat	24,018.000	GAL	3.54		
0080	412-A001	Pre-Grinding	624.000	SF	3.25		
0090	423-A001	Rumble Strips, Ground In	22.000	MI	900.00		
0100	618-A001	Maintenance of Traffic	1.000	LS	142,000.00		
0110	618-B001	Additional Construction Signs	1.000	SF	10.00		
0120	619-A1001	Temporary Traffic Stripe, Continuous White	16.000	MI	1,250.00		
0130	619-A2001	Temporary Traffic Stripe, Continuous Yellow	14.000	MI	1,250.00		
0140	619-A3001	Temporary Traffic Stripe, Skip White	16.000	MI	1,250.00		
0150	619-A5001	Temporary Traffic Stripe, Detail	53,844.000	LF	0.03		
0160	619-A6001	Temporary Traffic Stripe, Legend	672.000	SF	1.00		
0170	619-A6002	Temporary Traffic Stripe, Legend	2,232.000	LF	0.55		
0180	620-A001	Mobilization	1.000	LS	300,000.00		
0190	626-A001	6" Thermoplastic Double Drop Traffic Stripe, Skip White	11.000	MI	5,500.00		
0200	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	11.000	MI	8,500.00		
0210	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	11.000	MI	8,300.00		
0220	626-G002	Thermoplastic Detail Stripe, White	22,209.000	LF	3.00		
0230	626-G003	Thermoplastic Detail Stripe, Yellow	12,975.000	LF	2.90		
0240	626-H004	Thermoplastic Legend, White	457.000	SF	25.00		
0250	626-H005	Thermoplastic Legend, White	3,008.000	LF	7.00		
0260	627-J001	Two-Way Clear Reflective High Performance Raised Markers	485.000	EA	15.00		

Mill & Overlay approximately 5 miles of US 84 from US 61 to Dunbarton Road, known as State Project No. MP-7084-01(012) / 308316301 in Adams County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,510,178.60					\$4,949,740.84		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	627-K001	Red-Clear Reflective High Performance Raised Markers	1,105.000	EA	15.00		
0280	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	124.000	EA	15.00		
0290	630-F002	Delineators, Flexible Post Mounted, Crossover, Type I, Yellow	56.000	EA	73.00		

Letting Date: 4/25/2023

Call Number: 16

Page 2 of 2