

**Call 10 Overlay approximately 15 miles of SR 433 from Benton to the EOSM at Ebenezer-Coxburg Road, known as State Project Nos. SP-1515-00(013) / 108941301 & SP-1515-00(012) / 108695301 in Holmes & Yazoo Counties.**

Q1. 1.) Is there a cover up time requirement for fine milling areas? 2.) How far from EOP/BOP and from either end of bridges will fine milling be required to go?

A1. 1.) 30 days. 2.) 150 ft. tapers for tie ins at the BOP and EOP. 150 ft. tapers from end of guardrail at bridge ends.

Q2. Are the guardrail pads required to be paved prior to installing new guardrail?

A2. No.