

Overlay approximately 16 miles of SR 448 from SR 1 to US 61, known as State Project No. SP-0610-00(018) / 108694301 in Bolivar County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$6,016,470.70					\$6,422,608.90		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	201-D001	Random Clearing	165.000	STA	650.00		
0020	202-B007	Removal of Asphalt Pavement, All Depths	302.000	SY	48.00		
0030	202-B073	Removal of Concrete Pavement, All Depths	42.000	SY	48.00		
0040	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	2,562.000	LF	11.00		
0050	202-B240	Removal of Traffic Stripe	1,250.000	LF	4.00		
0060	203-G001	Excess Excavation, FM, AH	101.000	CY	2.50		
0070	304-D002	Granular Material, Crushed Stone	5,000.000	TON	66.80		
0080	403-A015	9.5-mm, ST, Asphalt Pavement	17,000.000	TON	159.00		
0090	403-B006	19-mm, ST, Asphalt Pavement, Leveling	206.000	TON	208.40		
0100	403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	6,500.000	TON	186.30		
0110	406-D001	Fine Milling of Bituminous Pavement, All Depths	16,500.000	SY	6.50		
0120	407-A001	Asphalt for Tack Coat	18,500.000	GAL	3.20		
0130	412-A001	Pre-Grinding	11,328.000	SF	3.25		
0140	503-C010	Saw Cut, Full Depth	761.000	LF	10.00		
0150	606-B001	Guard Rail, Class A, Type 1	1,450.000	LF	35.00		
0160	606-D019	Guard Rail, Bridge End Section, Type H	4.000	EA	2,800.00		
0170	606-D022	Guard Rail, Bridge End Section, Type I	12.000	EA	4,100.00		
0180	606-E005	Guard Rail, Terminal End Section, Flared	16.000	EA	3,950.00		
0190	618-A001	Maintenance of Traffic	1.000	LS	500,000.00		
0200	618-B001	Additional Construction Signs	1.000	SF	10.00		
0210	619-A1001	Temporary Traffic Stripe, Continuous White	45.000	MI	2,000.00		
0220	619-A2001	Temporary Traffic Stripe, Continuous Yellow	19.000	MI	2,000.00		
0230	619-A4002	Temporary Traffic Stripe, Skip Yellow	14.000	MI	2,000.00		
0240	619-A5001	Temporary Traffic Stripe, Detail	3,000.000	LF	0.40		
0250	619-A6002	Temporary Traffic Stripe, Legend	500.000	LF	2.00		
0260	620-A001	Mobilization	1.000	LS	550,000.00		

Overlay approximately 16 miles of SR 448 from SR 1 to US 61, known as State Project No. SP-0610-00(018) / 108694301 in Bolivar County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$6,016,470.70					\$6,422,608.90		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	626-B002	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	31.000	MI	6,800.00		
0280	626-D001	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	13.000	MI	3,400.00		
0290	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	10.000	MI	6,800.00		
0300	626-G004	Thermoplastic Double Drop Detail Stripe, White	3,425.000	LF	3.50		
0310	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	1,625.000	LF	3.50		
0320	626-H002	Thermoplastic Double Drop Legend, White	1,900.000	LF	4.00		
0330	627-J001	Two-Way Clear Reflective High Performance Raised Markers	700.000	EA	9.50		
0340	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,550.000	EA	9.50		
0350	630-F006	Delineators, Guard Rail, White	104.000	EA	24.00		
0360	630-G005	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	16.000	EA	85.00		
0370	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	115.00		