

Call 04 Mill & Overlay approximately 11 miles of SR 27 from the Copiah County Line to SR 18, known as Federal Aid Project No. STP-0054-02(032) / 108725301 in Hinds County.

- Q1. 1.) What is the intent of line item 0120: pay item 403-A001, 12.5-mm HT asphalt pavement? 2.) There is also a pay item for temporary portable rumble strips, but on Page 110 of the Scope of Work, it says they will be paid for under Maintenance of Traffic. Which is correct?
- A1. 1.) The 12.5mm, HT, Asphalt Pavement will be used for the guardrail pads and driveway pads. 2.) See addendum.
- Q2. Will 12.5 mm HT Polymer be required on local roads also?
- A2. Yes.
- Q3. Can you provide station numbers for the areas with intended grade corrections with milling and paving?
- A3. At this time no specific locations of slope correction are known. The statement in the Scope of Work is intended for use if locations of slope correction are discovered in the field during construction activities.