

Roundabout Construction on Shriners Blvd. at I-10, known as Federal Aid Project No. STBG-0086-00(009) / 108824301 in Harrison County.					JLB Contractors, LLC	Colony Construction, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,377,622.05					\$2,349,495.45	\$2,410,902.75	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-A001	Clearing and Grubbing	1.000	LS	35,000.00	6,750.00	
0020	202-B007	Removal of Asphalt Pavement, All Depths	2,130.000	SY	5.00	13.00	
0030	202-B088	Removal of Curb & Gutter, All Types	1,015.000	LF	5.00	5.00	
0040	202-B092	Removal of Curb, All Types	491.000	LF	5.00	5.00	
0050	202-B191	Removal of Pipe, 8" And Above	21.000	LF	50.00	22.00	
0060	202-B215	Removal of Sign Including Post & Footing	10.000	EA	125.00	120.00	
0070	203-A001	Unclassified Excavation, FM, AH	695.000	CY	10.00	15.00	
0080	203-EX017	Borrow Excavation, AH, FME, Class B7	3,625.000	CY	20.00	25.00	
0090	203-G001	Excess Excavation, FM, AH	50.000	CY	20.00	21.50	
0100	206-A001	Structure Excavation	19.000	CY	50.00	35.00	
0110	209-A005	Geotextile Stabilization, Type V, Non-Woven	3,693.000	SY	4.00	3.25	
0120	211-B001	Topsoil for Slope Treatment, Contractor Furnished	167.000	CY	40.00	47.80	
0130	213-C001	Superphosphate	1.000	TON	2,500.00	1,700.00	
0140	216-A001	Solid Sodding	13,140.000	SY	7.00	7.70	
0150	219-A001	Watering	263.000	KGAL	20.00	20.00	
0160	220-A001	Insect Pest Control	2.000	ACRE	30.00	30.00	
0170	223-A001	Mowing	2.000	ACRE	50.00	50.00	
0200	226-A001	Temporary Grassing	2.000	ACRE	4,000.00	2,430.00	
0210	237-A002	Wattles, 20"	725.000	LF	6.00	7.70	
0220	245-A001	Silt Dike	250.000	LF	18.00	14.10	
0230	246-B002	Rockbags	280.000	LF	15.00	7.05	
0240	403-A002	12.5-mm, MT, Asphalt Pavement	684.000	TON	205.00	201.00	
0250	403-A005	19-mm, MT, Asphalt Pavement	409.000	TON	250.00	194.20	
0260	403-A006	19-mm, ST, Asphalt Pavement	511.000	TON	230.00	193.60	
0270	403-A014	9.5-mm, MT, Asphalt Pavement	513.000	TON	235.00	210.40	
0280	406-D001	Fine Milling of Bituminous Pavement, All Depths	2,481.000	SY	8.00	17.90	

Roundabout Construction on Shriners Blvd. at I-10, known as Federal Aid Project No. STBG-0086-00(009) / 108824301 in Harrison County.					JLB Contractors, LLC	Colony Construction, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,377,622.05					\$2,349,495.45	\$2,410,902.75	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0290	407-A001	Asphalt for Tack Coat	807.000	GAL	12.00	10.00	
0300	503-C010	Saw Cut, Full Depth	3,307.000	LF	6.00	12.80	
0310	601-B001	Class "B" Structural Concrete, Minor Structures	43.000	CY	2,225.00	1,880.00	
0320	602-A001	Reinforcing Steel	4,045.000	LBS	4.00	3.00	
0330	603-CA011	18" Reinforced Concrete Pipe, Class III	608.000	LF	65.00	81.60	
0340	603-CA040	30" Reinforced Concrete Pipe, Class III	8.000	LF	200.00	156.90	
0350	603-CB003	18" Reinforced Concrete End Section	6.000	EA	1,500.00	1,375.00	
0360	603-CB005	30" Reinforced Concrete End Section	1.000	EA	2,000.00	1,875.00	
0370	603-CE018	44" x 27" Concrete Arch Pipe, Class A III	40.000	LF	255.00	180.80	
0380	603-CE028	58" x 36" Concrete Arch Pipe, Class A III	8.000	LF	320.00	266.50	
0390	603-CF005	44" x 27" Concrete Arch Pipe End Section	2.000	EA	2,600.00	2,345.00	
0400	603-CF007	58" x 36" Concrete Arch Pipe End Section	1.000	EA	3,200.00	3,210.00	
0410	604-A001	Castings	1,766.000	LBS	5.00	5.00	
0420	604-B001	Gratings	800.000	LBS	6.00	5.00	
0430	609-B003	Concrete Curb, Special Design	1,270.000	LF	35.00	57.60	
0440	609-C001	Concrete Integral Curb, Type 1	471.000	LF	35.00	25.60	
0450	609-D012	Combination Concrete Curb and Gutter Type 3A Modified	4,708.000	LF	35.00	35.85	
0460	616-A001	Concrete Median and/or Island Pavement, 10-inch	19.000	SY	115.00	163.80	
0470	616-A003	Concrete Median and/or Island Pavement, 12-inch	1,150.000	SY	115.00	168.90	
0480	618-A001	Maintenance of Traffic	1.000	LS	75,000.00	101,000.00	
0490	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	8,614.000	LF	1.00	0.65	
0500	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	4,159.000	LF	1.00	0.65	
0510	619-A5002	Temporary Traffic Stripe, Detail, Paint	2,164.000	LF	1.30	1.30	
0520	619-A6003	Temporary Traffic Stripe, Legend, Paint	557.000	SF	2.50	2.60	
0530	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	48.000	SF	50.00	25.00	
0540	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	160.000	SF	55.00	25.00	

Roundabout Construction on Shriners Blvd. at I-10, known as Federal Aid Project No. STBG-0086-00(009) / 108824301 in Harrison County.					JLB Contractors, LLC	Colony Construction, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,377,622.05					\$2,349,495.45	\$2,410,902.75	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0550	619-G4001	Barricades, Type III, Double Faced	32.000	LF	75.00	35.00	
0560	619-G4005	Barricades, Type III, Single Faced	32.000	LF	70.00	35.00	
0570	619-G5001	Free Standing Plastic Drums	123.000	EA	80.00	85.00	
0580	620-A001	Mobilization	1.000	LS	190,000.00	140,000.00	
0590	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3,616.000	LF	2.50	2.60	
0600	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	757.000	LF	2.50	2.60	
0610	626-F002	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	2,281.000	LF	2.50	2.60	
0620	626-G004	Thermoplastic Double Drop Detail Stripe, White	371.000	LF	3.75	3.85	
0630	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	918.000	LF	3.75	3.85	
0640	626-H001	Thermoplastic Double Drop Legend, White	488.000	SF	12.00	12.80	
0650	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	4.000	EA	12.00	12.80	
0660	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	94.000	SF	45.00	32.00	
0670	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	72.000	SF	52.00	35.00	
0680	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	128.000	SF	62.00	34.00	
0690	630-C001	Square Tube Posts, 4.0 lb/ft	196.000	LF	47.00	75.00	
0700	630-C005	Square Tube Posts, 2.0 lb/ft	128.000	LF	43.00	60.00	
0710	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	50.000	LF	80.00	88.00	
0720	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	3,406.000	LF	11.00	11.90	
0730	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	276.000	LF	25.00	25.80	
0740	682-C009	Structure Mounted Branch Circuit, AWG 10, 3 Conductor	498.000	LF	17.00	17.90	
0750	682-D002	Structure Mounted Pull Box	4.000	EA	100.00	1.30	
0760	682-D004	Underground Pull Box With Concrete Pad	31.000	EA	1,650.00	1,665.00	
0770	682-F001	Secondary Power Controller	1.000	EA	8,500.00	8,980.00	
0780	683-B200	Lighting Assembly, Low Mast, LED, Type 30-1-10-17	22.000	EA	5,800.00	6,500.00	
0790	683-C001	Lighting Assembly, Underpass, Type A	4.000	EA	650.00	680.00	
0800	684-A005	Pole Foundation, 36" Diameter	87.000	CY	1,000.00	1,025.00	

Roundabout Construction on Shriners Blvd. at I-10, known as Federal Aid Project No. STBG-0086-00(009) / 108824301 in Harrison County.					JLB Contractors, LLC	Colony Construction, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,377,622.05					\$2,349,495.45	\$2,410,902.75	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0810	684-B005	Slip Casing, 36" Diameter	330.000	LF	45.00	46.10	
0820	699-A001	Roadway Construction Stakes	1.000	LS	65,000.00	20,000.00	
0830	907-234-A001	Temporary Silt Fence	600.000	LF	4.00	4.95	
0840	907-616-C003	Colored and Imprinted Concrete Median and Island Pavement, 4-inch Thickness	2,249.000	SF	20.00	32.00	
0850	907-619-E3001	Changeable Message Sign	2.000	EA	19,000.00	20,600.00	
0860	304-F001	3/4" and Down Crushed Stone Base	1,552.000	TON			
0870	304-F002	Size 610 Crushed Stone Base	1,552.000	TON	75.00	81.30	
0880	304-F003	Size 825B Crushed Stone Base	1,552.000	TON			