

Call 05 Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.

Q1. Will precast drainage units be allowed on this project?

A1. No.

Q2. Pay Item No. 202-B027- Removal of Bridge Deck, Curb and Railing plan quantity is 837 SY per sheet number 8002. Our quantity take-off yields 25% of the plan quantity. Please verify removal area or advise measurement process.

A2. See addendum.

Q3. The plans call for (4) electrical pull boxes but there are no line items listed for pull boxes. **1.)** The junction boxes shown on the drawings have pay items but the (4) pull boxes do not. How are the (4) pull boxes to be paid for? **2.)** The drawings call for splices of the existing conductors. Is it expected to be inline splices in conduit or should their be a junction box for the splices to be located in? Please see Drawing LP-2 Note 8.

A3. **1.)** These pull boxes are to be absorbed in other items bid. **2.)** Splices shall be established within the closest new or existing electrical junction structure, pull box, or light pole base so that splices are accessible for maintenance in the future.