

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					Huey P Stockstill, LLC	Necaise Brothers Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,641,086.30					\$17,957,622.50	\$19,029,085.15	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-A001	Clearing and Grubbing	1.000	LS	18,000.00	40,000.00	
0020	201-B001	Clearing and Grubbing	1.000	ACRE	18,000.00	11,114.00	
0030	202-B006	Removal of Asphalt Paved Shoulders, All Depths	2,149.000	SY	18.00	27.00	
0040	202-B007	Removal of Asphalt Pavement, All Depths	4,720.000	SY	13.00	33.00	
0050	202-B052	Removal of Concrete Driveways, All Depths	1,160.000	SY	13.00	45.00	
0060	202-B059	Removal of Concrete Median & Island Pavement, All Depths	157.000	SY	13.00	254.00	
0070	202-B063	Removal of Concrete Paved Ditch	328.000	SY	13.00	61.00	
0080	202-B073	Removal of Concrete Pavement, All Depths	9,030.000	SY	18.00	44.00	
0090	202-B089	Removal of Curb &/or Curb and Gutter, All Types	1,769.000	LF	18.00	44.00	
0100	202-B090	Removal of Curb Inlet	1.000	EA	6,500.00	890.00	
0110	202-B092	Removal of Curb, All Types	1,410.000	LF	25.00	45.00	
0120	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	619.000	LF	11.50	11.50	
0130	202-B170	Removal of Junction Box	2.000	EA	250.00	224.25	
0140	202-B178	Removal of Low Mast Lighting Assembly and Foundation	2.000	EA	2,500.00	592.25	
0150	202-B191	Removal of Pipe, 8" And Above	6.000	LF	125.00	17.00	
0160	202-B240	Removal of Traffic Stripe	19,670.000	LF	3.00	3.50	
0170	202-B251	Removal of Underground Electric Wire	1,680.000	LF	1.50	1.35	
0180	203-A001	Unclassified Excavation, FM, AH	4,965.000	CY	33.50	20.50	
0190	203-EX017	Borrow Excavation, AH, FME, Class B7	29,847.000	CY	36.00	25.50	
0200	206-A001	Structure Excavation	575.000	CY	60.00	22.50	
0210	209-A005	Geotextile Stabilization, Type V, Non-Woven	15,744.000	SY	5.00	4.70	
0220	211-B001	Topsoil for Slope Treatment, Contractor Furnished	3,411.000	CY	40.00	16.00	
0230	213-C001	Superphosphate	7.000	TON	1,250.00	1,380.00	
0240	216-A001	Solid Sodding	3,360.000	SY	10.00	6.15	
0250	217-A001	Ditch Liner	847.000	SY	3.00	3.00	
0260	219-A001	Watering	78.000	KGAL	20.00	20.00	

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					Huey P Stockstill, LLC	Necaise Brothers Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,641,086.30					\$17,957,622.50	\$19,029,085.15	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	220-A001	Insect Pest Control	14.000	ACRE	30.00	30.00	
0280	221-A001	Concrete Paved Ditch	234.000	CY	975.00	1,512.25	
0290	223-A001	Mowing	14.000	ACRE	50.00	50.00	
0300	225-A001	Grassing	14.000	ACRE	1,000.00	920.00	
0310	225-B001	Agricultural Limestone	6.000	TON	825.00	805.00	
0320	225-C001	Mulch, Vegetative Mulch	25.000	TON	875.00	833.75	
0330	226-A001	Temporary Grassing	14.000	ACRE	1,700.00	1,610.00	
0340	237-A002	Wattles, 20"	13,900.000	LF	6.00	6.00	
0350	239-A001	Temporary Slope Drains	732.000	LF	5.00	5.25	
0360	246-B001	Rockbags	2,213.000	EA	5.00	5.00	
0370	249-A001	Riprap for Erosion Control	80.000	TON	125.00	111.00	
0380	403-A002	12.5-mm, MT, Asphalt Pavement	2,614.000	TON	165.00	190.00	
0390	403-A003	12.5-mm, ST, Asphalt Pavement	501.000	TON	165.00	190.00	
0400	403-A005	19-mm, MT, Asphalt Pavement	3,098.000	TON	175.00	201.00	
0410	403-A006	19-mm, ST, Asphalt Pavement	4,236.000	TON	158.00	182.00	
0420	403-A014	9.5-mm, MT, Asphalt Pavement	2,470.000	TON	158.00	182.00	
0430	403-A015	9.5-mm, ST, Asphalt Pavement	376.000	TON	180.00	207.00	
0440	403-B002	12.5-mm, MT, Asphalt Pavement, Leveling	679.000	TON	180.00	207.00	
0450	406-D001	Fine Milling of Bituminous Pavement, All Depths	2,199.000	SY	12.00	14.00	
0460	407-A001	Asphalt for Tack Coat	6,035.000	GAL	5.00	5.75	
0470	423-A001	Rumble Strips, Ground In	1.000	MI	5,000.00	20,987.50	
0480	503-C010	Saw Cut, Full Depth	1,670.000	LF	10.00	5.75	
0490	601-B001	Class "B" Structural Concrete, Minor Structures	110.000	CY	2,500.00	3,000.00	
0500	602-A001	Reinforcing Steel	9,498.000	LBS	3.00	5.00	
0510	603-CA012	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	648.000	LF	100.00	107.00	
0520	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	296.000	LF	125.00	128.50	

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					Huey P Stockstill, LLC	Necaise Brothers Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,641,086.30					\$17,957,622.50	\$19,029,085.15	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	603-CA041	30" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	80.000	LF	150.00	185.50	
0540	603-CA056	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	96.000	LF	175.00	239.25	
0550	603-CB003	18" Reinforced Concrete End Section	3.000	EA	1,900.00	1,600.00	
0560	603-CB004	24" Reinforced Concrete End Section	5.000	EA	2,500.00	2,300.00	
0570	603-CB005	30" Reinforced Concrete End Section	3.000	EA	3,000.00	2,800.00	
0580	603-CB006	36" Reinforced Concrete End Section	2.000	EA	4,000.00	3,600.00	
0590	603-CE003	22" x 13" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	24.000	LF	160.00	271.00	
0600	603-CE009	29" x 18" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	424.000	LF	215.00	218.00	
0610	604-A001	Castings	1,817.000	LBS	12.50	5.10	
0620	604-B001	Gratings	300.000	LBS	42.00	7.93	
0630	606-B001	Guard Rail, Class A, Type 1	113.000	LF	55.00	55.20	
0640	606-D022	Guard Rail, Bridge End Section, Type 1	3.000	EA	5,250.00	5,232.50	
0650	606-E007	Guard Rail, Terminal End Section, Non-Flared	3.000	EA	5,250.00	5,175.00	
0660	608-A001	Concrete Sidewalk, Without Reinforcement	2,085.000	SY	80.00	76.99	
0670	609-B003	Concrete Curb, Special Design	1,157.000	LF	38.50	36.80	
0680	609-C001	Concrete Integral Curb, Type 1	811.000	LF	38.50	36.80	
0690	609-D003	Combination Concrete Curb and Gutter Type 2	190.000	LF	38.50	36.80	
0700	609-D009	Combination Concrete Curb and Gutter Type 3A Mod1	8,511.000	LF	33.50	36.80	
0710	614-A001	Concrete Driveway, Without Reinforcement	1,378.000	SY	132.00	126.50	
0720	616-A001	Concrete Median and/or Island Pavement, 10-inch	308.000	SY	140.00	135.70	
0730	616-A004	Concrete Median and/or Island Pavement, 4-inch	2,054.000	SY	78.00	74.75	
0740	617-A001	Right-of-Way Marker	10.000	EA	425.00	517.50	
0750	618-A001	Maintenance of Traffic	1.000	LS	750,000.00	1,577,461.00	
0760	619-A1001	Temporary Traffic Stripe, Continuous White	6.000	MI	2,100.00	2,300.00	
0770	619-A1005	Temporary Traffic Stripe, Continuous White, Type 1 Tape	2,196.000	LF	2.25	2.30	
0780	619-A2001	Temporary Traffic Stripe, Continuous Yellow	6.000	MI	2,100.00	2,300.00	

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					Huey P Stockstill, LLC	Necaise Brothers Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,641,086.30					\$17,957,622.50	\$19,029,085.15	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0790	619-A2006	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	2,196.000	LF	2.25	2.30	
0800	619-A3002	Temporary Traffic Stripe, Skip White	2,318.000	LF	1.00	1.15	
0810	619-A5001	Temporary Traffic Stripe, Detail	14,552.000	LF	0.50	0.40	
0820	619-A6001	Temporary Traffic Stripe, Legend	2,303.000	SF	2.25	2.30	
0830	619-A6002	Temporary Traffic Stripe, Legend	184.000	LF	3.25	3.45	
0840	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	209.000	SF	10.00	19.55	
0850	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,006.000	SF	10.00	19.55	
0860	619-E1001	Flashing Arrow Panel, Type C	1.000	EA	6,275.00	4,025.00	
0870	619-F1001	Concrete Median Barrier, Precast	2,620.000	LF	125.00	99.48	
0880	619-F2001	Remove and Reset Concrete Median Barrier, Precast	4,360.000	LF	35.00	31.40	
0890	619-G4005	Barricades, Type III, Single Faced	372.000	LF	50.00	84.24	
0900	619-G5001	Free Standing Plastic Drums	210.000	EA	100.00	140.31	
0910	619-G7001	Warning Lights, Type "B"	9.000	EA	200.00	221.83	
0920	619-J1001	Impact Attenuator, 40 MPH	4.000	EA	9,000.00	12,075.00	
0930	619-J2001	Impact Attenuator, 40 MPH, Replacement Package	8.000	EA	7,000.00	7,245.00	
0940	620-A001	Mobilization	1.000	LS	1,565,500.00	1,486,000.00	
0950	626-A002	6" Thermoplastic Double Drop Traffic Stripe, Skip White	1,833.000	LF	2.00	2.30	
0960	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3,804.000	LF	2.00	2.30	
0970	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	2,542.000	LF	2.00	2.30	
0980	626-F002	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	1,039.000	LF	2.00	2.30	
0990	626-G004	Thermoplastic Double Drop Detail Stripe, White	8,332.000	LF	4.00	4.60	
1000	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	5,815.000	LF	4.00	4.60	
1010	626-H001	Thermoplastic Double Drop Legend, White	2,303.000	SF	12.00	13.80	
1020	627-K001	Red-Clear Reflective High Performance Raised Markers	114.000	EA	12.00	11.50	
1030	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	32.000	EA	12.00	11.50	
1040	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	200.000	SF	30.00	33.35	

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					Huey P Stockstill, LLC	Necaise Brothers Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,641,086.30					\$17,957,622.50	\$19,029,085.15	
Ref#	Item	Item Description	Item Qty	Units	1	2	
1050	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	106.000	SF	30.00	35.65	
1060	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	111.000	SF	30.00	34.50	
1070	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	161.000	SF	40.00	44.85	
1080	630-C003	Steel U-Section Posts, 3.0 lb/ft	637.000	LF	25.00	26.45	
1090	630-D008	Structural Steel Beams, W6 x 9	195.000	LF	80.00	90.85	
1100	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	227.000	LBS	5.00	5.18	
1110	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	106.000	LBS	5.00	4.31	
1120	630-F006	Delineators, Guard Rail, White	9.000	EA	30.00	28.75	
1130	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	2.000	EA	200.00	201.25	
1140	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	2.000	EA	200.00	201.25	
1150	630-K001	Welded & Seamless Steel Pipe Posts, 3 1/2"	166.000	LF	60.00	66.70	
1160	630-K003	Welded & Seamless Steel Pipe Posts, 4"	18.000	LF	70.00	74.75	
1170	682-A028	Underground Branch Circuit, AWG 4, 3 Conductor	490.000	LF	14.00	13.69	
1180	682-A038	Underground Branch Circuit, AWG 8, 2 Conductor	160.000	LF	8.00	8.05	
1190	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	4,360.000	LF	9.00	8.97	
1200	682-A041	Underground Branch Circuit, AWG 8, 5 Conductor	230.000	LF	13.00	13.00	
1210	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	310.000	LF	20.00	19.32	
1220	682-E003	Underground Junction Box With Concrete Pad	28.000	EA	2,500.00	2,346.00	
1230	683-B001	Lighting Assembly, Low Mast, LED, Type 15-1-0-90	28.000	EA	4,800.00	4,617.25	
1240	684-A003	Pole Foundation, 24" Diameter	30.000	CY	1,800.00	1,713.50	
1250	699-A001	Roadway Construction Stakes	1.000	LS	375,000.00	340,000.00	
1260	815-A007	Loose Riprap, Size 300	80.000	TON	180.00	108.00	
1270	815-E001	Geotextile under Riprap	107.000	SY	50.00	12.85	
1280	907-234-A001	Temporary Silt Fence	13,400.000	LF	5.00	4.00	
1290	907-234-C001	Super Silt Fence	400.000	LF	15.00	12.65	
1300	907-234-D001	Inlet Siltation Guard	2.000	EA	100.00	557.75	

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					Huey P Stockstill, LLC	Necaise Brothers Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,641,086.30					\$17,957,622.50	\$19,029,085.15	
Ref#	Item	Item Description	Item Qty	Units	1	2	
1310	907-234-E001	Reset Inlet Siltation Guard	2.000	EA	100.00	247.25	
1320	907-604-PP001	Modify Existing Inlet, Per Plans	1.000	EA	15,500.00	2,282.66	
1330	907-608-C001	Detectable Warning Panels	126.000	SF	120.00	115.00	
1340	907-609-F002	Prefabricated Curb	815.000	LF	60.00	50.00	
1350	907-616-C002	Colored and Imprinted Concrete Median and Island Pavement, 12-inch Thickness	7,911.000	SF	31.25	30.07	
1360	907-619-E3001	Changeable Message Sign	8.000	EA	13,250.00	11,500.00	
1370	907-682-A1007	Branch Circuit Wire, AWG #10, 1 Conductor	310.000	LF	0.65	0.69	
1380	907-682-A1018	Branch Circuit Wire, AWG #4, 1 Conductor	1,060.000	LF	2.00	1.96	
1390	907-906001	Trainees	720.000	HRS	5.00	5.00	
1400	304-F001	3/4" and Down Crushed Stone Base	16,650.000	TON			
1410	304-F002	Size 610 Crushed Stone Base	16,650.000	TON	80.00	86.50	
1420	304-F003	Size 825B Crushed Stone Base	16,650.000	TON			
1430	907-624-A002	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White	366.000	LF			
1440	907-624-B002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White	732.000	LF			
1450	907-624-D002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow	732.000	LF			
1460	628-G001	6" High Performance Cold Plastic Traffic Stripe, Skip White	366.000	LF	9.00	9.20	
1470	628-H001	6" High Performance Cold Plastic Traffic Stripe, Continuous White	732.000	LF	9.00	9.20	
1480	628-J001	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow	732.000	LF	9.00	9.20	
1490	202-B027	Removal of Bridge Deck, Curb and Railing	202.000	SY	1,750.00	1,725.00	
1500	202-B275	Removal of Part of End Bent Cap, Curb, and Wingwall	54.000	SY	1,000.00	862.50	
1510	202-B277	Removal of Part of Int. Bent Cap	24.000	SY	900.00	862.50	
1520	503-C001	Saw Cut, 1-inch	1,684.000	LF	13.00	12.65	
1530	608-B001	Concrete Sidewalk, With Reinforcement	564.000	SY	267.50	256.45	
1540	803-D005	HP 14 x 117 Steel Piling	580.000	LF	215.00	207.00	
1550	803-P001	24" Steel Pipe Piling, Wall Thickness 0.500"	1,390.000	LF	290.00	277.15	
1560	804-C209	115' Prestressed Concrete Beam, Type FIB-45	1,370.000	LF	720.00	690.00	

Interchange Reconstruction on I-10 at Diamondhead, known as Federal Aid Project No. NHPP-0010-01(161) / 107509301 in Hancock County.					Huey P Stockstill, LLC	Necaise Brothers Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,641,086.30					\$17,957,622.50	\$19,029,085.15	
Ref#	Item	Item Description	Item Qty	Units	1	2	
1570	804-C269	68' Prestressed Concrete Beam, Type FIB-45	808.000	LF	720.00	690.00	
1580	805-A001	Reinforcement	132,840.000	LBS	2.50	2.42	
1590	805-C001	Reinforcement, Corrosion Resistant	3,570.000	LBS	3.75	3.68	
1600	813-A004	Concrete Railing, 36"	366.000	LF	117.50	112.70	
1610	813-E007	Modified Railing	366.000	LF	1,015.00	972.90	
1620	815-D001	Concrete Slope Paving	18.000	CY	6,600.00	6,325.00	
1630	907-803-B001	Conventional Static Pile Load Test	1.000	EA	5,000.00	5,000.00	
1640	907-803-I003	PDA Test Pile, HP Steel Pile	1.000	EA	60,000.00	57,500.00	
1650	907-803-I004	PDA Test Pile, Steel Pipe Pile	1.000	EA	70,000.00	66,700.00	
1660	907-803-J001	Pile Restrike	2.000	EA	1,200.00	1,150.00	
1670	907-804-A001	Bridge Concrete, Class BDX	398.000	CY	3,850.00	3,680.00	
1680	907-804-A002	Bridge Concrete, Class AA	141.000	CY	4,200.00	4,025.00	
1690	907-808-A002	Joint Repair	66.000	LF	250.00	230.00	
1700	907-823-A002	Preformed Joint Seal, Type II	105.000	LF	120.00	115.00	