

Call 02 Mill & Overlay approximately 1 mile of US 49 from Richland Creek to US 80 & Frontage Roads from 0.6 miles south of Industrial Park Drive to north of Carrier Boulevard, known as Federal Aid project No. STP-0008-03(063) / 109444301 in Rankin County.

- Q1. 1.) Can you provide a map that has the Stations for the East and West Frontage Roads? On page 111 and 112 of the Proposal it lists Sta 12+00 to 16+58, 32+50 to 23+32, but on page 107 it does not show the Stations for the Frontage Roads. 2.) Also, on page 115, the Extra Depth Repairs calls for Fine Milling. Is this correct? Where will Pay Item 406-A002 be used?
- A1. 1.) See addendum. 2.) As shown on Page 119, Pay Item No. 406-A002 Cold Milling of Bituminous Pavements, All Depths shall be used for the longitudinal joint repairs.
- Q2. 907-626-H002, Thermoplastic Legend, Interstate Shield, EA - Can this Product/Pay Item be used in lieu of 907-625-G001 Methyl Methacrylate Pavement Markings for Interstate Route Shield Marker
- A2. No.
- Q3. On page 122 of the proposal, it notes that County Roads are to be milled 1.5" and overlaid with 1.5" of 9.5mm, SMA. Is this correct or should County Roads be overlaid with 9.5mm, HT mix?
- A3. County roads will be overlaid with 9.5-mm, HT asphalt.
- Q4. Please provide the dimensions for the Interstate Route Shield Markers. Pay Item is 72 SF each.
- A4. See addendum.