

Call 14 Overlay approximately 10 miles of SR 32 from SR 1 to SR 161, known as State Project No. MP-3032-06(005) / 308280301 in Bolivar County.

- Q1. See sheet #85 in proposal. Pay item #630-G005 is missing. Quantity for this item is 12. Pay item #630-F006, quantity should be 42 not 54 in notice to contractors.
- A1. See addendum.
- Q2. Will asphalt guardrail pads be required at bridge 2.6?
- A2. Yes.
- Q3. Will non-existent apron and local road intersections be required to be constructed with multiple lifts (19mm & 9.5mm)?
- A3. Yes, multiple lifts of 9.5-mm will be required.
- Q4. Would it be a good plan to add the longitudinal joints in this section to the saw and seal joints? Or would that be something that could be added later with a quantity overrun? That would only add approximately 1,500 LF to saw and seal pay item.
- A4. Only the transverse joints will require sawing and sealing.