

**Call 03 Bridge Repair on Culkin Road over US 61 (Bridge No. 118.9), known as Federal Aid Project No. STBG-0009-02(090) / 109527301 in Warren County.**

Q1. Will MDOT accept 907-828-1 Hybrid Polymer Concrete as an alternative to 907-417-1 Polymer Cement Surface System?

A1. No.

Q2. Sheet 61 calls for the new curb to be installed to the original plan dimensions, is this an absorbed item?

A2. Yes.

Q3. On sheet -22- (bearing replacement details) the Anchor plates are called out with a 0.375"x 0.75" retaining bar on 4 sides of the anchor plate. Is it acceptable to buy thicker anchor plates (2.375") and machine a "pocket" 0.375" deep in lieu of welding the bars?

A3. Yes, but four drainage channels shall be cut into the thicker anchor plate on the corners.