

**Call 08 Placement of Audible Stripe and Signing Improvements along SR 25 from 0.3 miles north of SR 8 to the SR 25 Bypass, known as Federal Aid Project No. HSIP-0040-01(038) / 109542301 in Monroe County.**

- Q1. 1.) The Proposal says in the Scope of work Audible Markings will be on the Centerline according to Special Provisions No. 907-626 Page 74 however there are no Pay Items for this, just Edge Audible Pay Items. Will there be a Pay Item for the Center Line Audible? 2.) Scope of Work on Page 75 Mentions Potholes must be patched will this be done on this Project? 3.) Bridges that have stripe on them are asphalt will the stripe have to be Removed since they are not concrete? 4.) Will sweeping be sufficient on Main Line Prior to Restripe?
- A1. 1.) See addendum. 2.) See addendum. 3.) Stripe will not have to be removed from asphalt surfaces. 4.) Loose existing thermoplastic material shall be removed by brooming or other approved methods by the Engineer prior to the placement of new thermoplastic pavement markings.