

| Bridge Preventive Maintenance on SR 16 (Bridge No. 122.8), SR 15 (Bridge Nos. 172.2, 172.4, & 172.6) & I-20 (Bridge Nos. 100.5B, 110.7A & 110.7B), known as Federal Aid Project No. STBG-9999-05(396) / 1087793050, 3051, & 3052 in Leake, Neshoba, & Newton Counties. |               |  |           |       | Century Construction Group, Inc. | Gibson & Associates, Inc. | Key, LLC       |
|--|---------------|--|-----------|-------|----------------------------------|---------------------------|----------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,516,659.20   |               |  |           |       | \$1,669,281.00                   | \$1,780,762.80            | \$2,145,829.00 |
| Ref#   | Item          | Item Description   | Item Qty  | Units | 1                                | 2                         | 3              |
| 0010   | 619-D1001     | Standard Roadside Construction Signs, Less than 10 Square Feet | 80.000    | SF    | 9.50                             | 8.80                      | 9.00           |
| 0020   | 619-D2001     | Standard Roadside Construction Signs, 10 Square Feet or More   | 160.000   | SF    | 9.50                             | 8.80                      | 9.00           |
| 0030   | 619-F1001     | Concrete Median Barrier, Precast                               | 70.000    | LF    | 90.00                            | 290.00                    | 110.00         |
| 0040   | 619-G4001     | Barricades, Type III, Double Faced                             | 48.000    | LF    | 28.00                            | 25.30                     | 26.00          |
| 0050   | 619-G4005     | Barricades, Type III, Single Faced                             | 72.000    | LF    | 25.00                            | 23.10                     | 26.00          |
| 0060   | 619-J1002     | Impact Attenuator, 45 MPH                                      | 1.000     | EA    | 7,750.00                         | 6,500.00                  | 10,630.00      |
| 0070   | 619-J2002     | Impact Attenuator, 45 MPH, Replacement Package                 | 1.000     | EA    | 3,750.00                         | 3,750.00                  | 4,500.00       |
| 0080   | 620-A001      | Mobilization   | 1.000     | LS    | 165,000.00                       | 262,000.00                | 210,000.00     |
| 0090   | 907-420-A001  | Undersealing   | 7,500.000 | LBS   | 4.75                             | 5.50                      | 5.50           |
| 0100   | 907-618-A001  | Maintenance of Traffic   | 1.000     | LS    | 130,000.00                       | 67,000.00                 | 150,000.00     |
| 0110   | 907-899-A001  | Railway-Highway Provisions                                     | 1.000     | LS    | 30,000.00                        | 36,500.00                 | 143,000.00     |
| 0120   | 202-B063      | Removal of Concrete Paved Ditch                                | 89.000    | SY    | 65.00                            | 165.00                    | 50.00          |
| 0130   | 815-A007      | Loose Riprap, Size 300   | 1,500.000 | TON   | 180.00                           | 250.00                    | 150.00         |
| 0140   | 815-E001      | Geotextile under Riprap  | 670.000   | SY    | 8.50                             | 10.00                     | 5.00           |
| 0150   | 907-808-A002  | Joint Repair   | 1,272.000 | LF    | 25.00                            | 11.00                     | 11.00          |
| 0160   | 907-823-A001  | Preformed Joint Seal, Type I                                   | 636.000   | LF    | 35.00                            | 38.50                     | 38.00          |
| 0170   | 907-823-B001  | Saw Cut, Type I  | 1,272.000 | LF    | 11.00                            | 6.60                      | 7.00           |
| 0180   | 907-824-A003  | General Epoxy Repair   | 71.000    | SF    | 250.00                           | 490.00                    | 955.00         |
| 0190   | 907-824-C001  | Cap Cleaning   | 57.000    | EA    | 1,550.00                         | 1,375.00                  | 1,900.00       |
| 0200   | 907-824-D001  | Bearing Replacements   | 178.000   | EA    | 4,100.00                         | 4,225.00                  | 5,500.00       |
| 0210   | 907-824-PP004 | Bridge Repair, Bank Reshaping                                  | 1.000     | LS    | 100,000.00                       | 30,000.00                 | 138,500.00     |