

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. <u> 1 </u>	DATED <u> 9/19/2024 </u>	ADDENDUM NO. <u> </u>	DATED <u> </u>
ADDENDUM NO. <u> </u>	DATED <u> </u>	ADDENDUM NO. <u> </u>	DATED <u> </u>
ADDENDUM NO. <u> </u>	DATED <u> </u>	ADDENDUM NO. <u> </u>	DATED <u> </u>

Number	Description
1	Revised Bid Items; Revised or Added Plan Sheet Nos. 2, 4 & 12; Amendment EBSx Download Required.

TOTAL ADDENDA: 1
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____
Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____	President	Address
_____	Secretary	Address
_____	Treasurer	Address

The following is my (our) itemized proposal.
 NHPP-0056-01(105)/ 108281301000
 Rankin County(ies)
 Revised 01/26/2016

Bridge Preservation on SR 25 over Plummer Slough (Bridge No. 12.7), known as Federal Aid Project No. NHPP-0056-01(105) / 108281301 in Rankin County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	201-B001		1	Acre	Clearing and Grubbing
0020	203-EX008	(E)	79	Cubic Yard	Borrow Excavation, AH, FME, Class B15
0030	203-G001	(E)	27	Cubic Yard	Excess Excavation, FM, AH
0040	206-A001	(S)	74	Cubic Yard	Structure Excavation
0050	206-B001	(E)	33	Cubic Yard	Select Material for Undercuts, Contractor Furnished, FM
0060	213-C001		1	Ton	Superphosphate
0070	220-A001		1	Acre	Insect Pest Control [\$30.00]
0080	223-A001		1	Acre	Mowing [\$50.00]
0090	225-B001		1	Ton	Agricultural Limestone
0110	227-A001		1	Acre	Hydroseeding
0120	237-A002		100	Linear Feet	Wattles, 20"
0130	617-B001		8	Each	Permanent Easement Marker
0140	619-D1001		8	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0150	619-D2001		78	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0160	619-G4005		78	Linear Feet	Barricades, Type III, Single Faced
0170	619-G5001		12	Each	Free Standing Plastic Drums
0180	620-A001		1	Lump Sum	Mobilization
0190	699-A001		1	Lump Sum	Roadway Construction Stakes
0200	907-234-A001		1,560	Linear Feet	Temporary Silt Fence
0210	907-234-C001		100	Linear Feet	Super Silt Fence
0220	907-234-F001		130	Linear Feet	Turbidity Barrier
0230	907-618-A001		1	Lump Sum	Maintenance of Traffic
0240	907-619-E3001		3	Each	Changeable Message Sign
Bridge Items					
0250	203-F001	(E)	1,720	Cubic Yard	Channel Excavation, FM
0260	304-D004	(GT)	150	Ton	Granular Material, Size 57
0270	805-A001	(S)	43,369	Pounds	Reinforcement
0280	815-A007	(S)	7,483	Ton	Loose Riprap, Size 300
0290	815-E001	(S)	4,223	Square Yard	Geotextile under Riprap
0300	907-804-B001	(S)	235	Cubic Yard	Box Bridge Concrete, Class B
0310	907-824-PP004		1	Lump Sum	Bridge Repair, Dewatering and Water Diversion Measurements
0320	907-824-PP004		1	Lump Sum	Bridge Repair, Removal of Existing Headwall, Apron, Wing Walls, and a Portion of Barrel

ADDENDUM

DESCRIPTION OF SHEET

TITLE SHEET (1)

1

DETAILED INDEX & GENERAL NOTES (2)

DETAILED INDEX

2

GENERAL NOTES

3

QUANTITY SHEETS (3)

△ SUMMARY OF QUANTITIES

4

ESTIMATED QUANTITIES - TRAFFIC CONTROL ITEMS AND EARTHWORK

5

ESTIMATED QUANTITIES - TRAFFIC CONTROL SIGNS

6

PLAN & PROFILE SHEETS (1)

SR 25 OVER PLUMMER SLOUGH

7

SPECIAL DESIGN SHEETS (5)

RIPRAP LIMITS

8

DETAIL OF CONSTRUCTION SIGNING

9

TRAFFIC CONTROL - PHASE I

10

PERMANENT EASEMENT COORDINATES

11

△ VEGETATION SCHEDULE

12

STANDARD DRAWINGS (14)

TYPICAL TEMPORARY EROSION/ SEDIMENT CONTROL APPLICATIONS

6101

DETAILS OF SEDIMENT BARRIER APPLICATIONS

6102

DETAILS OF SILT FENCE INSTALLATION

6103

DITCH CHECK STRUCTURES, TYPICAL APPLICATIONS AND DETAILS

6104

TEMPORARY EROSION, SEDIMENT, AND WATER POLLUTION CONTROL MEASURES (SILT

FENCE AND HAY BALE DITCH CHECKS)

6105

DETAILS OF EROSION CONTROL WATTLE DITCH CHECK

6106

TEMPORARY STREAM DIVERSION (BOX EXTENSION)

6119

FLOATING TURBIDITY CURTAIN

6120

SUPER SILT FENCE

6130

HIGHWAY SIGN AND BARRICADE DETAILS FOR CONSTRUCTION PROJECTS

6358

TRAFFIC CONTROL DETAILS DRUM PLACEMENT AND SHOULDER CLOSURE

6366

RIGHT-OF-WAY MARKER

6401

COLLAR DETAILS FOR BOX STRUCTURES (SINGLE & DOUBLE)

7008

CULVERT DRAWING - EXTENSION DETAILS - FOR LENGTHENING EXISTING BOX CULVERTS

7010

TOTAL SHEETS (26)

WK. NO., SHEET NO.

STATE	PROJECT NO.
MISS.	NHPP-0056-01(105)

PS & E PLANS-DATE 08/05/24	
FMS CON. # 108281-301000	
REVISIONS	
DATE	BY
9-9-24	4.12
	SR

RUST

BY	REVISION	DATE


MISSISSIPPI DEPARTMENT OF TRANSPORTATION
DETAILED INDEX

PROJ. NO.: NHPP-0056-01(105)
COUNTY: RANKIN

WORKING NUMBER
DI-1

SHEET NUMBER
2

FILE NAME: DLGDD
DESIGN TEAM: RUST
CHECKED: _____
DATE: _____



ADDENDUM

STATE	PROJECT NO.
MISS	NHPP-0056-01(105)


PAY ITEM NO.	PAY ITEM	UNIT	RANKIN : 108281-301000	
			Prelim	Final
201-B001	Clearing and Grubbing	ACRE	1	
203-EX008	Borrow Excavation, AH, FME, Class B15	CY	79	
203-G001	Excess Excavation, FM, AH	CY	27	
206-A001	Structure Excavation	CY	74	
206-B001	Select Material for Undercuts, Contractor Furnished, FM	CY	33	
213-C001	Superphosphate	TON	1	
220-A001	Insect Pest Control	ACRE	1	
223-A001	Mowing	ACRE	1	
225-B001	Agricultural Limestone	TON	1	
227-A001	Hydroseeding	ACRE	1	
907-234-A001	Temporary Silt Fence	LF	1,560	
907-234-C001	Super Silt Fence	LF	100	
907-234-F001	Turbidity Barrier	LF	130	
237-A002	Wattles, 20"	LF	100	
617-B001	Permanent Easement Marker	EA	8	
907-618-A001	Maintenance of Traffic	LS	1	
619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	SF	8	
619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	SF	78	
907-619-E3001	Changeable Message Sign	EA	3	
619-G4005	Barricades, Type III, Single Faced	LF	78	
619-G5001	Free Standing Plastic Drums	EA	12	
620-A001	Mobilization	LS	1	
699-A001	Roadway Construction Stakes	LS	1	

SUMMARY OF QUANTITIES (SHEET 1)

SR	UPDATED PAY ITEMS
09/09/2024	Revision

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PROJ NO: NHPP-0056-01(105)
COUNTY: RANKIN



Working Number
SQ-1

Sheet Number
4

FILENAME: 108281-301000-SQS
Design Team: RUST Checked Date

ADDENDUM

FMS CON: 108281 /301000

STATE	PROJECT NO.
MISS.	NHPP-0056-01(105)



EROSION CONTROL ITEMS		VEGETATION SCHEDULE			
SEASONAL APPLICATIONS-DATES & RATES		REQUIREMENTS			
PAY ITEM NO.	ITEMS	SPRING & SUMMER		FALL & WINTER	
		RATES	DATES	RATES	DATES
211-B001	TOPSOIL FOR SLOPE TREATMENT (LVM)	4" THICK	MARCH 1 TO SEPTEMBER 1	4" THICK	SEPTEMBER 1 TO MARCH 1
225-A001	STANDARD GROUND PREPARATION	PER SQ.YD.	MARCH 1 TO SEPTEMBER 1	PER SQ.YD.	SEPTEMBER 1 TO MARCH 1
225-B001	AGRICULTURAL LIMESTONE	1000 LBS./ACRE	MARCH 1 TO SEPTEMBER 1		SEPTEMBER 1 TO MARCH 1
225-A001	COMBINATION FERTILIZER (13-13-13)	250 LBS./ACRE	MARCH 1 TO SEPTEMBER 1		SEPTEMBER 1 TO MARCH 1
213-C001	SUPERPHOSPHATE	0.5 TONS/ACRE (EST.)	MARCH 1 TO DECEMBER 1		SEPTEMBER 1 TO MARCH 1
225-A001	SEEDING (BERMUDAGRASS)	80 LBS./ACRE	MARCH 1 TO SEPTEMBER 1		SEPTEMBER 1 TO MARCH 1
225-A001	SEEDING (BAHIAGRASS)	80 LBS./ACRE	MARCH 1 TO SEPTEMBER 1		SEPTEMBER 1 TO MARCH 1
225-A001	SEEDING (TALL FESCUE)			100 LBS./ACRE	NOVEMBER 1 TO APRIL 1
225-A001	SEEDING (SERICEA LESPEDEZA)	25 LBS./ACRE	MARCH 1 TO SEPTEMBER 1	25 LBS./ACRE	SEPTEMBER 1 TO MARCH 1
225-A001	SEEDING (CRIMSON CLOVER)			20 LBS./ACRE	AUGUST 1 TO APRIL 1
225-C001	MULCH - VEGETATIVE MULCH	2 TONS ACRE (EST.)	MARCH 1 TO SEPTEMBER 1	2 TONS/ACRE (EST.)	SEPTEMBER 1 TO MARCH 1
216-A001	SOLID SODDING	PER SQ.YD.	MARCH 1 TO SEPTEMBER 1	PER SQ. YD.	SEPTEMBER 1 TO MARCH 1
219-A001	WATERING	20 GALS./S.Y. (EST.)	MARCH 1 TO SEPTEMBER 1	20 GALS. S.Y. (EST.)	SEPTEMBER 1 TO MARCH 1
220-A001	INSECT PEST CONTROL	PER ACRE		PER ACRE	
	TEMPORARY EROSION CONTROL ITEMS				
226-A001	LIGHT GROUND PREPARATION	PER SQ.YD.		PER SQ.YD.	
226-A001	COMBINATION FERTILIZER (13-13-13)	250 LBS./ACRE			
226-A001	SEEDING (BROWN TOP MILLET)	20 LBS./ACRE	APRIL 1 TO AUGUST 31		
226-A001	SEEDING (RYE GRASS)			25 LBS./ACRE	SEPTEMBER 1 TO MARCH 31
226-A001	SEEDING (OATS)			90 LBS./ACRE	SEPTEMBER 1 TO DECEMBER 15
226-A001	VEGETATIVE MATERIAL FOR MULCH	2 TON /ACRE (EST.)		2 TON /ACRE (EST.)	

- ALL AREAS THAT HAVE BEEN VEGETATED, UNDER THIS CONTRACT FOR AT LEAST (60) SIXTY DAYS, SHALL RECEIVE ADDITIONAL APPLICATIONS OF FERTILIZERS OF THE TYPE(S) AND RATE(S) OF APPLICATIONS AS DETERMINED BY SOIL TESTS OR AS DIRECTED DURING THE GROWING SEASONS THE CONTRACT IS IN FORCE. GROUND PREPARATION WILL NOT BE REQUIRED FOR THE ADDITIONAL APPLICATIONS. PAYMENT FOR ALL FERTILIZERS ACCEPTABLY APPLIED AS AN ADDITIONAL APPLICATION(S) WILL BE MADE IN ACCORDANCE WITH SUPERPHOSPHATE BID ITEM 213-C001.
- PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT 100% OF THE ACREAGE WILL BE SEEDED.
- PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT 50% OF THE ACREAGE WILL BE SEEDED.
- QUANTITY ESTIMATED ON THE BASIS 50% OF THE ACREAGE VEGETATED MAY REQUIRE TREATMENT.
- SOW, IN ADDITION TO OTHER SPECIFIED SEEDS, ON HIGH FILL AND BACKSLOPE AREAS SELECTED BY ENGINEERS DURING CONSTRUCTION. PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT 50% OF THE ACREAGE WILL BE SEEDED.
- THE ACTUAL RATE/ACRE TO BE DETERMINED BY SOIL TEST DURING CONSTRUCTION.

SR	9-9-24	REMOVED DESIGNER INSTRUCTIONS NOTE	BY	
		REVISION		

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
 DISTRICT 3 OR 5
 VEGETATION SCHEDULE
 RURAL - GRADE & DRAIN AND/OR BRIDGES, EXCLUDING MS DELTA

PROJ. NO.: NHPP-0056-01(105)
 COUNTY: RANKIN

FILE NAME: VS.dwg
 DESIGN TEAM: RUST
 CHECKED: _____
 DATE: _____

WORKING NUMBER
VS-1
 SHEET NUMBER
12