

**SECTION 905 -- PROPOSAL (CONTINUED)**

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. <u>  1  </u>	DATED <u>  10/17/2024  </u>	ADDENDUM NO. <u>          </u>	DATED <u>          </u>
ADDENDUM NO. <u>          </u>	DATED <u>          </u>	ADDENDUM NO. <u>          </u>	DATED <u>          </u>
ADDENDUM NO. <u>          </u>	DATED <u>          </u>	ADDENDUM NO. <u>          </u>	DATED <u>          </u>

Number	Description
1	Revised Bid Items; Revised or Added Plansheet Nos. 2, 3, 11, 13, 28 & 29; Amendment EBSx Download Required.

TOTAL ADDENDA:   1    
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE \_\_\_\_\_

\_\_\_\_\_  
Contractor

BY \_\_\_\_\_  
Signature

TITLE \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY, STATE, ZIP \_\_\_\_\_

PHONE \_\_\_\_\_

FAX \_\_\_\_\_

E-MAIL \_\_\_\_\_

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of \_\_\_\_\_ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.  
STBG-0018-02(054)/ 107012301000  
Holmes County(ies)

Revised 01/26/2016

Bridge Replacement on SR 12 over Moccasin Creek (Bridge No. 69.2), known as Federal Aid Project No. STBG-0018-02(054) / 107012301 in Holmes County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
<b>Roadway Items</b>					
0010	201-A001		1	Lump Sum	Clearing and Grubbing
0020	202-B004		301	Square Yard	Removal of Asphalt Driveways, All Depths
0030	202-B007		1,493	Square Yard	Removal of Asphalt Pavement, All Depths
0040	202-B023		1	Each	Removal of Bridge
0050	202-B051		60	Linear Feet	Removal of Concrete Curb
0060	202-B080		165	Square Yard	Removal of Concrete Sidewalk
0070	202-B136		550	Linear Feet	Removal of Guard Rail
0080	202-B191		184	Linear Feet	Removal of Pipe, 8" And Above
0090	203-EX020	(E)	1,384	Cubic Yard	Borrow Excavation, AH, FME, Class B9
0100	203-G001	(E)	3,132	Cubic Yard	Excess Excavation, FM, AH
0110	206-A001	(S)	3	Cubic Yard	Structure Excavation
0120	209-A005		1,960	Square Yard	Geotextile Stabilization, Type V, Non-Woven
0130	213-C001		2	Ton	Superphosphate
0140	216-A001		620	Square Yard	Solid Sodding
0150	217-A001		189	Square Yard	Ditch Liner
0160	219-A001		13	Thousand Gallon	Watering [\$20.00]
0170	220-A001		2	Acre	Insect Pest Control [\$30.00]
0180	221-A001	(S)	8	Cubic Yard	Concrete Paved Ditch
0190	223-A001		6	Acre	Mowing [\$50.00]
0200	225-A001		3	Acre	Grassing
0210	225-B001		7	Ton	Agricultural Limestone
0220	225-C001		6	Ton	Mulch, Vegetative Mulch
0230	226-A001		3	Acre	Temporary Grassing
0240	236-A008		2	Each	Silt Basin, Type D
0250	237-A002		500	Linear Feet	Wattles, 20"
0260	246-B001		50	Each	Rockbags
0270	304-B004	(GT)	932	Ton	Granular Material, Class 5, Group D
0280	403-A002	(BA1)	219	Ton	12.5-mm, MT, Asphalt Pavement
0290	403-A005	(BA1)	294	Ton	19-mm, MT, Asphalt Pavement
0300	403-A014	(BA1)	245	Ton	9.5-mm, MT, Asphalt Pavement
0310	406-D001		1,378	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0320	407-A001	(A2)	332	Gallon	Asphalt for Tack Coat

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	501-E001		90	Linear Feet	Expansion Joints, Without Dowels
0340	501-K001		183	Square Yard	Transverse Grooving
0350	502-A001	(C)	183	Square Yard	Reinforced Cement Concrete Bridge End Pavement
0360	601-B001	(S)	3	Cubic Yard	Class "B" Structural Concrete, Minor Structures
0370	602-A001	(S)	169	Pounds	Reinforcing Steel
0380	603-ALT006	(S)	176	Linear Feet	24" Type A Alternate Pipe
0390	603-CA026	(S)	56	Linear Feet	24" Reinforced Concrete Pipe, Class III
0400	603-CB004	(S)	1	Each	24" Reinforced Concrete End Section
0410	604-A001		547	Pounds	Castings
0420	604-B001		488	Pounds	Gratings
0430	605-AA001	(S)	50	Square Yard	Geotextile for Subsurface Drainage, Type III
0440	605-O002	(S)	89	Linear Feet	4" Perforated Sewer Pipe for Underdrains, SDR 23.5
0450	605-P002	(S)	5	Linear Feet	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5
0460	605-W001	(GY)	4	Cubic Yard	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM
0470	606-B001		150	Linear Feet	Guard Rail, Class A, Type 1
0480	606-D022		4	Each	Guard Rail, Bridge End Section, Type I
0490	606-E001		4	Each	Guard Rail, Terminal End Section
0500	608-A001	(S)	389	Square Yard	Concrete Sidewalk, Without Reinforcement
0510	609-D008	(S)	305	Linear Feet	Combination Concrete Curb and Gutter Type 3A
0530	615-A024	(S)	40	Linear Feet	Concrete Bridge End Barrier, 37.5"
0540	617-A001		23	Each	Right-of-Way Marker
0550	619-A1003		2,253	Linear Feet	Temporary Traffic Stripe, Continuous White, Paint
0560	619-A2003		2,245	Linear Feet	Temporary Traffic Stripe, Continuous Yellow, Paint
0570	619-A5002		127	Linear Feet	Temporary Traffic Stripe, Detail, Paint
0580	619-A6003		33	Square Feet	Temporary Traffic Stripe, Legend, Paint
0590	619-A6004		22	Linear Feet	Temporary Traffic Stripe, Legend, Paint
0600	619-D1001		16	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0610	619-D2001		344	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0620	619-G4001		90	Linear Feet	Barricades, Type III, Double Faced
0630	619-G7001		10	Each	Warning Lights, Type "B"
0640	620-A001		1	Lump Sum	Mobilization
0650	630-A003		9	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness
0660	630-A005		8	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness
0670	630-C005		30	Linear Feet	Square Tube Posts, 2.0 lb/ft

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0680	630-F006		16	Each	Delineators, Guard Rail, White
0690	630-G005		4	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted
0700	699-A001		1	Lump Sum	Roadway Construction Stakes
0710	815-A007	(S)	279	Ton	Loose Riprap, Size 300
0720	815-F002	(S)	57	Ton	Sediment Control Stone
0730	907-234-A001		2,300	Linear Feet	Temporary Silt Fence
0740	907-234-C001		500	Linear Feet	Super Silt Fence
0750	907-253-A001		324	Linear Feet	Coir Fiber Baffle
0760	907-413-E001		48	Linear Feet	Sawing and Sealing Transverse Joints in Asphalt Pavement
0770	907-618-A001		1	Lump Sum	Maintenance of Traffic
0780	907-619-E3001		5	Each	Changeable Message Sign
0790	907-626-C011		2,253	Linear Feet	6" Thermoplastic Double Drop Edge Stripe, Continuous White
0800	907-626-E004		2,245	Linear Feet	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow
0810	907-626-G006		127	Linear Feet	Thermoplastic Double Drop Detail Stripe, White
0820	907-626-H006		39	Square Feet	Thermoplastic Double Drop Legend, White
0830	907-626-H007		86	Linear Feet	Thermoplastic Double Drop Legend, White
0840	907-627-J001		30	Each	Two-Way Clear Reflective High Performance Raised Markers
0850	907-627-L001		28	Each	Two-Way Yellow Reflective High Performance Raised Markers
<b>ALTERNATE GROUP AA NUMBER 1</b>					
0860	304-F001	(GT)	768	Ton	3/4" and Down Crushed Stone Base
<b>ALTERNATE GROUP AA NUMBER 2</b>					
0870	304-F002	(GT)	768	Ton	Size 610 Crushed Stone Base
<b>ALTERNATE GROUP AA NUMBER 3</b>					
0880	304-F003	(GT)	768	Ton	Size 825B Crushed Stone Base
<b>ALTERNATE GROUP BB NUMBER 1</b>					
0890	605-W002	(GY)	55	Cubic Yard	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM
<b>ALTERNATE GROUP BB NUMBER 2</b>					
0900	605-W003	(GY)	55	Cubic Yard	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM
<b>Bridge Items</b>					
0910	501-K001		536	Square Yard	Transverse Grooving
0920	803-P001	(S)	810	Linear Feet	24" Steel Pipe Piling, Wall Thickness 0.500"
0930	803-P007	(S)	850	Linear Feet	18" Steel Pipe Piling, Wall Thickness 0.500"
0940	804-C199	(S)	347	Linear Feet	70' Prestressed Concrete Beam, Type FIB-36
0950	804-C213	(S)	495	Linear Feet	50' Prestressed Concrete Beam, Type MFIB-25

<b>Line No.</b>	<b>Item Code</b>	<b>Adj Code</b>	<b>Quantity</b>	<b>Units</b>	<b>Description [Fixed Unit Price]</b>
0960	805-A001	(S)	58,599	Pounds	Reinforcement
0970	805-C001	(S)	2,884	Pounds	Reinforcement, Corrosion Resistant
0980	813-A004	(S)	345	Linear Feet	Concrete Railing, 36"
0990	813-E012	(S)	172	Linear Feet	42" Pedestrian Railing
1000	815-A007	(S)	279	Ton	Loose Riprap, Size 300
1010	815-E001	(S)	3,385	Square Yard	Geotextile under Riprap
1020	907-803-B001	(S)	1	Each	Conventional Static Pile Load Test [\$5,000.00]
1030	907-803-I004	(S)	2	Each	PDA Test Pile, Steel Pipe Pile
1040	907-803-J001	(S)	2	Each	Pile Restrike
1050	907-804-A002	(S)	120	Cubic Yard	Bridge Concrete, Class AA
1060	907-804-A004	(S)	197	Cubic Yard	Bridge Concrete, Class BD
1070	907-823-A001		86	Linear Feet	Preformed Joint Seal, Type I





**ADDENDUM**


STATE	PROJECT NO.
MISS	STBG-0018-02(054)

**SUMMARY OF QUANTITIES (SHEET 2)**

PAY ITEM NO.	PAY ITEM	UNIT	HOLMES : 107012-301000	
			Prelim	Final
406-D001	Fine Milling of Bituminous Pavement, All Depths	SY	1,378	
407-A001	Asphalt for Tack Coat	GAL	332	
907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	LF	48	
501-E001	Expansion Joints, Without Dowels	LF	90	
501-K001	Transverse Grooving	SY	183	
502-A001	Reinforced Cement Concrete Bridge End Pavement	SY	183	
615-A024	Concrete Bridge End Barrier, 37.5"	LF	40	
601-B001	Class "B" Structural Concrete, Minor Structures	CY	3	
602-A001	Reinforcing Steel	LBS	169	
603-ALT006	24" Type A Alternate Pipe	LF	176	
603-CA026	24" Reinforced Concrete Pipe, Class III	LF	56	
603-CB004	24" Reinforced Concrete End Section	EA	1	
604-A001	Castings	LBS	547	
604-B001	Gratings	LBS	488	
605-AA001	Geotextile for Subsurface Drainage, Type III	SY	50	
605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	LF	89	
605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	LF	5	
605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	CY	4	
605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	CY	55	
605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	CY	55	
606-B001	Guard Rail, Class A, Type 1	LF	150	
606-D022	Guard Rail, Bridge End Section, Type I	EA	4	
606-E001	Guard Rail, Terminal End Section	EA	4	
608-A001	Concrete Sidewalk, Without Reinforcement	SY	389	
609-D008	Combination Concrete Curb and Gutter Type 3A	LF	305	
617-A001	Right-of-Way Marker	EA	23	
907-618-A001	Maintenance of Traffic	LS	1	
619-A1003	Temporary Traffic Stripe, Continuous White, Paint	LF	2,253	
619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	LF	2,245	
619-A5002	Temporary Traffic Stripe, Detail, Paint	LF	127	
619-A6003	Temporary Traffic Stripe, Legend, Paint	SF	33	
619-A6004	Temporary Traffic Stripe, Legend, Paint	LF	22	
619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	SF	16	
619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	SF	344	
907-619-E3001	Changeable Message Sign	EA	5	
619-G4001	Barricades, Type III, Double Faced	LF	90	

① INCLUDES 3 CMS BOARDS TO BE USED AT THE DISCRETION OF THE PROJECT ENGINEER



	
<b>MISSISSIPPI DEPARTMENT OF TRANSPORTATION</b> <b>SUMMARY OF QUANTITIES</b>	
UPDATED PAY ITEM NUMBERS SR	Revision 08/26/2024
PROJ NO: STBG-0018-02(054) COUNTY: HOLMES	
Working Number SQ-2	Sheet Number 11
FILENAME: SQS Design Team RUST	Checked _____ Date _____

①









