

**Call 15 Renovation of Delma Furniss Hospitality Station & Desoto Welcome Center, known as State Project Nos. BWO-2162-14(002) / 503757303 & BWO-2199-17(003) / 503757304 in Coahoma & Desoto Counties.**

- Q1. Section 01 10 00 1.01 Work covered by Contract Documents A. ....building will be vacated and site closed to public .....at the discretion of the Project Engineer. Please clarify to what extent the site will be closed.....Trying to figure what necessary security measures will be required? Will parking lots be closed? Does contractor need to make any areas accessible to current welcome center employees? 1.05 H. contractor shall be responsible for providing Full protection of all furniture and equipment REMAINING on site. will any of the furniture/ equipment be removed? Employee stated furniture had recently been delivered? Is there a place/ building to relocate to onsite? 1.08 Work restrictions will there be any restrictions? If it's closed and vacated? 03 30 00 Cast in place concrete 2.03 related materials: A. preformed expansion joint fillers..... where will these be required? Between all existing concrete and new concrete? If so are these to be sealed per 07 92 00 joint sealants 06 40 00 Architectural Woodwork to which items of work does this section apply?
- A1. The Welcome Center site will be closed to the public and MDOT will close entrance ramps to the site. The existing security guard will remain on site providing security night and day for the site. The Welcome Center building will be vacant, and no staff present during construction. It is the responsibility of the Contractor to protect any furniture/equipment remaining in the building during construction. No building on site to store furniture/equipment. No work restrictions noted. No preformed expansion joints are required, between existing and new concrete, therefore no joint sealant is required. Tool edges of new concrete slab with an edging tool.