

Construction of a Roundabout on SR 3 at Willie Morris Parkway, known as Federal Aid Project No. HSIP-0037-02(006) / 109195301 in Yazoo County.					Simmons Erosion Control, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,741,205.27					\$3,974,361.42		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	201-A001	Clearing and Grubbing	1.000	LS	98,345.00		
0020	202-B007	Removal of Asphalt Pavement, All Depths	5,644.000	SY	21.50		
0030	202-B088	Removal of Curb & Gutter, All Types	1,425.000	LF	33.00		
0040	202-B129	Removal of Flared End Section, All Sizes	6.000	EA	750.00		
0050	202-B165	Removal of Inlets, All Sizes	3.000	EA	1,000.00		
0060	202-B168	Removal of Island Pavement, All Types	477.000	SY	21.50		
0070	202-B178	Removal of Low Mast Lighting Assembly and Foundation	9.000	EA	815.00		
0080	202-B191	Removal of Pipe, 8" And Above	119.000	LF	33.00		
0090	202-B240	Removal of Traffic Stripe	200.000	LF	15.00		
0100	203-A001	Unclassified Excavation, FM, AH	694.000	CY	23.75		
0110	203-EX020	Borrow Excavation, AH, FME, Class B9	1,428.000	CY	40.00		
0120	203-G001	Excess Excavation, FM, AH	1,844.000	CY	31.00		
0130	206-A001	Structure Excavation	48.000	CY	50.00		
0140	209-A005	Geotextile Stabilization, Type V, Non-Woven	5,079.000	SY	3.50		
0150	211-B001	Topsoil for Slope Treatment, Contractor Furnished	619.000	CY	20.00		
0160	213-C001	Superphosphate	3.000	TON	900.00		
0170	216-A001	Solid Sodding	11,132.000	SY	6.00		
0180	219-A001	Watering	223.000	KGAL	20.00		
0190	220-A001	Insect Pest Control	2.000	ACRE	30.00		
0200	221-A001	Concrete Paved Ditch	28.000	CY	1,250.00		
0210	223-A001	Mowing	10.000	ACRE	50.00		
0220	225-B001	Agricultural Limestone	2.000	TON	100.00		
0230	225-C001	Mulch, Vegetative Mulch	5.000	TON	200.00		
0240	226-A001	Temporary Grassing	3.000	ACRE	1,000.00		
0250	237-A002	Wattles, 20"	231.000	LF	6.00		
0260	245-A001	Silt Dike	203.000	LF	15.00		

Construction of a Roundabout on SR 3 at Willie Morris Parkway, known as Federal Aid Project No. HSIP-0037-02(006) / 109195301 in Yazoo County.					Simmons Erosion Control, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,741,205.27					\$3,974,361.42		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	246-B002	Rockbags	203.000	LF		15.00	
0280	249-A001	Riprap for Erosion Control	158.000	TON		150.00	
0290	249-B001	Remove and Reset Riprap	79.000	CY		50.00	
0300	403-A002	12.5-mm, MT, Asphalt Pavement	1,121.000	TON		192.00	
0310	403-A005	19-mm, MT, Asphalt Pavement	295.000	TON		238.50	
0320	403-A014	9.5-mm, MT, Asphalt Pavement	863.000	TON		179.00	
0330	406-D003	Fine Milling of Bituminous Pavement, All Depths	151.000	TON		255.50	
0340	407-A001	Asphalt for Tack Coat	1,296.000	GAL		4.50	
0350	503-C010	Saw Cut, Full Depth	3,144.000	LF		10.00	
0360	601-B001	Class "B" Structural Concrete, Minor Structures	6.000	CY		3,500.00	
0370	602-A001	Reinforcing Steel	113.000	LBS		5.00	
0380	603-CA011	18" Reinforced Concrete Pipe, Class III	104.000	LF		90.25	
0390	603-CA055	36" Reinforced Concrete Pipe, Class III	16.000	LF		190.50	
0400	603-CB003	18" Reinforced Concrete End Section	6.000	EA		1,250.00	
0410	603-CB006	36" Reinforced Concrete End Section	2.000	EA		2,500.00	
0420	603-CF003	29" x 18" Concrete Arch Pipe End Section	2.000	EA		2,345.00	
0430	603-CF005	44" x 27" Concrete Arch Pipe End Section	2.000	EA		2,445.00	
0440	609-B003	Concrete Curb, Special Design	390.000	LF		65.00	
0450	609-C001	Concrete Integral Curb, Type 1	308.000	LF		42.00	
0460	609-D012	Combination Concrete Curb and Gutter Type 3A Modified	1,817.000	LF		42.50	
0470	616-A001	Concrete Median and/or Island Pavement, 10-inch	535.000	SY		80.00	
0480	616-A003	Concrete Median and/or Island Pavement, 12-inch	3,393.000	SY		90.00	
0490	616-A004	Concrete Median and/or Island Pavement, 4-inch	6,646.000	SY		40.00	
0500	618-B001	Additional Construction Signs	1.000	SF		10.00	
0510	619-A1002	Temporary Traffic Stripe, Continuous White	11,101.000	LF		1.07	
0520	619-A2002	Temporary Traffic Stripe, Continuous Yellow	4,268.000	LF		1.07	

Construction of a Roundabout on SR 3 at Willie Morris Parkway, known as Federal Aid Project No. HSIP-0037-02(006) / 109195301 in Yazoo County.					Simmons Erosion Control, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,741,205.27					\$3,974,361.42		
Ref#	Item	Item Description	Item Qty	Units	1		
0530	619-A5001	Temporary Traffic Stripe, Detail	19,228.000	LF	1.07		
0540	619-A6001	Temporary Traffic Stripe, Legend	664.000	SF	3.75		
0550	619-A6002	Temporary Traffic Stripe, Legend	286.000	LF	2.50		
0560	619-G4001	Barricades, Type III, Double Faced	96.000	LF	29.50		
0570	619-G5001	Free Standing Plastic Drums	105.000	EA	70.25		
0580	619-G7001	Warning Lights, Type "B"	39.000	EA	198.00		
0590	620-A001	Mobilization	1.000	LS	386,000.00		
0600	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	159.000	SF	34.50		
0610	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	72.000	SF	37.00		
0620	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	176.000	SF	48.50		
0630	630-C001	Square Tube Posts, 4.0 lb/ft	158.000	LF	64.00		
0640	630-C005	Square Tube Posts, 2.0 lb/ft	249.000	LF	25.50		
0650	630-D008	Structural Steel Beams, W6 x 9	62.000	LF	83.00		
0660	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	125.000	LBS	9.00		
0670	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	57.000	LF	38.50		
0680	682-A039	Underground Branch Circuit, AWG 8, 3 Conductor	3,281.000	LF	12.00		
0690	682-B037	Underground Branch Circuit, Jacked or Bored, AWG 8, 3 Conductor	157.000	LF	40.00		
0700	682-E002	Underground Junction Box	21.000	EA	2,600.00		
0710	682-F001	Secondary Power Controller	1.000	EA	21,000.00		
0720	684-A004	Pole Foundation, 30" Diameter	30.000	CY	2,075.00		
0730	699-A001	Roadway Construction Stakes	1.000	LS	197,650.00		
0740	815-F002	Sediment Control Stone	16.000	TON	150.00		
0750	907-234-A001	Temporary Silt Fence	2,500.000	LF	4.00		
0760	907-618-A001	Maintenance of Traffic	1.000	LS	336,000.00		
0770	907-619-E3001	Changeable Message Sign	4.000	EA	6,500.00		
0780	907-626-C011	6" Thermoplastic Double Drop Edge Stripe, Continuous White	4,566.000	LF	3.17		

Construction of a Roundabout on SR 3 at Willie Morris Parkway, known as Federal Aid Project No. HSIP-0037-02(006) / 109195301 in Yazoo County.					Simmons Erosion Control, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,741,205.27					\$3,974,361.42		
Ref#	Item	Item Description	Item Qty	Units	1		
0790	907-626-E004	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	748.000	LF	3.17		
0800	907-626-G006	Thermoplastic Double Drop Detail Stripe, White	1,027.000	LF	2.50		
0810	907-626-G007	Thermoplastic Double Drop Detail Stripe, Yellow	8,165.000	LF	10.00		
0820	907-626-H006	Thermoplastic Double Drop Legend, White	299.000	SF	15.00		
0830	907-626-H010	Thermoplastic Legend, White	127.000	LF	10.00		
0840	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	126.000	EA	31.50		
0850	907-630-O008	Remove and Reset Signs, Post Mounted	1.000	EA	385.00		
0860	907-683-PP001	Lighting Assembly, Per Plans	18.000	EA	7,225.00		
0870	304-F001	3/4" and Down Crushed Stone Base	5,794.000	TON			
0880	304-F002	Size 610 Crushed Stone Base	5,794.000	TON			
0890	304-F003	Size 825B Crushed Stone Base	5,794.000	TON	100.00		