

| Intersection Improvements on US 49 at SR 35, known as Federal Aid Project No. HSIP-0008-02(117) / 108247301 in Covington County. |          |   |            |       | Walters Construction Co.,<br>Inc. | T. L. Wallace Construction,<br>Inc. | Joe McGee Construction<br>Company, Inc. |
|--|----------|---|------------|-------|-----------------------------------|-------------------------------------|---|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,515,245.83   |          |   |            |       | \$2,152,544.80                    | \$2,454,949.60                      | \$2,724,809.25                          |
| Ref#   | Item     | Item Description                                  | Item Qty   | Units | 1                                 | 2                                   | 3                                       |
| 0010   | 201-B001 | Clearing and Grubbing                             | 2.000      | ACRE  | 5,500.00                          | 7,500.00                            | 5,000.00                                |
| 0020   | 201-C002 | Random Clearing and Grubbing                      | 1.000      | ACRE  | 4,500.00                          | 7,500.00                            | 5,000.00                                |
| 0030   | 202-B007 | Removal of Asphalt Pavement, All Depths           | 4,536.000  | SY    | 6.35                              | 22.00                               | 12.50                                   |
| 0040   | 202-B191 | Removal of Pipe, 8" And Above                     | 56.000     | LF    | 27.65                             | 28.00                               | 40.00                                   |
| 0050   | 202-B215 | Removal of Sign Including Post & Footing          | 13.000     | EA    | 194.25                            | 185.00                              | 55.00                                   |
| 0060   | 203-E001 | Borrow Excavation, AH, LVM, State Furnished       | 2,860.000  | CY    | 22.00                             | 25.00                               | 15.15                                   |
| 0070   | 203-G001 | Excess Excavation, FM, AH                         | 901.000    | CY    | 16.00                             | 25.00                               | 21.00                                   |
| 0080   | 209-A005 | Geotextile Stabilization, Type V, Non-Woven       | 12,780.000 | SY    | 2.50                              | 2.70                                | 4.00                                    |
| 0090   | 211-B001 | Topsoil for Slope Treatment, Contractor Furnished | 857.000    | CY    | 21.50                             | 0.01                                | 20.00                                   |
| 0100   | 213-C001 | Superphosphate                                    | 1.000      | TON   | 1,295.00                          | 1,200.00                            | 1,450.00                                |
| 0110   | 216-A001 | Solid Sodding                                     | 8,220.000  | SY    | 8.00                              | 7.05                                | 6.65                                    |
| 0120   | 219-A001 | Watering  | 164.000    | KGAL  | 20.00                             | 20.00                               | 20.00                                   |
| 0130   | 220-A001 | Insect Pest Control                               | 1.000      | ACRE  | 30.00                             | 30.00                               | 30.00                                   |
| 0140   | 223-A001 | Mowing  | 2.000      | ACRE  | 50.00                             | 50.00                               | 50.00                                   |
| 0150   | 225-A001 | Grassing  | 2.000      | ACRE  | 1,165.00                          | 1,051.00                            | 1,800.00                                |
| 0160   | 225-B001 | Agricultural Limestone                            | 4.000      | TON   | 129.50                            | 618.00                              | 180.00                                  |
| 0170   | 225-C001 | Mulch, Vegetative Mulch                           | 4.000      | TON   | 259.00                            | 790.00                              | 300.00                                  |
| 0180   | 226-A001 | Temporary Grassing                                | 2.000      | ACRE  | 1,300.00                          | 1,725.00                            | 1,200.00                                |
| 0190   | 237-A002 | Wattles, 20"                                      | 200.000    | LF    | 8.00                              | 9.30                                | 10.00                                   |
| 0200   | 245-A001 | Silt Dike   | 200.000    | LF    | 19.50                             | 0.01                                | 15.00                                   |
| 0210   | 246-A001 | Sandbags  | 200.000    | LF    | 19.50                             | 17.75                               | 20.00                                   |
| 0220   | 249-A001 | Riprap for Erosion Control                        | 80.000     | TON   | 128.25                            | 120.00                              | 125.00                                  |
| 0230   | 304-B006 | Granular Material, Class 6, Group C               | 870.000    | TON   | 33.00                             | 82.75                               | 30.00                                   |
| 0240   | 403-A003 | 12.5-mm, ST, Asphalt Pavement                     | 946.000    | TON   | 159.00                            | 147.75                              | 186.60                                  |
| 0250   | 403-A006 | 19-mm, ST, Asphalt Pavement                       | 1,891.000  | TON   | 140.00                            | 130.75                              | 157.50                                  |
| 0260   | 403-A015 | 9.5-mm, ST, Asphalt Pavement                      | 630.000    | TON   | 165.00                            | 198.00                              | 209.60                                  |

| Intersection Improvements on US 49 at SR 35, known as Federal Aid Project No. HSIP-0008-02(117) / 108247301 in Covington County. |           |  |           |       | Walters Construction Co.,<br>Inc. | T. L. Wallace Construction,<br>Inc. | Joe McGee Construction<br>Company, Inc. |
|--|-----------|--|-----------|-------|-----------------------------------|-------------------------------------|---|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,515,245.83   |           |  |           |       | \$2,152,544.80                    | \$2,454,949.60                      | \$2,724,809.25                          |
| Ref#   | Item      | Item Description   | Item Qty  | Units | 1                                 | 2                                   | 3                                       |
| 0270   | 407-A001  | Asphalt for Tack Coat  | 1,146.000 | GAL   | 4.60                              | 4.20                                | 5.45                                    |
| 0280   | 503-C010  | Saw Cut, Full Depth  | 1,693.000 | LF    | 11.25                             | 0.01                                | 7.65                                    |
| 0290   | 601-B001  | Class "B" Structural Concrete, Minor Structures                | 6.000     | CY    | 4,000.00                          | 2,500.00                            | 3,450.00                                |
| 0300   | 602-A001  | Reinforcing Steel  | 345.000   | LBS   | 2.35                              | 3.50                                | 2.40                                    |
| 0310   | 603-CA011 | 18" Reinforced Concrete Pipe, Class III                        | 32.000    | LF    | 75.30                             | 100.00                              | 100.00                                  |
| 0320   | 603-CA040 | 30" Reinforced Concrete Pipe, Class III                        | 8.000     | LF    | 195.00                            | 200.00                              | 200.00                                  |
| 0330   | 603-CB003 | 18" Reinforced Concrete End Section                            | 1.000     | EA    | 1,804.00                          | 2,000.00                            | 1,500.00                                |
| 0340   | 609-D008  | Combination Concrete Curb and Gutter Type 3A                   | 266.000   | LF    | 59.60                             | 53.75                               | 58.00                                   |
| 0350   | 616-A001  | Concrete Median and/or Island Pavement, 10-inch                | 212.000   | SY    | 155.50                            | 140.25                              | 144.65                                  |
| 0360   | 617-A001  | Right-of-Way Marker  | 7.000     | EA    | 431.00                            | 408.75                              | 425.00                                  |
| 0370   | 619-A1003 | Temporary Traffic Stripe, Continuous White, Paint              | 3,789.000 | LF    | 1.30                              | 2.65                                | 2.59                                    |
| 0380   | 619-A2003 | Temporary Traffic Stripe, Continuous Yellow, Paint             | 4,205.000 | LF    | 1.30                              | 2.65                                | 2.59                                    |
| 0390   | 619-A5002 | Temporary Traffic Stripe, Detail, Paint                        | 1,388.000 | LF    | 1.30                              | 0.20                                | 0.17                                    |
| 0400   | 619-A6001 | Temporary Traffic Stripe, Legend                               | 160.000   | SF    | 2.60                              | 0.20                                | 0.17                                    |
| 0410   | 619-A6002 | Temporary Traffic Stripe, Legend                               | 424.000   | LF    | 2.60                              | 0.15                                | 0.12                                    |
| 0420   | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 147.000   | SF    | 12.95                             | 11.75                               | 9.10                                    |
| 0430   | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More   | 521.000   | SF    | 12.95                             | 11.75                               | 9.10                                    |
| 0440   | 619-G4001 | Barricades, Type III, Double Faced                             | 54.000    | LF    | 30.00                             | 27.00                               | 19.40                                   |
| 0450   | 619-G4005 | Barricades, Type III, Single Faced                             | 318.000   | LF    | 27.20                             | 24.75                               | 17.00                                   |
| 0460   | 619-G5001 | Free Standing Plastic Drums                                    | 14.000    | EA    | 84.00                             | 76.00                               | 54.50                                   |
| 0470   | 620-A001  | Mobilization   | 1.000     | LS    | 123,500.00                        | 323,500.00                          | 275,000.00                              |
| 0480   | 630-A001  | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness      | 43.000    | SF    | 31.00                             | 28.50                               | 21.80                                   |
| 0490   | 630-A003  | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness      | 123.000   | SF    | 35.00                             | 31.75                               | 24.05                                   |
| 0500   | 630-A005  | Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness        | 53.000    | SF    | 32.40                             | 29.50                               | 22.90                                   |
| 0510   | 630-C001  | Square Tube Posts, 4.0 lb/ft                                   | 112.000   | LF    | 60.90                             | 55.25                               | 61.80                                   |
| 0520   | 630-C005  | Square Tube Posts, 2.0 lb/ft                                   | 227.000   | LF    | 25.90                             | 23.75                               | 23.30                                   |

| Intersection Improvements on US 49 at SR 35, known as Federal Aid Project No. HSIP-0008-02(117) / 108247301 in Covington County. |              |   |           |       | Walters Construction Co., Inc. | T. L. Wallace Construction, Inc. | Joe McGee Construction Company, Inc. |
|--|--------------|---|-----------|-------|--------------------------------|----------------------------------|--------------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,515,245.83   |              |   |           |       | \$2,152,544.80                 | \$2,454,949.60                   | \$2,724,809.25                       |
| Ref#   | Item         | Item Description  | Item Qty  | Units | 1                              | 2                                | 3                                    |
| 0530   | 630-G003     | Type 3 Object Markers, OM-3L, Post Mounted                                | 1.000     | EA    | 239.50                         | 214.25                           | 181.75                               |
| 0540   | 630-G007     | Type 3 Object Markers, OM-3R, Post Mounted                                | 1.000     | EA    | 239.50                         | 214.25                           | 181.75                               |
| 0550   | 635-A059     | Traffic Signal Head, Type 1   | 6.000     | EA    | 1,813.00                       | 1,635.00                         | 1,695.00                             |
| 0560   | 635-A061     | Traffic Signal Head, Type 2   | 2.000     | EA    | 1,295.00                       | 1,168.00                         | 1,210.00                             |
| 0570   | 635-A070     | Traffic Signal Head, Type 3   | 2.000     | EA    | 1,942.00                       | 1,751.00                         | 1,815.00                             |
| 0580   | 638-A003     | Flashing Assembly, Be Prepared to Stop When Flashing                      | 4.000     | EA    | 4,900.00                       | 4,436.00                         | 4,605.00                             |
| 0590   | 647-A001     | Removal of Existing Traffic Signal Equipment                              | 1.000     | LS    | 5,180.00                       | 4,670.00                         | 4,845.00                             |
| 0600   | 699-A001     | Roadway Construction Stakes   | 1.000     | LS    | 26,000.00                      | 24,600.00                        | 115,000.00                           |
| 0610   | 815-F002     | Sediment Control Stone  | 10.000    | TON   | 217.50                         | 120.00                           | 115.00                               |
| 0620   | 907-234-A001 | Temporary Silt Fence  | 1,000.000 | LF    | 7.65                           | 4.70                             | 4.25                                 |
| 0630   | 907-416-A001 | High Friction Surface Treatment   | 3,600.000 | SY    | 39.00                          | 35.50                            | 36.60                                |
| 0632   | 907-416-B001 | High Friction Surface Treatment Training                                  | 1.000     | LS    | 11,100.00                      | 10,000.00                        | 10,300.00                            |
| 0640   | 907-618-A001 | Maintenance of Traffic  | 1.000     | LS    | 95,000.00                      | 150,000.00                       | 342,500.00                           |
| 0650   | 907-626-C011 | 6" Thermoplastic Double Drop Edge Stripe, Continuous White                | 3,789.000 | LF    | 2.60                           | 4.10                             | 4.00                                 |
| 0660   | 907-626-E004 | 6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow            | 4,205.000 | LF    | 2.60                           | 4.10                             | 4.00                                 |
| 0670   | 907-626-G006 | Thermoplastic Double Drop Detail Stripe, White                            | 794.000   | LF    | 6.50                           | 11.75                            | 11.50                                |
| 0680   | 907-626-G007 | Thermoplastic Double Drop Detail Stripe, Yellow                           | 594.000   | LF    | 6.50                           | 11.75                            | 11.50                                |
| 0690   | 907-626-H006 | Thermoplastic Double Drop Legend, White                                   | 160.000   | SF    | 12.95                          | 14.25                            | 13.80                                |
| 0700   | 907-626-H007 | Thermoplastic Double Drop Legend, White                                   | 424.000   | LF    | 7.80                           | 13.50                            | 13.25                                |
| 0710   | 907-627-J001 | Two-Way Clear Reflective High Performance Raised Markers                  | 49.000    | EA    | 12.95                          | 29.25                            | 28.75                                |
| 0720   | 907-627-L001 | Two-Way Yellow Reflective High Performance Raised Markers                 | 33.000    | EA    | 12.95                          | 29.25                            | 28.75                                |
| 0730   | 907-632-A007 | Solid State Traffic Cabinet Assembly, Type III Cabinet, Type I Controller | 1.000     | EA    | 28,500.00                      | 25,700.00                        | 26,650.00                            |
| 0740   | 907-632-J001 | Power Service Pedestal  | 1.000     | EA    | 5,180.00                       | 4,670.00                         | 4,850.00                             |
| 0750   | 907-634-A107 | Traffic Signal Equipment Pole, Type II, 22' Shaft, 40' Arm                | 2.000     | EA    | 14,250.00                      | 12,900.00                        | 13,325.00                            |
| 0760   | 907-634-A115 | Traffic Signal Equipment Pole, Type II, 22' Shaft, 80' Arm                | 1.000     | EA    | 34,960.00                      | 31,600.00                        | 32,715.00                            |
| 0770   | 907-634-A117 | Traffic Signal Equipment Pole, Type II, 22' Shaft, 90' Arm                | 1.000     | EA    | 38,850.00                      | 35,100.00                        | 36,350.00                            |

| Intersection Improvements on US 49 at SR 35, known as Federal Aid Project No. HSIP-0008-02(117) / 108247301 in Covington County. |              |  |           |       | Walters Construction Co., Inc. | T. L. Wallace Construction, Inc. | Joe McGee Construction Company, Inc. |
|--|--------------|--|-----------|-------|--------------------------------|----------------------------------|--------------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,515,245.83   |              |  |           |       | \$2,152,544.80                 | \$2,454,949.60                   | \$2,724,809.25                       |
| Ref#   | Item         | Item Description   | Item Qty  | Units | 1                              | 2                                | 3                                    |
| 0780   | 907-634-C001 | Pole Foundations, Class "B" Concrete                                   | 16.000    | CY    | 1,035.00                       | 934.00                           | 970.00                               |
| 0790   | 907-636-B013 | Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 4 Conductor | 1,958.000 | LF    | 2.60                           | 2.35                             | 2.40                                 |
| 0800   | 907-636-B016 | Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor | 1,023.000 | LF    | 3.90                           | 3.50                             | 3.65                                 |
| 0810   | 907-636-B028 | Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 3 Conductor  | 78.000    | LF    | 11.65                          | 10.75                            | 10.90                                |
| 0820   | 907-637-A001 | Pullbox Enclosure, Type 1  | 4.000     | EA    | 1,425.00                       | 1,285.00                         | 1,335.00                             |
| 0830   | 907-637-A002 | Pullbox Enclosure, Type 2  | 4.000     | EA    | 1,425.00                       | 1,285.00                         | 1,335.00                             |
| 0840   | 907-637-A003 | Pullbox Enclosure, Type 3  | 1.000     | EA    | 1,813.00                       | 1,635.00                         | 1,695.00                             |
| 0850   | 907-637-C028 | Traffic Signal Conduit, Underground, Type 4, 2"                        | 212.000   | LF    | 1.30                           | 1.20                             | 1.20                                 |
| 0860   | 907-637-C030 | Traffic Signal Conduit, Underground, Type 4, 3"                        | 51.000    | LF    | 15.50                          | 14.25                            | 14.55                                |
| 0870   | 907-637-D002 | Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 2" | 1,785.000 | LF    | 12.95                          | 11.75                            | 12.15                                |
| 0880   | 907-637-D003 | Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3" | 190.000   | LF    | 38.85                          | 35.25                            | 36.35                                |
| 0890   | 907-641-A002 | Signal Stop Bar Radar Vehicle Detection Sensor, Type 2                 | 4.000     | EA    | 9,000.00                       | 8,172.00                         | 8,480.00                             |
| 0900   | 907-641-B002 | Signal Advanced Radar Vehicle Detection Sensor, Type 2                 | 2.000     | EA    | 9,700.00                       | 8,755.00                         | 9,100.00                             |
| 0910   | 907-641-D001 | Radar Vehicle Detection Cable  | 1,133.000 | LF    | 3.90                           | 3.50                             | 3.60                                 |
| 0920   | 907-650-A003 | On Street Video Equipment, PTZ Type                                    | 1.000     | EA    | 6,475.00                       | 5,837.00                         | 6,060.00                             |
| 0930   | 907-653-B001 | Street Name Sign   | 18.000    | SF    | 195.00                         | 175.25                           | 181.75                               |
| 0940   | 907-663-A001 | Network Switch, Type A   | 1.000     | EA    | 2,600.00                       | 2,335.00                         | 2,425.00                             |
| 0950   | 304-F001     | 3/4" and Down Crushed Stone Base                                       | 4,860.000 | TON   |                                |                                  |                                      |
| 0960   | 304-F002     | Size 610 Crushed Stone Base  | 4,860.000 | TON   |                                |                                  |                                      |
| 0970   | 304-F003     | Size 825B Crushed Stone Base   | 4,860.000 | TON   | 83.75                          | 82.75                            | 85.00                                |