

Mill & Overlay approximately 13 miles of SR 16 from the Neshoba County Line to east of Watkins Road & 0.30 miles of SR 39 connector from SR 39 south to SR 39 north, known as Project Nos. STP-0024-05(016) / 109445301 & STP-0074-02(016) / 109445302 in Kemper County.					Dickerson & Bowen, Inc.	Falcon Contracting Company, Inc.	APAC - Mississippi, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,928,291.76					\$5,938,835.00	\$6,045,896.00	\$6,150,472.17
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	202-B007	Removal of Asphalt Pavement, All Depths	786.000	SY	26.50	20.00	26.50
0020	202-B117	Removal of Delineator, All Types	120.000	EA	8.65	8.65	8.65
0030	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	2,175.000	LF	14.00	14.00	14.00
0040	202-B168	Removal of Island Pavement, All Types	170.000	SY	26.50	50.00	26.50
0050	202-B188	Removal of Pavement, All Types and Depths	1,000.000	SY	26.50	20.00	26.50
0060	203-G002	Excess Excavation, LVM, AH	300.000	CY	27.50	20.00	27.50
0070	209-A005	Geotextile Stabilization, Type V, Non-Woven	360.000	SY	30.00	5.00	6.50
0080	304-D002	Granular Material, Crushed Stone	3,280.000	TON	115.00	70.00	125.20
0090	403-A002	12.5-mm, MT, Asphalt Pavement	26,920.000	TON	128.00	145.00	137.66
0092	403-A005	19-mm, MT, Asphalt Pavement	100.000	TON	156.00	175.00	180.08
0100	403-A006	19-mm, ST, Asphalt Pavement	320.000	TON	156.00	175.00	182.03
0110	403-B002	12.5-mm, MT, Asphalt Pavement, Leveling	130.000	TON	171.00	175.00	269.09
0120	406-D001	Fine Milling of Bituminous Pavement, All Depths	232,432.000	SY	3.25	2.00	2.68
0130	407-A001	Asphalt for Tack Coat	23,244.000	GAL	3.40	3.25	3.30
0140	423-A001	Rumble Strips, Ground In	24.000	MI	655.00	265.00	398.59
0150	503-C010	Saw Cut, Full Depth	600.000	LF	8.00	15.00	8.00
0160	601-B001	Class "B" Structural Concrete, Minor Structures	7.000	CY	7,000.00	3,500.00	7,000.00
0170	606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	1,425.000	LF	65.00	65.00	65.00
0180	606-E005	Guard Rail, Terminal End Section, Flared	20.000	EA	4,150.00	4,150.00	4,150.00
0190	609-D003	Combination Concrete Curb and Gutter Type 2	220.000	LF	48.50	85.00	48.50
0200	619-A1002	Temporary Traffic Stripe, Continuous White	2,548.000	LF	1.00	1.00	1.00
0210	619-A2002	Temporary Traffic Stripe, Continuous Yellow	1,310.000	LF	1.00	1.00	1.00
0220	619-A4002	Temporary Traffic Stripe, Skip Yellow	13.000	MI	2,000.00	2,000.00	2,000.00
0230	619-A5001	Temporary Traffic Stripe, Detail	16,785.000	LF	1.00	1.00	1.00
0240	619-A6002	Temporary Traffic Stripe, Legend	3,080.000	LF	2.50	2.50	2.50
0250	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	865.000	SF	8.08	8.00	8.20

Mill & Overlay approximately 13 miles of SR 16 from the Neshoba County Line to east of Watkins Road & 0.30 miles of SR 39 connector from SR 39 south to SR 39 north, known as Project Nos. STP-0024-05(016) / 109445301 & STP-0074-02(016) / 109445302 in Kemper County.					Dickerson & Bowen, Inc.	Falcon Contracting Company, Inc.	APAC - Mississippi, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,928,291.76					\$5,938,835.00	\$6,045,896.00	\$6,150,472.17
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0260	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	292.000	SF	8.08	8.00	8.20
0270	619-G4001	Barricades, Type III, Double Faced	24.000	LF	23.23	23.00	23.58
0280	620-A001	Mobilization	1.000	LS	200,000.00	300,000.00	155,482.00
0290	630-F006	Delineators, Guard Rail, White	90.000	EA	30.00	30.00	30.00
0300	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	10.000	EA	150.00	150.00	150.00
0310	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	10.000	EA	150.00	150.00	150.00
0320	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	604.000	LF	8.08	5.00	8.00
0330	907-618-A001	Maintenance of Traffic	1.000	LS	125,000.00	150,000.00	213,488.23
0340	907-626-C011	6" Thermoplastic Double Drop Edge Stripe, Continuous White	2,500.000	LF	1.40	1.40	1.40
0350	907-626-C012	6" Thermoplastic Double Drop Edge Stripe, Continuous White	24.000	MI	7,200.00	7,200.00	7,200.00
0360	907-626-D003	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	5.000	MI	3,600.00	3,600.00	3,600.00
0370	907-626-E003	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	20.000	MI	7,200.00	7,200.00	7,200.00
0380	907-626-E004	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	1,250.000	LF	1.40	1.40	1.40
0390	907-626-G006	Thermoplastic Double Drop Detail Stripe, White	9,453.000	LF	3.00	3.00	3.00
0400	907-626-G007	Thermoplastic Double Drop Detail Stripe, Yellow	3,666.000	LF	3.00	3.00	3.00
0410	907-626-H006	Thermoplastic Double Drop Legend, White	147.000	SF	12.00	12.00	12.00
0420	907-626-H007	Thermoplastic Double Drop Legend, White	1,540.000	LF	6.00	6.00	6.00
0430	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	2,555.000	EA	12.00	12.00	12.00
0440	907-627-K001	Red-Clear Reflective High Performance Raised Markers	132.000	EA	12.00	12.00	12.00
0450	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,085.000	EA	12.00	12.00	12.00

Mill & Overlay approximately 13 miles of SR 16 from the Neshoba County Line to east of Watkins Road & 0.30 miles of SR 39 connector from SR 39 south to SR 39 north, known as Project Nos. STP-0024-05(016) / 109445301 & STP-0074-02(016) / 109445302 in Kemper County.					Walters Construction Co., Inc.	Superior Asphalt, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,928,291.76					\$6,162,928.55	\$7,232,821.40	
Ref#	Item	Item Description	Item Qty	Units	4	5	
0010	202-B007	Removal of Asphalt Pavement, All Depths	786.000	SY	3.00	30.00	
0020	202-B117	Removal of Delineator, All Types	120.000	EA	9.25	10.00	
0030	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	2,175.000	LF	14.95	15.00	
0040	202-B168	Removal of Island Pavement, All Types	170.000	SY	19.75	30.00	
0050	202-B188	Removal of Pavement, All Types and Depths	1,000.000	SY	6.75	0.01	
0060	203-G002	Excess Excavation, LVM, AH	300.000	CY	9.55	28.00	
0070	209-A005	Geotextile Stabilization, Type V, Non-Woven	360.000	SY	5.90	2.50	
0080	304-D002	Granular Material, Crushed Stone	3,280.000	TON	84.70	120.00	
0090	403-A002	12.5-mm, MT, Asphalt Pavement	26,920.000	TON	152.50	150.00	
0092	403-A005	19-mm, MT, Asphalt Pavement	100.000	TON	230.80	180.00	
0100	403-A006	19-mm, ST, Asphalt Pavement	320.000	TON	213.00	180.00	
0110	403-B002	12.5-mm, MT, Asphalt Pavement, Leveling	130.000	TON	180.65	225.00	
0120	406-D001	Fine Milling of Bituminous Pavement, All Depths	232,432.000	SY	2.00	3.75	
0130	407-A001	Asphalt for Tack Coat	23,244.000	GAL	4.10	3.60	
0140	423-A001	Rumble Strips, Ground In	24.000	MI	296.25	550.00	
0150	503-C010	Saw Cut, Full Depth	600.000	LF	7.15	9.00	
0160	601-B001	Class "B" Structural Concrete, Minor Structures	7.000	CY	1,975.00	7,100.00	
0170	606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	1,425.000	LF	69.40	66.00	
0180	606-E005	Guard Rail, Terminal End Section, Flared	20.000	EA	4,430.30	4,250.00	
0190	609-D003	Combination Concrete Curb and Gutter Type 2	220.000	LF	53.65	50.00	
0200	619-A1002	Temporary Traffic Stripe, Continuous White	2,548.000	LF	1.05	1.00	
0210	619-A2002	Temporary Traffic Stripe, Continuous Yellow	1,310.000	LF	1.05	1.00	
0220	619-A4002	Temporary Traffic Stripe, Skip Yellow	13.000	MI	2,135.00	2,000.00	
0230	619-A5001	Temporary Traffic Stripe, Detail	16,785.000	LF	1.05	1.00	
0240	619-A6002	Temporary Traffic Stripe, Legend	3,080.000	LF	2.60	2.50	
0250	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	865.000	SF	8.95	10.00	

Mill & Overlay approximately 13 miles of SR 16 from the Neshoba County Line to east of Watkins Road & 0.30 miles of SR 39 connector from SR 39 south to SR 39 north, known as Project Nos. STP-0024-05(016) / 109445301 & STP-0074-02(016) / 109445302 in Kemper County.					Walters Construction Co., Inc.	Superior Asphalt, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,928,291.76					\$6,162,928.55	\$7,232,821.40	
Ref#	Item	Item Description	Item Qty	Units	4	5	
0260	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	292.000	SF	8.95	10.00	
0270	619-G4001	Barricades, Type III, Double Faced	24.000	LF	25.70	25.00	
0280	620-A001	Mobilization	1.000	LS	205,000.00	600,000.00	
0290	630-F006	Delineators, Guard Rail, White	90.000	EA	32.00	30.00	
0300	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	10.000	EA	160.00	150.00	
0310	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	10.000	EA	160.00	150.00	
0320	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	604.000	LF	8.95	5.00	
0330	907-618-A001	Maintenance of Traffic	1.000	LS	80,000.00	300,000.00	
0340	907-626-C011	6" Thermoplastic Double Drop Edge Stripe, Continuous White	2,500.000	LF	1.50	1.40	
0350	907-626-C012	6" Thermoplastic Double Drop Edge Stripe, Continuous White	24.000	MI	7,686.00	7,200.00	
0360	907-626-D003	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	5.000	MI	3,845.00	3,600.00	
0370	907-626-E003	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	20.000	MI	7,686.00	7,200.00	
0380	907-626-E004	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	1,250.000	LF	1.50	1.40	
0390	907-626-G006	Thermoplastic Double Drop Detail Stripe, White	9,453.000	LF	3.20	3.00	
0400	907-626-G007	Thermoplastic Double Drop Detail Stripe, Yellow	3,666.000	LF	3.20	3.00	
0410	907-626-H006	Thermoplastic Double Drop Legend, White	147.000	SF	12.80	12.00	
0420	907-626-H007	Thermoplastic Double Drop Legend, White	1,540.000	LF	6.00	6.00	
0430	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	2,555.000	EA	12.80	12.00	
0440	907-627-K001	Red-Clear Reflective High Performance Raised Markers	132.000	EA	12.80	12.00	
0450	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,085.000	EA	12.80	12.00	