

Call 07 Bridge Repair on SR 2 over the Tuscumbia River and reliefs (Bridge Nos. 45.6, 45.7 & 45.8, known as Federal Aid Project No. STBG-0033-02(006) / 109533301 in Alcorn County.

Q1. Can we request for as-builts on this project?

A1. They can be downloaded here: <https://file-exchange.mdot.state.ms.us/dl/?f=4350bea5cef563672943ada3b5eadd2c37728dca>

Q2. Can MDOT provide a transition detail for the end of the bridge decks and the asphalt? The 1/2" overlay has caused a "bump" on previous projects getting on and off the bridge.

A2. An overlay project on this section of roadway has been let but has not yet started. We would like to coordinate the work in this area so that there is no taper placed on the bridges themselves.

Q3. The plans show concrete barriers for the Hybrid Polymer Concrete Overlay. Is this an absorbed item?

A3. See addendum.

Q4. Re: the bearing replacements - The plans show replacing the bearing pads at the end bents of Bridge #45.6, but the deck is connected to the end wall. In this case, there is really no way to jack the girders up and replace the bearings without removing the end wall. Is it actually MDOT's intent to replace these bearings or should the end bents be omitted?

A4. See addendum.