

Overlay approximately 6 miles of US 61 from Washington to the Jefferson County Line, known as Project No. NHPP-0009-01(149) / 108720301 in Adams County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,191,290.23					\$5,454,320.00		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	202-B006	Removal of Asphalt Paved Shoulders, All Depths	639.000	SY	20.50		
0020	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	1,438.000	LF	10.00		
0030	202-B240	Removal of Traffic Stripe	823.000	LF	8.00		
0040	203-G002	Excess Excavation, LVM, AH	53.000	CY	236.00		
0050	304-A008	Granular Material, LVM, Class 6, Group D	8,040.000	CY	42.00		
0060	403-A005	19-mm, MT, Asphalt Pavement	202.000	TON	210.00		
0070	403-A014	9.5-mm, MT, Asphalt Pavement	19,164.000	TON	156.00		
0080	403-B011	9.5-mm, MT, Asphalt Pavement, Leveling	1,722.000	TON	175.00		
0090	406-A002	Cold Milling of Bituminous Pavement, All Depths	1,049.000	SY	10.00		
0100	406-D001	Fine Milling of Bituminous Pavement, All Depths	21,244.000	SY	8.50		
0110	407-A001	Asphalt for Tack Coat	20,632.000	GAL	3.60		
0120	412-A001	Pre-Grinding	1.000	SF	3.25		
0130	423-A001	Rumble Strips, Ground In	23.000	MI	565.35		
0140	503-C010	Saw Cut, Full Depth	1,438.000	LF	2.50		
0150	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	850.000	LF	38.00		
0160	606-D017	Guard Rail, Bridge End Section, Type G	2.000	EA	2,813.00		
0170	606-D019	Guard Rail, Bridge End Section, Type H	6.000	EA	2,354.00		
0180	606-E005	Guard Rail, Terminal End Section, Flared	8.000	EA	4,100.00		
0190	618-B001	Additional Construction Signs	1.000	SF	10.00		
0200	619-A1001	Temporary Traffic Stripe, Continuous White	15.000	MI	1,100.00		
0210	619-A2001	Temporary Traffic Stripe, Continuous Yellow	15.000	MI	1,100.00		
0220	619-A3001	Temporary Traffic Stripe, Skip White	16.000	MI	1,100.00		
0230	619-A5001	Temporary Traffic Stripe, Detail	49,300.000	LF	0.03		
0240	619-A6001	Temporary Traffic Stripe, Legend	564.000	SF	1.00		
0250	619-A6002	Temporary Traffic Stripe, Legend	2,426.000	LF	1.00		
0260	620-A001	Mobilization	1.000	LS	455,000.00		

Overlay approximately 6 miles of US 61 from Washington to the Jefferson County Line, known as Project No. NHPP-0009-01(149) / 108720301 in Adams County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,191,290.23					\$5,454,320.00		
Ref#	Item	Item Description	Item Qnty	Units	1		
0270	630-F002	Delineators, Flexible Post Mounted, Crossover, Type I, Yellow	40.000	EA	85.00		
0280	630-F003	Delineators, Flexible Post Mounted, Crossover, Type II	12.000	EA	82.50		
0290	630-F006	Delineators, Guard Rail, White	28.000	EA	28.00		
0300	630-F007	Delineators, Guard Rail, Yellow	26.000	EA	28.00		
0310	907-618-A001	Maintenance of Traffic	1.000	LS	375,000.00		
0320	907-626-A007	6" Thermoplastic Double Drop Traffic Stripe, Skip White	13.000	MI	5,000.00		
0330	907-626-C012	6" Thermoplastic Double Drop Edge Stripe, Continuous White	12.000	MI	8,500.00		
0340	907-626-F003	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	12.000	MI	8,300.00		
0350	907-626-G004	Thermoplastic Detail Stripe, White	22,440.000	LF	2.75		
0360	907-626-G005	Thermoplastic Detail Stripe, Yellow	15,060.000	LF	2.75		
0370	907-626-H009	Thermoplastic Legend, White	498.000	SF	25.00		
0380	907-626-H010	Thermoplastic Legend, White	2,426.000	LF	10.00		
0390	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	324.000	EA	15.00		
0400	907-627-K001	Red-Clear Reflective High Performance Raised Markers	1,427.000	EA	15.00		
0410	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,377.000	EA	15.00		
0420	907-627-P001	Two-Way Blue Reflective High Performance Raised Markers	4.000	EA	25.00		
0430	304-F001	3/4" and Down Crushed Stone Base	216.000	TON			
0440	304-F002	Size 610 Crushed Stone Base	216.000	TON	118.00		
0450	304-F003	Size 825B Crushed Stone Base	216.000	TON			