

Mill & Overlay approximately 8 miles of US 98 from the end of the 5-Lane to the Bogue Chitto River, known as Federal Aid Project No. NHPP-0014-01(076) / 108718301 in Pike County.					Dickerson & Bowen, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,750,949.60					\$5,354,271.20		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	202-B006	Removal of Asphalt Paved Shoulders, All Depths	924.000	SY	30.75		
0020	202-B007	Removal of Asphalt Pavement, All Depths	51.000	SY	215.00		
0030	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	917.000	LF	5.05		
0040	203-G002	Excess Excavation, LVM, AH	86.000	CY	155.00		
0050	209-A005	Geotextile Stabilization, Type V, Non-Woven	59.000	SY	18.50		
0060	304-A008	Granular Material, LVM, Class 6, Group D	3,334.000	CY	59.50		
0070	406-A002	Cold Milling of Bituminous Pavement, All Depths	1,404.000	SY	44.00		
0080	406-D001	Fine Milling of Bituminous Pavement, All Depths	283,171.000	SY	2.75		
0090	407-A001	Asphalt for Tack Coat	21,797.000	GAL	3.50		
0100	423-A001	Rumble Strips, Ground In	29.000	MI	700.00		
0110	503-C010	Saw Cut, Full Depth	1,006.000	LF	5.37		
0120	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	450.000	LF	29.29		
0130	606-D019	Guard Rail, Bridge End Section, Type H	4.000	EA	2,121.00		
0140	606-E005	Guard Rail, Terminal End Section, Flared	4.000	EA	3,282.50		
0150	618-B001	Additional Construction Signs	1.000	SF	10.00		
0160	619-A1001	Temporary Traffic Stripe, Continuous White	29.000	MI	1,100.00		
0170	619-A2001	Temporary Traffic Stripe, Continuous Yellow	29.000	MI	1,100.00		
0180	619-A3001	Temporary Traffic Stripe, Skip White	30.000	MI	1,100.00		
0190	619-A5001	Temporary Traffic Stripe, Detail	110,058.000	LF	0.03		
0200	619-A6001	Temporary Traffic Stripe, Legend	1,395.000	SF	1.00		
0210	619-A6002	Temporary Traffic Stripe, Legend	3,352.000	LF	1.00		
0220	620-A001	Mobilization	1.000	LS	325,000.00		
0230	630-F002	Delineators, Flexible Post Mounted, Crossover, Type I, Yellow	48.000	EA	85.85		
0240	630-F003	Delineators, Flexible Post Mounted, Crossover, Type II	8.000	EA	95.95		
0250	630-F006	Delineators, Guard Rail, White	14.000	EA	28.28		
0260	630-F007	Delineators, Guard Rail, Yellow	14.000	EA	28.28		

Mill & Overlay approximately 8 miles of US 98 from the end of the 5-Lane to the Bogue Chitto River, known as Federal Aid Project No. NHPP-0014-01(076) / 108718301 in Pike County.					Dickerson & Bowen, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,750,949.60					\$5,354,271.20		
Ref#	Item	Item Description	Item Qnty	Units	1		
0270	907-403-A005	19-mm, MT, Asphalt Pavement	288.000	TON	250.00		
0280	907-403-A014	9.5-mm, MT, Asphalt Pavement	23,860.000	TON	118.00		
0290	907-618-A001	Maintenance of Traffic	1.000	LS	200,000.00		
0300	907-626-A007	6" Thermoplastic Double Drop Traffic Stripe, Skip White	15.000	MI	3,500.00		
0310	907-626-C012	6" Thermoplastic Double Drop Edge Stripe, Continuous White	14.000	MI	8,600.00		
0320	907-626-F003	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	14.000	MI	8,300.00		
0330	907-626-G004	Thermoplastic Detail Stripe, White	30,473.000	LF	3.00		
0340	907-626-G005	Thermoplastic Detail Stripe, Yellow	24,556.000	LF	2.90		
0350	907-626-H009	Thermoplastic Legend, White	697.000	SF	20.00		
0360	907-626-H010	Thermoplastic Legend, White	1,676.000	LF	10.00		
0370	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	874.000	EA	15.00		
0380	907-627-K001	Red-Clear Reflective High Performance Raised Markers	1,477.000	EA	15.00		
0390	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,694.000	EA	15.00		
0400	907-627-P001	Two-Way Blue Reflective High Performance Raised Markers	4.000	EA	150.00		
0410	304-F001	3/4" and Down Crushed Stone Base	330.000	TON			
0420	304-F002	Size 610 Crushed Stone Base	330.000	TON	162.00		
0430	304-F003	Size 825B Crushed Stone Base	330.000	TON			