

Mill & Overlay approximately 9 miles of US 51 from the Madison City Limits to Dinkins Street, known as Federal Aid Project No. STBG -6928-00(018) / 109022301 in Madison County.					APAC - Mississippi, Inc.	A J Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,394,235.78					\$8,248,905.53	\$8,677,078.92	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-D001	Random Clearing	217.000	STA	730.17	730.17	
0020	202-B006	Removal of Asphalt Paved Shoulders, All Depths	13,255.000	SY	12.13	20.00	
0030	202-B009	Removal of Asphalt Pavement, Failed Areas	893.000	SY	168.00	158.00	
0040	202-B063	Removal of Concrete Paved Ditch	70.000	SY	225.00	225.00	
0050	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	1,709.000	SY	168.00	158.00	
0060	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	3,050.000	LF	5.00	5.00	
0070	203-G001	Excess Excavation, FM, AH	250.000	CY	1.00	1.00	
0080	209-A005	Geotextile Stabilization, Type V, Non-Woven	940.000	SY	7.57	11.50	
0090	221-A001	Concrete Paved Ditch	13.000	CY	2,250.00	2,250.00	
0100	304-D002	Granular Material, Crushed Stone	1,800.000	TON	180.75	84.09	
0110	406-D001	Fine Milling of Bituminous Pavement, All Depths	207,159.000	SY	2.97	3.79	
0120	407-A001	Asphalt for Tack Coat	17,047.000	GAL	3.30	4.61	
0130	423-A001	Rumble Strips, Ground In	14.000	MI	402.01	282.15	
0140	503-C010	Saw Cut, Full Depth	11,497.000	LF	0.01	0.01	
0150	606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	2,300.000	LF	29.00	29.00	
0160	606-D019	Guard Rail, Bridge End Section, Type H	20.000	EA	2,150.00	2,150.00	
0170	606-E005	Guard Rail, Terminal End Section, Flared	20.000	EA	3,350.00	3,350.00	
0180	619-A1001	Temporary Traffic Stripe, Continuous White	35.000	MI	1,000.00	1,000.00	
0190	619-A2001	Temporary Traffic Stripe, Continuous Yellow	11.000	MI	2,000.00	2,000.00	
0200	619-A3001	Temporary Traffic Stripe, Skip White	2.000	MI	2,000.00	2,000.00	
0210	619-A4002	Temporary Traffic Stripe, Skip Yellow	15.000	MI	1,800.00	1,800.00	
0220	619-A5001	Temporary Traffic Stripe, Detail	200,757.000	LF	0.05	0.05	
0230	619-A6001	Temporary Traffic Stripe, Legend	3,340.000	SF	0.25	0.25	
0240	619-A6002	Temporary Traffic Stripe, Legend	7,072.000	LF	0.10	0.10	
0250	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	537.000	SF	10.00	6.00	
0260	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	884.000	SF	10.00	6.00	

Mill & Overlay approximately 9 miles of US 51 from the Madison City Limits to Dinkins Street, known as Federal Aid Project No. STBG -6928-00(018) / 109022301 in Madison County.					APAC - Mississippi, Inc.	A J Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,394,235.78					\$8,248,905.53	\$8,677,078.92	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	619-F3001	Delineators, Guard Rail, White	120.000	EA	27.00	27.00	
0280	619-G4005	Barricades, Type III, Single Faced	24.000	LF	20.00	21.00	
0290	620-A001	Mobilization	1.000	LS	524,000.00	637,763.50	
0300	630-G004	Type 3 Object Markers, OM-3R or OM-3L	20.000	EA	110.00	114.95	
0310	907-403-A002	12.5-mm, MT, Asphalt Pavement	22,660.000	TON	143.20	134.00	
0320	907-403-B002	12.5-mm, MT, Asphalt Pavement, Leveling	2,900.000	TON	144.10	140.00	
0330	907-403-C007	12.5-mm, HT, Asphalt Pavement, Trench Widening	3,645.000	TON	144.25	130.00	
0340	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	59,430.000	LF	2.90	2.90	
0350	907-420-A001	Undersealing	250.000	LBS	10.00	10.00	
0360	907-618-A001	Maintenance of Traffic	1.000	LS	451,000.00	954,424.63	
0370	907-619-B001	Temporary Portable Rumble Strips	132.000	LF	210.60	115.00	
0380	907-626-A007	6" Thermoplastic Double Drop Traffic Stripe, Skip White	1.000	MI	5,000.00	5,000.00	
0390	907-626-B004	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	17.000	MI	7,900.00	7,900.00	
0400	907-626-D003	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	8.000	MI	5,000.00	5,000.00	
0410	907-626-E003	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	6.000	MI	7,700.00	7,700.00	
0420	907-626-G006	Thermoplastic Double Drop Detail Stripe, White	29,109.000	LF	4.25	4.25	
0430	907-626-G007	Thermoplastic Double Drop Detail Stripe, Yellow	46,346.000	LF	4.25	4.25	
0440	907-626-H006	Thermoplastic Double Drop Legend, White	1,724.000	SF	12.00	12.00	
0450	907-626-H007	Thermoplastic Double Drop Legend, White	3,536.000	LF	9.00	9.00	
0460	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	737.000	EA	12.00	12.00	
0470	907-627-K001	Red-Clear Reflective High Performance Raised Markers	471.000	EA	12.00	12.00	
0480	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	3,434.000	EA	12.00	12.00	
0490	907-632-D001	Solid State Traffic Actuated Controller, Type 1	1.000	EA	4,000.00	4,180.00	
0500	907-643-A004	Video Vehicle Detection Sensor, Type 1A	4.000	EA	2,250.00	2,351.25	
0510	907-643-A005	Video Vehicle Detection Sensor, Type 1B	1.000	EA	3,750.00	3,918.75	
0520	907-643-B001	Video Vehicle Detection Cable	1,100.000	LF	3.00	3.14	

Mill & Overlay approximately 9 miles of US 51 from the Madison City Limits to Dinkins Street, known as Federal Aid Project No. STBG -6928-00(018) / 109022301 in Madison County.					APAC - Mississippi, Inc.	A J Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,394,235.78					\$8,248,905.53	\$8,677,078.92	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	907-643-C002	Video Vehicle Detection Processor, Type 1	2.000	EA	15,000.00	15,675.00	
0540	907-650-A004	On Street Video Equipment, PTZ Type, Signal Monitoring	2.000	EA	2,750.00	2,873.75	
0550	907-663-A001	Network Switch, Type A	2.000	EA	1,100.00	1,149.50	
0560	907-663-C002	SD-WAN Router	2.000	EA	3,750.00	3,918.75	
0570	907-808-A002	Joint Repair	1,578.000	LF	1.00	1.00	
0580	907-823-A001	Preformed Joint Seal, Type I	625.000	LF	35.00	35.00	
0590	907-823-A002	Preformed Joint Seal, Type II	123.000	LF	41.00	41.00	
0600	907-823-A003	Preformed Joint Seal, Type III	41.000	LF	50.00	50.00	
0610	907-823-B001	Saw Cut, Type I	1,250.000	LF	6.00	6.00	
0620	907-823-B002	Saw Cut, Type II	246.000	LF	6.00	6.00	
0630	907-823-B003	Saw Cut, Type III	82.000	LF	6.00	6.00	