

Call 07 Mill & Overlay approximately 4 miles of I-69 from 0.95 miles north of I-269 to 5.1 miles south of Church Road, known as Federal Aid Project No. IM-0069-04(005) / 109260301 in Desoto County.

Q1. Will 9.5 HT mix be used at the end of all ramps on the acceleration lane portion until it tapers back into traffic or will the acceleration lane be SMA and OGFC?

A1. The ramps will have OGFC on 9.5 HT.

Q2. There is not a 402-B Bituminous Tack Coat pay item on the bid schedule for the OGFC. How will that tack coat be paid for the OGFC?

A2. See Addendum 1.