

Mill & Overlay approximately 7 miles of I-20 from 5.1 miles east of SR 15 to 2.3 miles east of the Chunky River & on the Gentry Road and Experiment Station Road Overpasses, known as Federal Aid Project No. IM-0020-02(101) / 108587301 & State Project No. SP-0020-02(105) / 108587302 in Newton County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$11,417,552.08					\$12,427,290.52		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	201-D001	Random Clearing	462.000	STA	980.00		
0020	202-B009	Removal of Asphalt Pavement, Failed Areas	4.000	SY	285.00		
0030	202-B045	Removal of Cement Treated Base, All Depths	150.000	SY	35.75		
0040	202-B063	Removal of Concrete Paved Ditch	101.000	SY	75.00		
0050	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	448.000	SY	285.00		
0060	202-B129	Removal of Flared End Section, All Sizes	7.000	EA	1,500.00		
0070	202-B135	Removal of Guard Post	75.000	EA	10.35		
0080	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	16,668.000	LF	4.14		
0082	202-B165	Removal of Inlets, All Sizes	1.000	EA	2,500.00		
0090	202-B191	Removal of Pipe, 8" And Above	136.000	LF	115.00		
0100	202-B244	Removal of Trees	150.000	EA	400.00		
0110	202-B273	Removal of Debris and Sand From Box Culvert, 6-foot to Less than 10-foot Width	120.000	LF	158.00		
0120	202-B276	Removal of Debris from Drainage Channel	1,407.000	LF	158.00		
0130	203-EX008	Borrow Excavation, AH, FME, Class B15	275.000	CY	105.50		
0140	203-G002	Excess Excavation, LVM, AH	230.000	CY	100.00		
0150	221-A001	Concrete Paved Ditch	9.000	CY	2,000.00		
0160	223-A001	Mowing	672.000	ACRE	50.00		
0170	304-D002	Granular Material, Crushed Stone	3,473.000	TON	158.00		
0180	406-A002	Cold Milling of Bituminous Pavement, All Depths	6,934.000	SY	8.15		
0190	406-D001	Fine Milling of Bituminous Pavement, All Depths	297,842.000	SY	2.64		
0200	407-A001	Asphalt for Tack Coat	23,773.000	GAL	3.98		
0210	423-A001	Rumble Strips, Ground In	12.000	MI	270.00		
0220	503-A001	8" and Variable Continuously Reinforced Concrete Pavement, Broom Finish	448.000	SY	515.50		
0230	503-B001	Saw Cut, Longitudinal Joints	363.000	LF	15.00		
0240	503-C004	Saw Cut, 3-inch	740.000	LF	15.00		
0250	503-C010	Saw Cut, Full Depth	15,470.000	LF	0.01		

Mill & Overlay approximately 7 miles of I-20 from 5.1 miles east of SR 15 to 2.3 miles east of the Chunky River & on the Gentry Road and Experiment Station Road Overpasses, known as Federal Aid Project No. IM-0020-02(101) / 108587301 & State Project No. SP-0020-02(105) / 108587302 in Newton County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$11,417,552.08					\$12,427,290.52		
Ref#	Item	Item Description	Item Qty	Units	1		
0260	503-D001	Concrete for Base Repair	75.000	CY	200.00		
0270	503-E002	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted	427.000	EA	17.50		
0280	601-B001	Class "B" Structural Concrete, Minor Structures	11.000	CY	5,000.00		
0290	603-CA011	18" Reinforced Concrete Pipe, Class III	16.000	LF	400.00		
0300	603-CA026	24" Reinforced Concrete Pipe, Class III	40.000	LF	400.00		
0310	603-CA040	30" Reinforced Concrete Pipe, Class III	48.000	LF	400.00		
0320	603-CA066	42" Reinforced Concrete Pipe, Class III	16.000	LF	400.00		
0330	603-CB003	18" Reinforced Concrete End Section	1.000	EA	4,500.00		
0340	603-CB004	24" Reinforced Concrete End Section	5.000	EA	4,500.00		
0350	603-CB005	30" Reinforced Concrete End Section	1.000	EA	4,500.00		
0352	604-B001	Gratings	250.000	LBS	10.00		
0360	606-A003	Guard Posts	85.000	EA	155.25		
0370	606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	11,761.000	LF	24.84		
0380	606-B010	Guard Rail, Class A, Type 1, Thrie Beam	250.000	LF	53.82		
0390	606-B013	Guard Rail, Class A, Type 1, Thrie Beam, Transition Section	50.000	LF	20.70		
0400	606-C003	Guard Rail, Cable Anchor, Type 1	14.000	EA	1,242.00		
0410	606-D005	Guard Rail, Bridge End Section, Type A	28.000	EA	2,380.50		
0420	606-D022	Guard Rail, Bridge End Section, Type I	31.000	EA	2,846.25		
0430	606-E005	Guard Rail, Terminal End Section, Flared	63.000	EA	3,053.25		
0440	606-G002	Special Sections, Guard Rail Bridge End Connector	12.000	EA	2,583.50		
0450	606-G003	Special Sections, Special Design Bridge Connector	16.000	EA	2,070.00		
0460	619-A1001	Temporary Traffic Stripe, Continuous White	40.000	MI	1,100.00		
0470	619-A2001	Temporary Traffic Stripe, Continuous Yellow	40.000	MI	1,100.00		
0480	619-A3001	Temporary Traffic Stripe, Skip White	39.000	MI	2,000.00		
0490	619-A5001	Temporary Traffic Stripe, Detail	36,675.000	LF	0.06		
0500	619-A6002	Temporary Traffic Stripe, Legend	1,920.000	LF	1.00		

Mill & Overlay approximately 7 miles of I-20 from 5.1 miles east of SR 15 to 2.3 miles east of the Chunky River & on the Gentry Road and Experiment Station Road Overpasses, known as Federal Aid Project No. IM-0020-02(101) / 108587301 & State Project No. SP-0020-02(105) / 108587302 in Newton County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$11,417,552.08					\$12,427,290.52		
Ref#	Item	Item Description	Item Qty	Units	1		
0510	619-C6001	Red-Clear Reflective High Performance Raised Marker	2,100.000	EA	9.00		
0520	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	32.000	SF	10.25		
0530	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	200.000	SF	10.25		
0540	619-G4005	Barricades, Type III, Single Faced	48.000	LF	21.53		
0550	620-A001	Mobilization	1.000	LS	953,000.00		
0560	630-F006	Delineators, Guard Rail, White	364.000	EA	31.05		
0570	630-F007	Delineators, Guard Rail, Yellow	146.000	EA	31.05		
0580	630-F010	Delineators, Post Mounted, Double White	78.000	EA	56.93		
0590	630-F011	Delineators, Post Mounted, Double Yellow	26.000	EA	56.93		
0600	630-F012	Delineators, Post Mounted, Single White	28.000	EA	46.58		
0610	630-F013	Delineators, Post Mounted, Single Yellow	16.000	EA	46.58		
0620	630-G004	Type 3 Object Markers, OM-3R or OM-3L	76.000	EA	103.50		
0622	805-A001	Reinforcement	161.000	LBS	7.50		
0630	815-A002	Loose Riprap, Size 100	104.000	TON	225.00		
0640	815-E001	Geotextile under Riprap	300.000	SY	8.75		
0650	907-402-A002	Open Graded Friction Course, 9.5-mm Mixture	9,757.000	TON	189.00		
0660	907-402-B001	Bituminous Tack Coat	24,257.000	GAL	3.98		
0670	907-403-A001	12.5-mm, HT, Asphalt Pavement	731.000	TON	163.00		
0680	907-403-A015	9.5-mm, ST, Asphalt Pavement	5,186.000	TON	165.00		
0690	907-403-B004	19-mm, HT, Asphalt Pavement, Leveling	207.000	TON	400.00		
0700	907-403-S001	Joint Sealant	27.000	MI	2,260.00		
0710	907-405-A001	Stone Matrix Asphalt, 9.5 mm Mixture	18,556.000	TON	172.00		
0720	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	5,400.000	LF	3.50		
0730	907-618-A001	Maintenance of Traffic	1.000	LS	500,000.00		
0740	907-626-A007	6" Thermoplastic Double Drop Traffic Stripe, Skip White	13.000	MI	4,400.00		
0750	907-626-B004	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	14.000	MI	8,600.00		

Mill & Overlay approximately 7 miles of I-20 from 5.1 miles east of SR 15 to 2.3 miles east of the Chunky River & on the Gentry Road and Experiment Station Road Overpasses, known as Federal Aid Project No. IM-0020-02(101) / 108587301 & State Project No. SP-0020-02(105) / 108587302 in Newton County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$11,417,552.08					\$12,427,290.52		
Ref#	Item	Item Description	Item Qty	Units	1		
0760	907-626-E003	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	14.000	MI	8,400.00		
0770	907-626-G006	Thermoplastic Double Drop Detail Stripe, White	12,225.000	LF	6.00		
0780	907-626-G007	Thermoplastic Double Drop Detail Stripe, Yellow	2,400.000	LF	6.00		
0790	907-626-H007	Thermoplastic Double Drop Legend, White	960.000	LF	9.00		
0800	907-627-K001	Red-Clear Reflective High Performance Raised Markers	2,100.000	EA	15.00		
0810	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	20.000	EA	15.00		
0818	907-808-A002	Joint Repair	3,712.000	LF	15.00		
0820	907-808-A003	Joint Repair Without Epoxy	5,792.000	LF	1.00		
0830	907-823-A001	Preformed Joint Seal, Type I	4,752.000	LF	35.00		
0840	907-823-B001	Saw Cut, Type I	7,840.000	LF	6.00		
0850	907-824-A003	General Epoxy Repair	30.000	SF	400.00		