SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. ADDENDUM NO ADDENDUM NO		DATED DATED DATED	4/17/2025	ADDENDUM NO. ADDENDUM NO. ADDENDUM NO.	DATED DATED DATED	3		
Number 1 Revised Table of Cor No. 6816; Added S Progress Schedule; A	SP 907-701-	ed NTB No. 68 ⁻ 4, W/ Supplei	ment; Revised	TOTAL ADDENDA: (Must agree with total ad Respectfully Submitted, DATE		ening of b	oids)	
				BY	Contractor Signature			
			-9	ADDRESS CITY, STATE, ZIP PHONE				
			Oll	FAXE-MAIL				
(To be filled in if a corpo Our corporation is charter titles and business addres	red under th					and	the	names,
Pr	esident				Address			
Se	cretary	•			Address			
Tr	easurer				Address			

The following is my (our) itemized proposal.

MP-1350-71(004)/ 309569301000

Tishomingo County(ies)

Revised 01/26/2016

MISSISSIPPI DEPARTMENT OF TRANSPORTATION TABLE OF CONTENTS

PROJECT: MP-1350-71(004)/309569301 - Tishomingo

Section 901 - Advertisement

Section 904 - Notice to	o Bidders
#1	Governing Specification, w/ Supplement
#3	Final Cleanup
#13	Safety Edge
#296	Reduced Speed Limit Signs
#445	Mississippi Agent or Qualified Nonresident Agent
#447	Traffic on Milled Surface in Rural Areas
#516	Errata and Modifications to the 2017 Standard Specifications
#1225	Early Notice to Proceed
#1226	Material Storage Under Bridges
#1241	Fuel and Material Adjustments
#1963	Guardrail Pads
#2206	MASH Compliant Devices
#2273	Mississippi Special Fuel Tax Law
#2954	Reflective Sheeting for Signs
#3676	Asphalt Gyratory Compactor Internal Angle Calibration
#4702	App for Traffic Control Report
#5086	Detail of Square Tube Sign Posts
#5551	Federal Bridge Formula
#5750	Manual on Uniform Traffic Control Devices (MUTCD)
#6813	Contract Time
#6815	Temporary Transverse Joints
#6816	Pay Item Correction
Section 907 - Special 1	
907-101-1	Definitions and Terms
907-102-2	Bidding Requirements and Conditions
907-103-2	Award and Execution of Contract
907-105-2	Control of Work
907-108-4	Subletting of Contract
907-108-6	Default and Termination of Contract
907-109-5	Measurement and Payment
907-204-1	Geogrid
907-401-2	Asphalt Pavements - General
907-403-4	Asphalt Pavements
907-618-12	Traffic Control Management
907-619-6	Temporary Portable Rumble Strips
907-626-11	Thermoplastic Markings
907-627-1	Raised Pavement Markings
907-701-4	Hydraulic Cement, w/ Supplement
907-702-4	Bituminous Materials
907-703-2	Gradation
907-705-1	Stone Riprap

PROJECT: MP-1350-71(004)/309569301 - Tishomingo

907-707-3	Joint Materials
907-711-2	Plain Steel Wire
907-712-1	Fence and Guardrail
907-714-3	Miscellaneous Materials
907-718-1	Timber and Dimension Lumber
907-720-3	Pavement Marking Materials
907-721-4	Materials for Signing

Section 905 - Proposal, Proposal Bid Items, Combination Bid Proposal State Board of Contractors Requirement State Certification Regarding Non-Collusion, Debarment and Suspensions

Section 902 - Contract Form

Section 903 - Contract Bond Forms

Progress Schedule

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET OF SECTION 905 AS ADDENDA)
04/17/2025 09:36 AM

SECTION 904 - NOTICE TO BIDDERS NO. 6813 CODE: (SP)

DATE: 04/17/2025

SUBJECT: Contract Time

PROJECT: MP-1350-71(004)/309569301—Tishomingo County

The completion of work to be performed by the Contractor for this project will not be a specified date but shall be when all allowable working days are assessed, or any extension thereto as provided in Subsection 108.06. It is anticipated that the Notice of Award will be issued no later than May 13, 2025 and the date for Notice to Proceed / Beginning of Contract Time will be June 12, 2025.

Should the Contractor request a Notice to Proceed earlier than <u>June 12, 2025</u> and it is agreeable with the Department for an early Notice to Proceed, the requested date will become the new Notice to Proceed date. Regardless of whether or not an early Notice to Proceed is granted, contract time will start at the original Notice to Proceed date.

All requests for an early Notice to Proceed shall be sent to the Project Engineer who will forward it to the Contract Administration Division.

88 Working Days have been allowed for the completion of work on this project.

CODE: (SP)

SECTION 904 - NOTICE TO BIDDERS NO. 6816

DATE: 04/16/2025

SUBJECT: Pay Item Correction

PROJECT: MP-1350-71(004) / 309569301 – Tishomingo County

Bidders are hereby advised that Mobilization is shown on the Summary of Quantities in the Contract Plans as having Pay Item No. 907-620-A001 and having a unit of "EA". This is in error. The correct Pay Item No. is 620-A001, and the correct unit is "Lump Sum". The bid sheets are correct.

SUPPLEMENT TO SPECIAL PROVISION NO. 907-701-4

DATE: 11/05/2024

SUBJECT: Hydraulic Cement

907-701.04--Blended Hydraulic Cement.

<u>907-701.04.1--Types of Blended Hydraulic Cement</u>. After the last paragraph of Subsection 907-701.04.1 on page 1, add the following.

Blended cement Types IL meeting the "HE" high early strength requirement listed in AASHTO M 240, Table 3 shall have the "(HE)" suffix added to the type designation.

CODE: (IS)

SPECIAL PROVISION NO. 907-701-4

DATE: 11/21/2023

SUBJECT: Hydraulic Cement

Section 701, Hydraulic Cement, of the 2017 Edition of the Mississippi Standard Specifications for Road and Bridge Construction is hereby amended as follows.

<u>907-701.01--General</u>. In the first sentence of the second paragraph of Subsection 701.01 on page 718, change "mills" to "plants."

In the second sentence of the sixth paragraph of Subsection 701.01 on pages 718 and 719, change "shall" to "will."

<u>907-701.02--Portland Cement.</u>

907-701.02.1-General. Delete Subsections 701.02.1.1, 701.02.1.2, 701.02.2, 701.02.2.1, and 701.02.2.2 on pages 719 and 720, and substitute the following.

907-701.02.1.1--Types of Portland Cement. Portland cement shall be either Type I, Type II, or Type III conforming to AASHTO M85 or Type III (MS). Type III (MS) is defined as a Type III cement conforming to AASHTO M85 having a maximum tricalcium aluminate (C₃A) content of 8%.

907-701.02.2--Blank.

907-701.02.2.1--Blank.

907-701.02.2.2--Blank.

Delete Subsection 701.04 on pages 720 and 721, and substitute the following.

907-701.04--Blended Hydraulic Cement.

<u>907-701.04.1--Types of Blended Hydraulic Cement.</u> Blended hydraulic cements (blended cements) shall be of the following types and conform to AASHTO M 240:

Type IL – Portland-limestone cement

Type IP - Portland-pozzolan cement

Type IS – Portland blast-furnace slag cement

Blended cement Types IL, IP, and IS meeting the "MS" sulfate resistance requirement listed in AASHTO M 240, Table 3 shall have the "(MS)" suffix added to the type designation.

FORM C: Rev. 1/2	FORM CSD-612 Rev. 1 / 2015													3							
NORK	WORK PHASE DESCRIPTION	LINE NUMBERS	JAN FEB	B MAR	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER C	OCTOBER	NOV DEC JA	DEC JAN FEB MAR	R APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER OCTOBER	NOV	DEC
Misc	Miscellaneous	20-60, 110-270, 300-310, 420-440					6				88										
Clearing	ring	10					s	97													
Pave	Pavement	70-90, 280-290						26			80										
Pavement Markings	ment ings	100, 320-410								08	88 .										
	Ë	April 22, 2025																			
	NOA:	May 13, 2025																			
	NTP/BCT:	June 12, 2025																			
	W.D.:	88																			
		MONTH	JAN FE	JAN FEB MAR	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER OCTOBER		NOV DEC JAN FEB	AN FEB MAR	R APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER OCTOBER	Š.	DEC WORKING
P	NTICIPATED WA	ANTICIPATED WORKING DAYS PER MONTH	2 9	7	45	40	ç	2.5													Г

NOTE: THE ANTICIPATED WORKING DAYS SHOWN ON THIS SCHEDULE ARE FOR INFORMATIONAL PURPOSES ONLY. THE ACTUAL WORKING DAY TOTAL AS ASSESSED BY THE PROJECT ENGINEER ON FORM CSD-765 SHALL GOVERN.