

Bridge Repair on US 80 over Pearl River Relief (Bridge No. 46.9), known as Federal Aid Project No. NHPP-7314-01(007) / 109500301 in Rankin County.					Key, LLC		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,160,637.74					\$2,130,269.00		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	247.000	SY	20.00		
0020	202-B029	Removal of Bridge End Pavement	100.000	SY	49.00		
0030	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	100.000	SY	49.00		
0040	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	330.000	LF	7.00		
0050	202-B215	Removal of Sign Including Post & Footing	4.000	EA	690.00		
0060	203-G002	Excess Excavation, LVM, AH	45.000	CY	98.00		
0070	209-A001	Geotextile Stabilization, Type III	27.000	SY	5.00		
0080	209-A005	Geotextile Stabilization, Type V, Non-Woven	220.000	SY	5.00		
0090	221-A001	Concrete Paved Ditch	1.000	CY	3,000.00		
0100	304-D002	Granular Material, Crushed Stone	75.000	TON	126.00		
0110	407-A001	Asphalt for Tack Coat	15.000	GAL	11.00		
0120	503-A007	6" and Variable Jointed Concrete Pavement	100.000	SY	350.00		
0130	503-C010	Saw Cut, Full Depth	375.000	LF	21.00		
0140	605-T002	6" Perforated Pipe for Underdrains	48.000	LF	120.00		
0150	605-U002	6" Non-perforated Pipe for Underdrains	5.000	LF	120.00		
0160	605-X002	Filter Material for Filter Beds, Type A	2.000	CY	885.00		
0170	606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	325.000	LF	29.00		
0180	606-D003	Guard Rail, Bridge End Section, Special Design	3.000	EA	2,180.00		
0190	606-E001	Guard Rail, Terminal End Section	3.000	EA	3,760.00		
0200	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	1,700.000	LF	0.55		
0210	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	1,700.000	LF	0.55		
0220	619-A3004	Temporary Traffic Stripe, Skip White, Paint	1,700.000	LF	0.55		
0230	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	16.000	SF	9.00		
0240	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	164.000	SF	9.00		
0250	619-G4001	Barricades, Type III, Double Faced	108.000	LF	25.00		
0260	619-G4005	Barricades, Type III, Single Faced	24.000	LF	23.00		

Bridge Repair on US 80 over Pearl River Relief (Bridge No. 46.9), known as Federal Aid Project No. NHPP-7314-01(007) / 109500301 in Rankin County.					Key, LLC		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,160,637.74					\$2,130,269.00		
Ref#	Item	Item Description	Item Qnty	Units	1		
0270	619-G7001	Warning Lights, Type "B"	9.000	EA	165.00		
0280	620-A001	Mobilization	1.000	LS	210,000.00		
0290	630-F006	Delineators, Guard Rail, White	12.000	EA	33.00		
0300	630-G004	Type 3 Object Markers, OM-3R or OM-3L	4.000	EA	92.00		
0310	699-A001	Roadway Construction Stakes	1.000	LS	21,000.00		
0320	907-403-A002	12.5-mm, MT, Asphalt Pavement	17.000	TON	600.00		
0330	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	375.000	LF	6.00		
0340	907-502-A001	Reinforced Cement Concrete Bridge End Pavement	100.000	SY	800.00		
0350	907-618-A001	Maintenance of Traffic	1.000	LS	49,000.00		
0360	907-618-M2001	Work Zone Law Enforcement	200.000	HRS	60.00		
0370	907-619-E3001	Changeable Message Sign	5.000	EA	5,900.00		
0380	907-626-A008	6" Thermoplastic Double Drop Traffic Stripe, Skip White	850.000	LF	3.50		
0390	907-626-B003	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	850.000	LF	4.50		
0400	907-626-E004	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	850.000	LF	4.50		
0410	907-627-K001	Red-Clear Reflective High Performance Raised Markers	18.000	EA	81.00		
0420	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	18.000	EA	81.00		
0430	503-C001	Saw Cut, 1-inch	118.000	LF	12.00		
0440	805-A001	Reinforcement	1,132.000	LBS	12.00		
0450	907-804-A002	Bridge Concrete, Class AA	10.000	CY	4,800.00		
0460	907-808-A003	Joint Repair Without Epoxy	720.000	LF	1.50		
0470	907-823-A001	Preformed Joint Seal, Type I	360.000	LF	53.00		
0480	907-823-B001	Saw Cut, Type I	720.000	LF	8.00		
0490	907-824-A003	General Epoxy Repair	209.000	SF	1,300.00		
0500	907-824-C001	Cap Cleaning	9.000	EA	2,050.00		
0510	907-824-PP004	Bridge Repair, Concrete Girder Span Resetting, Per Plans	1.000	LS	160,000.00		
0520	907-824-PP006	Bridge Repair, Beam Hanger Assembly (Exterior)	16.000	EA	15,450.00		

Bridge Repair on US 80 over Pearl River Relief (Bridge No. 46.9), known as Federal Aid Project No. NHPP-7314-01(007) / 109500301 in Rankin County.					Key, LLC		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,160,637.74					\$2,130,269.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0530	907-824-PP006	Bridge Repair, Beam Hanger Assembly (Interior))	24.000	EA	12,920.00		
0540	907-824-PP006	Bridge Repair, Install Bearings, Per Plans	14.000	EA	4,000.00		
0550	907-824-PP007	Bridge Repair, Deck, Curb, and Sidewalk Removal and Replacement	4.000	CY	4,800.00		
0560	907-824-PP008	Bridge Repair, Class II, spray Finish, Per Plans	756.000	LF	11.00		
0570	907-824-PP008	Bridge Repair, Rail Repair	7.000	LF	1,200.00		
0580	907-824-PP008	Bridge Repair, Rail, Curb, and End Post Cleaning, Per Plans	756.000	LF	31.00		
0590	907-824-PP008	Bridge Repair, Remove End Bent Endwall, Per Plans	58.000	LF	485.00		
0600	907-828-A001	Hybrid Polymer Concrete Overlay	37.000	CY	9,100.00		