

Mill & Overlay approximately 7 miles of SR 350 from the Alcorn County Line to SR 25, known as State Project No. MP-1350-71(004) / 309569301 in Tishomingo County.					WG Construction Company, Inc.	Cook & Son, LLC	APAC - Mississippi, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,233,174.57					\$2,887,757.50	\$3,169,048.52	\$3,304,340.78
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0010	201-D001	Random Clearing	30.000	STA	1,000.00	2,666.67	1,000.00
0020	202-B007	Removal of Asphalt Pavement, All Depths	1,120.000	SY	35.00	20.00	39.79
0030	202-B215	Removal of Sign Including Post & Footing	5.000	EA	50.00	130.00	136.13
0040	202-B240	Removal of Traffic Stripe	3,330.000	LF	4.00	4.00	4.00
0050	203-G001	Excess Excavation, FM, AH	750.000	CY	28.00	50.00	29.06
0060	209-A009	Geotextile Stabilization, Type VII, Non-Woven	1,120.000	SY	7.00	5.00	10.47
0070	304-A002	Granular Material, LVM, Class 3, Group C	2,005.000	CY	47.50	40.00	47.50
0080	406-D001	Fine Milling of Bituminous Pavement, All Depths	117,950.000	SY	2.10	1.56	2.02
0090	407-A001	Asphalt for Tack Coat	9,300.000	GAL	3.25	4.00	4.42
0100	423-A001	Rumble Strips, Ground In	14.000	MI	500.00	270.00	282.72
0110	503-C010	Saw Cut, Full Depth	1,192.000	LF	8.50	10.00	1.05
0120	606-D017	Guard Rail, Bridge End Section, Type G	12.000	EA	3,500.00	3,500.00	3,664.92
0130	606-E001	Guard Rail, Terminal End Section	12.000	EA	3,750.00	3,750.00	3,926.70
0140	606-F002	Guard Rail, Remove and Replace Guard Rail, Blockouts & Posts	1,500.000	LF	32.00	32.00	33.51
0150	618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	10.00
0160	619-A1001	Temporary Traffic Stripe, Continuous White	28.000	MI	2,400.00	2,400.00	2,400.00
0170	619-A2001	Temporary Traffic Stripe, Continuous Yellow	11.000	MI	2,400.00	2,400.00	2,400.00
0180	619-A4002	Temporary Traffic Stripe, Skip Yellow	12.000	MI	2,400.00	2,400.00	2,400.00
0190	619-A5001	Temporary Traffic Stripe, Detail	1,470.000	LF	1.00	1.00	1.00
0200	619-A6001	Temporary Traffic Stripe, Legend	82.000	SF	3.00	3.00	3.00
0210	619-A6002	Temporary Traffic Stripe, Legend	330.000	LF	2.00	2.00	2.00
0220	620-A001	Mobilization	1.000	LS	145,000.00	250,378.42	360,000.00
0230	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	4.000	SF	30.00	27.00	28.27
0240	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	36.000	SF	32.00	29.00	30.37
0250	630-C005	Square Tube Posts, 2.0 lb/ft	65.000	LF	20.00	23.00	24.08
0260	630-F006	Delineators, Guard Rail, White	66.000	EA	25.00	30.00	31.41

Mill & Overlay approximately 7 miles of SR 350 from the Alcorn County Line to SR 25, known as State Project No. MP-1350-71(004) / 309569301 in Tishomingo County.					WG Construction Company, Inc.	Cook & Son, LLC	APAC - Mississippi, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,233,174.57					\$2,887,757.50	\$3,169,048.52	\$3,304,340.78
Ref#	Item	Item Description	Item Qnty	Units	1	2	3
0270	907-204-A003	Geogrid, Type II, Biaxial	1,120.000	SY	7.00	10.00	10.47
0280	907-403-A005	19-mm, MT, Asphalt Pavement	775.000	TON	220.00	408.00	224.00
0290	907-403-A014	9.5-mm, MT, Asphalt Pavement	10,225.000	TON	138.00	143.00	139.00
0300	907-618-A001	Maintenance of Traffic	1.000	LS	95,000.00	65,000.00	270,000.00
0310	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	100.00	500.00	210.00
0320	907-626-B006	6" Thermoplastic Traffic Stripe, Continuous White	15.000	MI	8,500.00	8,500.00	8,500.00
0330	907-626-D005	6" Thermoplastic Traffic Stripe, Skip Yellow	6.000	MI	4,500.00	4,500.00	4,500.00
0340	907-626-E005	6" Thermoplastic Traffic Stripe, Continuous Yellow	6.000	MI	8,500.00	8,500.00	8,500.00
0350	907-626-G004	Thermoplastic Detail Stripe, White	1,290.000	LF	5.00	5.00	5.00
0360	907-626-G005	Thermoplastic Detail Stripe, Yellow	180.000	LF	5.00	5.00	5.00
0370	907-626-H009	Thermoplastic Legend, White	815.000	SF	12.00	12.00	12.00
0380	907-626-H010	Thermoplastic Legend, White	440.000	LF	7.00	7.00	7.00
0390	907-627-J001	Two-Way Clear Reflective High Performance Raised Markers	125.000	EA	15.00	15.00	15.00
0400	907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	720.000	EA	15.00	15.00	15.00
0410	907-627-M001	One-Way Clear Reflective High Performance Raised Markers	615.000	EA	15.00	15.00	15.00
0420	304-H001	3/4" and Down Crushed Stone Base, LVM	425.000	CY		100.00	
0430	304-H002	Size 610 Crushed Stone Base, LVM	425.000	CY	90.00		78.53
0440	304-H003	Size 825B Crushed Stone Base, LVM	425.000	CY			